



المنطقة الخامسة - (غرب الدلتا)

السيد المهندس / نائب رئيس الهيئة للتنفيذ والمناطق

تحية طيبة.. وبعد،،

بالإحالة إلى مشروع القطار الكهربائي فائق السرعة (فوكا - مطروح) (القطاع السابع)
نتشرف بأن نرفق لسيادتكم طيه المقاييس المعدلة للقطاعات الأتية:

مسلسل	اسم الشركة	بداية القطاع (كم)	نهاية القطاع (كم)	اتجاه
١	شركة القاهرة للطرق والإنشاءات	٥٢١+٠٠٠	٥٢٢+٠٠٠	النجيلة

برجاء من سيادتكم التفضل بالأحاطه والتوجيه بالازم

وذلك لصالح بدء اجراءات التعاقد طبقا لأوامر الأسناد الصادرة للشركة.

وتفضلوا بقبول فائق الاحترام والتقدير،،

رئيس الإدارة المركزية
المنطقة الخامسة- غرب الدلتا

عميد مهندس /
"هاني محمد محمود طه"



القاهرة للطرق والإنشاءات



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل



شركة القطار الكهربائي السريع
Electric Express Train
SYSTRA SHAKER



الهيئة العامة للطرق والجسور والنقل البري
General Authority For Roads, Bridges And Land Transport
(GARBLT)



وزارة النقل
MINISTRY OF TRANSPORT
AND URBAN PLANNING

مشروع القطار الكهربائي السريع
المقايضة المعدلة لبنود الاعمال بعد التفاوض بتاريخ (18/12/2023) للقطاع السابع (فوكا - مطروح) - شركة القاهرة للطرق والإنشاءات - النجيلة
القطاع من المحطة 521+000 إلى المحطة 522+000

رقم البند	بيان الأعمال	الوحدة	الكمية	الفئة	الاجمالي
1	أعمال الازالة و التطهير				
1-1	بالمتر المسطح اعمال تطهير الموقع من الاشجار والمزروعات والمخلفات في مناطق الدلتا ذات الطبيعة الزراعية الكثيفة والتخلص منها بالمقابل العمومية تمهيدا لاعمال الرفع المساحي لكامل حدود المشروع طبقا للشروط والمواصفات وتعليمات المهندس المشرف.	م ²	26,700.00	5.00	133,500.00
2	أعمال الحفر				
2-2	بالمتر المكعب اعمال حفر باستخدام المعدات الميكانيكية في التربة المتماسكة عدا التربة الصخرية (باستخدام البلدوزر) وتسوية السطح بالالت التسوية والرش بالمياه الاصلوية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى اقصى كثافة جافة (95% من الكثافة الجافة القصوى) ومحمل على البند تحميل ونقل التربة الزائدة لمسافة 500 متر من محور الطريق ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا لاصول الصناعة ومواصفات الهيئة العامة للطرق والكبارى وتعليمات المهندس المشرف. يتم احتساب علاوة 1.1 جنيه لكل 1 كم بالزيادة.	م ³	39,000.00	28.80	1,123,200.00
3	السعر طبقا لمفاوضة فبراير 2023				
3-1	أعمال الردم				
3-1	بالمتر المكعب اعمال توريد وتشغيل اترية صالحة للردم و مطابقة للمواصفات والتشغيل باستخدام الات التسوية بسمك لا يزيد عن 50 سم حتى منسوب 2- متر و بسمك لا يزيد عن 25 سم لاستكمال المنسوب التصميمي لتشكيل الجسر والاكتاف (نسبة تحمل كالفورنيا لا تقل عن 15%) و رشها بالمياه الاصلوية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى اقصى كثافة جافة (95% من الكثافة الجافة القصوى) ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا لاصول الصناعة ومواصفات الهيئة العامة للطرق والكبارى وتعليمات المهندس المشرف. في حالة طلب جهاز الإشراف زيادة نسبة الدمك عن 95 % بحسب زيادة 1 جنية علي زيادة نسبة الدمك لكل 1 % - مسافة النقل 2 كم ويتم احتساب علاوة 1.5 جنيه لكل 1 كم بالزيادة أو النقصان - السعر يشمل عمل تشوينات وتخليط واختيارات ونقل لموقع العمل حتي مسافة 2 كم - السعر يشمل قيمة المادة المحجربة	م ³	41,599.00	97.50	4,055,902.50
	السعر طبقا لمفاوضة فبراير 2023	م ³	41,599.00	339.00	14,102,061.00
	علاوة مسافة النقل 228 كم	م ³	41,599.00	13.00	540,787.00
	علاوة تحصيل رسوم الكارثة والموازين طبقا للائحة الشركة الوطنية	م ³	41,599.00		19,955,450.50
	الإجمالي				

(تسعة عشر مليوناً و تسعمائة وخمسة وخمسون الفا وربعمائة وخمسون جنيها وخمسون قرشا لاغير)

مدير عام المشروعات
م/ محمد حسني فياض

رئيس الإدارة المركزية
منطقة غرب الدلتا
الاسكندرية - منسي مطروح
عميد مهندس /
هاني محمد محمود طه "

مدير المشروع المالك
م / إبراهيم عبد الله الحناوي

مدير المشروع الاستشاري
م / خالد فوزي السيد

مدير المشروع العقول
م / محمد ضيف الله عبد الحافظ

شركة الطرق والإنشاءات
١٠٦٧٠٥
٥٤٥ - ٥٩٢ - ٥٤٥



قائمة الكميات الواردة بالمستخلص جارى (2)

عملية : اسناد أعمال الجسر الترابي لمسارالقطار الكهربائي السريع الخط الاول (العين السخنة -العلمين)(قطاع فوكة / مطروح) لتنفيذ أعمال تشكيل الجسور
المسافة من الكم 521+000 الى الكم 522+000 بطول 1 كم اتجاه النجيلة
رقم البند و بيانه : (1-1) اعمال تطهير الموقع من الاشجار والمزروعات و المخلفات

تنفيذ : شركة القاهرة للطرق والانشاءات

مقدار العمل السابق : 26700.0 م³

الكمية	بيان الاعمال
26700.00	مقدار العمل السابق
0.00	اجمالي الكميات خلال فترة المستخلص الحالية (م ³)
26700.00	الاجمالي الكلي (م ³)

مهندس الهيئة العامة للطرق والكباري
م / إبراهيم عبدالله الحناوي

مهندس الإستشاري
مكتب د/خالد فتنديل
م / خالد فوزي السيد

مهندس الإستشاري (xyz)
م / محمد شهاب خليل

مهندس الشركة
م / محمد ضيف الله

ك د / السيد

محمد خليل

محمد شريف الله



قائمة الكميات الواردة بالمستخلص جارى (2)

عملية: اسناد أعمال الجسر الترابي لمسارالقطار الكهربائي السريع الخط الاول (العين السخنة -العلمين) (قطاع فوكة / مطروح) لتنفيذ أعمال تشكيل الجسور
المسافة من الكم 521+000 الى الكم 522+000 بطول 1 كم اتجاه النجيلة
رقم البند و بيانه : (2-2) اعمال حفر باستخدام المعدات الميكانيكية فى التربة المتماسكة عدا التربة الصخرية (باستخدام البلدوزر)
طبقا لمفاوضة فبراير 2023

تنفيذ : شركة القاهرة للطرق والانشاءات

مقدار العمل السابق : 0.0 م 3

الكمية	بيان الاعمال
0.00	مقدار العمل السابق
37771.00	اجمالي الكميات خلال فترة المستخلص الحالية (م3)
37771.00	الاجمالي الكلي (م ³)

مهندس الهيئة العامة للطرق والكباري
م / إبراهيم عبدالله الحناوي

مهندس الاستشاري
مكتب د/ خالد قنديل
م / خالد فوزي السيد

مهندس الاستشاري (xyz)
م / محمد شهاب خليل

مهندس الشركة
م / محمد ضيف الله



قائمة الكميات الواردة بالمستخلص جارى (2)

عملية: اسناد أعمال الجسر الترابي لمسارالقطار الكهربائي السريع الخط الاول (العين السخنة -العلمين)(قطاع فوكة / مطروح) لتنفيذ أعمال
تشكيل الجسور
المسافة من الكم 521+000 الى الكم 522+000 بطول 1 كم اتجاه النجيلة

رقم البند و بيانه : (3-1) أعمال توريد و تشغيل اترية صالحة للردم مطابقة للمواصفات طبقا لمفاوضة فبراير 2023

تنفيذ : شركة القاهرة للطرق والانشاءات

مقدار العمل السابق : 0.0 3م

الكمية	بيان الاعمال
0	مقدار العمل السابق
41599.00	اجمالي الكميات خلال فترة المستخلص الحالية (م ³)
41599.00	الاجمالي الكلي (م ³)

مهندس الهيئة العامة للطرق
والكباري
م / إبراهيم عبد الله الحناوي

مهندس الإستشاري
مكتب د/خالد قنديل
م / خالد فوزي السيد

مهندس الإستشاري (xyz)
م / محمد شهاب خليل

مهندس الشركة
م / محمد صيف الله

م / خالد فوزي السيد

م / محمد شهاب خليل

م / محمد صيف الله



قائمة الكميات الواردة بالمستخلص جارى (2)

عملية :اسناد أعمال الجسر الترابي لمسارالقطار الكهربائي السريع الخط الاول (العين السخنة -العلمين)(قطاع فوكة / مطروح) لتنفيذ
أعمال تشكيل الجسور
المسافة من الكم 521+000 الى الكم 522+000 بطول 1 كم اتجاه النجيلة

رقم البند و بيانه : (3-1) علاوة مسافة النقل 228 كم

تنفيذ : شركة القاهرة للطرق والانشاءات

مقدار العمل السابق : 0.0 3م

الكمية	بيان الاعمال
0.00	امقدار العمل السابق
41599.00	اجمالي الكميات خلال فترة المستخلص الحالية (م ³)
41599.00	الاجمالي الكلي (م ³)

مهندس الهيئة العامة للطرق
والكباري
م / إبراهيم عبدالله الحناوي

مهندس الاستشاري
مكتب د/خالد قنديل
م / خالد فوزي السيد

مهندس الاستشاري (xyz)
م / محمد شهاب خليل

مهندس الشركة
م / محمد ضيف الله
محمد ضيف الله



قائمة الكميات الواردة بالمستخلص جارى (2)

عملية: اسناد أعمال الجسر الترابي لمسارالقطار الكهربائي السريع الخط الاول (العين السخنة -العلمين) (قطاع فوكة / مطروح)
لتنفيذ أعمال تشكيل الجسور
المسافة من الكم 521+000 الى الكم 522+000 بطول 1 كم اتجاه النجيلة
رقم البند و بيانه : (3-1) رسوم الكارطة والموازن طبقاً للمادة(36) من الشروط العامة والمواصفات طبقاً لما جاء بالقائمة الموحدة لاسعار الطرق
لأعمال طبقة الأتربة

تنفيذ : شركة القاهرة للطرق والانشاءات

مقدار العمل السابق :		0.0	3م
بيان الاعمال	الكميه		
مقدار العمل السابق	0.00		
اجمالي الكميات خلال فترة المستخلص الحالية (م ³)	41599.00		
الاجمالي الكلي (م ³)	41599.00		

مهندس الهيئة العامة للطرق والكباري
م / إبراهيم عبد الله الحناوي

مهندس الإستشاري
مكتب د/خالد قنديل
م / خالد فوزي السيد

مهندس الإستشاري (xyz)
م / محمد شهاب خليل

مهندس الشركة
م / محمد ضيف الله

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		19-10-2022							
Contractor reference	C/A = Emb-1									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	(Lower Embankment) MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+000 520+700	521+060 520+750	-11 -11		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m³	5000	15-10-2022	
2	Classification	m³	5000	15-10-2022	
3	Proctor & O.m.c	m³	5000	15-10-2022	
4	L.L & P.L & PI	m³	5000	15-10-2022	
5	C.B.R	m³	5000	19-10-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (Gomaa Badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	eng / Ahmed Mohammed		19-10-2022	A
QA/QC *	Ahmed AboZaid		19-10-2022	A
GARB**	Hussien Fouad		19-10-2022	A
Comments by	Rel quantity approval with Bs		19-10-2022	
Employers Representative	Mohamed Ahs		8-2-25	Auc

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		19-10-2022	
Contractor Reference	CA-Emb-1			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12.9%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.8%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	63%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng/ Ahmed mohamed		19/10/2022	A
Contractor QA/QC *	Ahmed Abo Zaid		19/10/2022	A
GARB**	Hussein Fawad		19/10/2022	A
Employers Representative	Mohamed Ahmed		15-1-2025	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	15/10/2022	code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-EMB-1	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		16000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	0.0	1884.0	3122.0	916.0	1008.0	565.0	995.0		A-1-a
(g)Cumulative Retained	0.0	1884.0	5006.0	5922.0	6930.0	7495.0	8490.0	PRO	2.16
Cumulative Retained %	0.0	11.8	31.3	37.0	43.3	46.8	53.1	WC	7.8
Cumulative Passing %	100.0	88.2	68.7	63.0	56.7	53.2	46.9	CBR	63%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	80.00	199.50	362.50					
Cumulative Retained %	16.00	39.90	72.50					
Cumulative Passing %	84.00	60.10	27.50					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	88.2	68.7	63.0	56.7	53.2	46.9	39.4	28.2	12.9

ATTEBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	N.P	N.P	N.P

Contractor

Consultant



PROCTOR TEST


TESTING DATE:	2022/10/16	code	ZONE	520+500	522+000
LOCATION	kp:521+000	Ce-Emb-1	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6428.0
Mold Volume:	2104.9

MAX Dry Density	2.16
Water content %	7.8

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	11016.0	11173.0	11322.0	11052	
WT. WET SOIL	4588.0	4745.0	4894.0	4624.0	
Wt. Density	2.180	2.254	2.325	2.197	

Tare No.	2	2	9	9	1	1	5	5		
Tare wt.	27.62	27.62	26.92	26.92	26.84	26.84	27.24	27.24		
Wt. Of wet soil & tare	120.0	120.0	133.2	133.2	145.3	145.3	144.5	144.5		
Wt. Of dry soil & tare	117.2	117.2	127.1	127.1	136.7	136.7	134.6	134.6		
Wt. Of water	2.8	2.8	6.1	6.1	8.6	8.6	9.9	9.9		
Wt. Of dry soil	89.6	89.6	100.2	100.2	109.9	109.9	107.4	107.4		
Water content %	3.1%	3.1%	6.1%	6.1%	7.8%	7.8%	9.2%	9.2%		
AV. Water content %	3.1%		6.1%		7.8%		9.2%			
Dry Density	2.114		2.125		2.156		2.011			



Contractor

[Signature]

[Stamp: 10/10/2022]

Consultant

[Signature]

[Stamp: 10/10/2022]



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	19/10/2022	Code	ZONE	520+500	522+000
Location :	kp:621+000	CA-Emb-1	Material	fill material layer	
NAME COMPANY	calro company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16653
(gm)Mold WT. + Wet WT.	21525
(gm)Wet WT.	4872
Wet Density (g/cm ³)	2.237
Dry Density (g/cm ³)	2.091
Proctor Density (g/cm ³)	2.160
Compaction %	97

Mositure Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	27.24
(gm)Tare WT. +Wet WT.	154.72
(gm)Tare WT. +Dry WT.	146.4
(gm)Water WT.	8.3
(gm)Dry WT.	119.2
Molsture Content %	7.0

Swelling	
Mold No.	55
Date	19/10/2022
(mm)Initial Height	5.00
(mm)Final Height	5.00
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penteration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	105.00	259.00	425.00	642.00	851.00	1001.00	1166.00	1285.00	1613.00
(KN)Load	1.0	2.5	4.2	6.3	8.3	9.8	11.4	12.6	15.8



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % 97
2.50	6.29	13.4	47.1%	97	97	47.2%
5.00	12.59	20.0	62.9%			63.0%

Lab. Specialist

Name :

Sign :

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

Lab. Engineer

Name :

Sign :

القاهرة بطريق الإسكندرية
11111 - 11111


Consultant Engineer

Name :

Sign :

القاهرة بطريق الإسكندرية
11111 - 11111

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		15/11/2022							
Contractor reference	CA-Emb-10									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+370	521+400	-8			
	521+680	521+800	-8			
	521+560	521+615	-8			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	11-11-2022		
2	Classification	m ³	5000	11-11-2022		
3	Proctor & O.m.c	m ³	5000	11-11-2022		
4	L.L & P.L & PI	m ³	5000	11-11-2022		
5	C.B.R	m ³	5000	15-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		15/11/2022	A		
QA/QC *	Ahmed Abo Zaid		15/11/2022	A		
GARB**	Hussien Fouad		15/11/2022	A		
Comments by	Rite quantity approved with @s					
Employers Representative	Mohamed Ahmed		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		15/11/2022	
Contractor Reference	CA-Emb-10			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.2%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.5%	
6	ASTM D 1557	Modified proctor	2.19	
7	ASTM D 1883	CBR	68%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel	Abdelrahman	15/11/2022	A
Contractor QA/QC *	Abdelbsh SAMY	Abdelbsh	15/11/2022	A
GARB**	Hussien Fouad	Hussien	15/11/2022	A
Employers Representative	Mohamed Ahmed	Mohamed	15-11-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	15/11/2022	code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
NAME COMPANY	cairo company	CH-Emb-10	quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		15000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	1281.0	1200.0	2071.0	1424.0	1598.0	1142.0	1900.0		A-1-a
(g)Cumulative Retained	1281.0	2481.0	4552.0	5976.0	7574.0	8716.0	10616.0		2.19
Cumulative Retained %	8.5	16.5	30.3	39.8	50.5	58.1	70.8		WC
Cumulative Passing %	91.5	83.5	69.7	60.2	49.5	41.9	29.2		CBR
									66%


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	100.00	248.34	325.00					
Cumulative Retained %	20.00	49.67	65.00					
Cumulative Passing %	80.00	50.33	35.00					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	91.5	83.5	69.7	60.2	49.5	41.9	29.2	23.4	14.7	10.2

ATTERBERG LIMITS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	23.1%	21.2%	1.9%

Contractor

Consultant





Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA TO MARSA MATROUH
From Station 504+000 To Station 568+177



PROCTOR TEST


TESTING DATE:	10-11-2022	code	ZONE	520+500	522+000
LOCATION	KP:521+000		Material	fill material layer	
NAME COMPANY	cairo company	CH-EMB-10	quaintity	5000 m3	

Weight of empty mold :	6128.0
Mold Volume:	2104.9

MAX Dry Density	2.19
Water content %	7.5

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10756.0	10986.0	11100.0	11126	
WT. WET SOIL	4628.0	4858.0	4972.0	4998.0	
Wt. Density	2.199	2.308	2.362	2.374	

Tare No.	12	12	7	7	8	8	11	11		
Tare wt.	26.1	26.1	25.93	25.93	26.63	26.63	25.34	25.34		
Wt. Of wet soil & tare	128.2	128.2	131.6	131.6	131.8	131.8	134.6	134.6		
Wt. Of dry soil & tare	124.8	125.0	125.1	125.1	124.5	124.5	124.2	124.2		
Wt. Of water	3.3	3.2	6.5	6.5	7.3	7.3	10.4	10.4		
Wt. Of dry soil	98.7	98.9	99.1	99.1	97.9	97.9	98.9	98.9		
Water content %	3.4%	3.2%	6.6%	6.6%	7.5%	7.5%	10.5%	10.5%		
AV. Water content %	3.3%		6.6%		7.5%		10.5%			
Dry Density	2.129		2.166		2.198		2.149			



Contractor

Handwritten signature
 مشروع مطار السويح
 القطاع السابع
 معمل المركزي
 (رقم 6)

مختبر الطرق والإنشاءات
 ب. ت. ١٠٦٧٠٥
 ب. ق. ٥٦ - ٥٤٣ - ٥٤٥

Consultant

Handwritten signature
 الشركة الهندسية
 ك. ك. انجنيئرنگ


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فخريل	 SVSTRA SHAKER	Electric Express Train - HSR	 الهيئة العامة للإعتماد والضمان والتأهيل (ISIRI)
---	--	-------------------------------------	--

Plasticity and Liquidity Test - Atterberg Limits

Testing Date :	15/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	Material		fill material layer	
Name Company	cairo company	CA-Emb-10		quantity	5000 m3

Testing Results :-


Test	Liquid Limit				Plastic Limit	
No. of Ticks	35	28	21	17	-	-
Tare No.	30	12	3	9	F	D
Tare WT. (gm)	25.70	27.18	26.29	26.91	11.96	12.52
Tare WT. + Wet WT. (gm)	48.33	54.41	55.73	54.58	12.67	13.18
Tare WT. + Dry WT. (gm)	44.68	49.36	49.95	48.92	12.54	13.07
(gm)Water WT.	3.65	5.05	5.78	5.66	0.13	0.11
(gm)Dry WT.	18.98	22.18	23.66	22.01	0.58	0.55
Moisture Content %	19.2%	22.8%	24.4%	25.7%	22.4%	20.0%
Average %					21.2%	



L.L	P.L	P.I
23.1%	21.2%	1.9%


Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : 

Sign : 


Name :

Sign :



Name :

Sign :







Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	15/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-10	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21564
(gm)Wet WT.	5011
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.141
Proctor Density (g/cm ³)	2.190
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	25.25
(gm)Tare WT. +Wet WT.	145.9
(gm)Tare WT. +Dry WT.	137.5
(gm)Water WT.	8.4
(gm)Dry WT.	112.3
Moisture Content %	7.5

Swelling	
Mold No.	5
Date	15/11/2022
(mm)Initial Height	5.1
(mm)Final Height	5.1
Difference	0
(mm)Sample Height	11.2
Swelling Ratio %	

Loading Reading :

(mm)Penetration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	125.00	325.00	489.00	585.00	754.00	1056.00	1244.00	1358.00	1564.00
(KN)Load	1.2	3.2	4.8	5.7	7.4	10.3	12.2	13.3	15.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 100
2.50	5.73	13.4	42.9%	98	100	43.9%
5.00	13.31	20.0	66.5%			68.0%

Lab. Specialist

Name :

Sign :

Lab. Engineer


Name :

Sign :


Consultant Engineer

Name :

Sign :



MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	20-11-2022							
Contractor reference	CA-EMB-11									
Received by ER	<i>[Signature]</i>	MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment					FILL MATERIAL RESULTS
Location to be Used	From	To	Fill			
	521+615	521+680	-8			
	521+000	521+080	-9.5			
521+500	521+540	-8				
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	16-11-2022		
2	Classification	m ³	5000	16-11-2022		
3	Proctor & O.m.c	m ³	5000	16-11-2022		
4	L.L & P.L & PI	m ³	5000	16-11-2022		
5	C.B.R	m ³	5000	20-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed	<i>Ahmed mohammed</i>	20/11/2022	A	
QA/QC *	<i>Ahmed Abo zaid</i>	<i>[Signature]</i>	20/11/2022	A	
GARB**	<i>Hussien Soued</i>	<i>[Signature]</i>	20/11/2022	A	
Comments by	<i>Real quantity approved with 0.5</i>				
Employers Representative	<i>Mohamed Ahmed</i>	<i>[Signature]</i>	8-2-25		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company						
Electric express train	Cairo for Roads and construction Company			k.k						
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel	<i>Abdel Rahman</i>	20-11-2022							
Contractor Reference	CA-Emb-11									
Received by ER	<i>reza</i>	MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	low embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.7%	
4	ASTM D 4318	Atterberg limit	20 %	
5	ASTM D 2974	Moisture content	7.6%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	60%	
Comments by:		Comments by:		
		All test under Responsibility third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	<i>Abdel Rahman Adel</i>	<i>Abdel Rahman</i>	20/11/2022	A
Contractor QA/QC *	<i>Eng / Abdallah Sany</i>	<i>Abdallah</i>	20/11/2022	A
GARB**	<i>Hussien Fouad</i>	<i>Hussien</i>	20/11/2022	A
Employers Representative	<i>Mohamed Ahmed</i>	<i>Mohamed</i>	15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
 From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARS MATROUH
 From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	16/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-EMB-11	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		15000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	174.0	305.0	1700.0	1550.0	1842.0	1090.0	1778.0		A-1-a
(g)Cumulative Retained	174.0	479.0	2179.0	3729.0	5571.0	6661.0	8439.0	PRO	2.18
Cumulative Retained %	1.2	3.2	14.5	24.9	37.1	44.4	56.3	WC	7.6
Cumulative Passing %	98.8	96.8	85.5	75.1	62.9	55.6	43.7	CBR	59.9

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	88.00	249.48	331.69					
Cumulative Retained %	17.60	49.90	66.34					
Cumulative Passing %	82.40	50.10	33.66					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.8	96.8	85.5	75.1	62.9	55.6	43.7	36.0	21.9	14.7

ATTEBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	23%	20%	3.1%

Contractor

Consultant

شروع العمل
 القطاع السابع
 عمل الممرات
 (رقم 6)

محافظة مطروح والإسكندرية
 س.ت. ١٠٦٧٠٥
 ب.ق. ٥٤٦ - ٥٤٣ - ٥٤٢

المكتب
 القاهرة
 ف.ق. ٥٤٦ - ٥٤٣ - ٥٤٢


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد فكري	 SVSTRA	Electric Express Train - HSR	 الهيئة العامة للإعانة الميناء والنقل (SARBT)
---	---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	16/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-1	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	


Testing Results :-


Test	Liquid Limit				Plastic Limit	
No. of Ticks	36	27	21	18	-	-
Tare No.	12	7	4	11	F	D
Tare WT. (gm)	25.70	27.18	26.29	26.91	11.96	12.52
Tare WT. + Wet WT. (gm)	48.33	54.41	55.73	54.58	12.67	13.18
Tare WT. + Dry WT. (gm)	44.68	49.36	49.95	48.92	12.54	13.08
(gm)Water WT.	3.65	5.05	5.78	5.66	0.13	0.10
(gm)Dry WT.	18.98	22.18	23.66	22.01	0.58	0.56
Moisture Content %	19.2%	22.8%	24.4%	25.7%	22.4%	17.9%
Average %					20.1%	



L.L	P.L	P.I
23.2%	20.1%	3.1%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : 

Sign : 

Name : 

Sign : 

Name : 

Sign : 

A handwritten signature in black ink is written over a horizontal line. Below the signature is a blue official stamp. The stamp contains the text 'الجمهورية التونسية' (Republic of Tunisia) at the top, 'الوزارة الداخلية' (Ministry of the Interior) in the middle, and 'مديرية التكوين' (Directorate of Training) at the bottom. There is also a small logo on the left side of the stamp.



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	20/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Em6-11	Material	fill material layer	
Name Company	calro company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	1
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21536
(gm)Wet WT.	4983
Wet Density (g/cm ³)	2.288
Dry Density (g/cm ³)	2.128
Proctor Density (g/cm ³)	2.180
Compaction %	98

Mositure Ratio After Compacted Mold	
Tare No.	11
Tare WT. (gm)	26.36
(gm)Tare WT. +Wet WT.	146
(gm)Tare WT. +Dry WT.	137.6
(gm)Water WT.	8.4
(gm)Dry WT.	111.2
Moisture Content %	7.6

Swelling	
Mold No.	1
Date	20/11/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penteration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	146.00	269.00	421.00	578.00	711.00	886.00	1056.00	1223.00	1465.00
(KN)Load	1.4	2.6	4.1	5.7	7.0	8.7	10.3	12.0	14.4



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR عند نسبة 100 %
2.50	5.66	13.4	42.4%	98	100	43.5%
5.00	11.99	20.0	59.9%			61.3%

Lab. Specialist

Name :

Sign :

Lab. Engineer


Name :


Sign :

Consultant Engineer

Name :




Sign :

MATERIAL INSPECTION REQUEST	     					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K							
Issued by Contractor	Name	Sign	Date	Time							
	Eng/ Abdelrahman Adel		21/11/2022								
Contractor reference	CA-Emb-12-21/11/2022										
Received by ER			MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		


Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+540	521+560	-8			
	521+680	521+780	-7.5			
MAR Approval No	521+800	521+950	-8	Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	17-11-2022		
2	Classification	m ³	5000	17-11-2022		
3	Proctor & O.m.c	m ³	5000	17-11-2022		
4	L.L & P.L & PI	m ³	5000	17-11-2022		
5	C.B.R	m ³	5000	21-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		21/11/2022	A	
QA/QC *	Ahmed Abo Zaid		21/11/2022	A	
GARB**	Hussien. Fouad		21/11/2022	A	
Comments by	Kindly attach approval with @s				
Employers Representative	Mohamed Ahmed		8-2-25		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel	<i>Abdel Rahman</i>	21/11/2022	
Contractor Reference	CA-Emb-12 - 21/11/2022			
Received by ER	<i>[Signature]</i>	MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.5%	
4	ASTM D 4318	Atterberg limit	18.6%	
5	ASTM D 2974	Moisture content	6.3%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	60.7%	
Comments by:		Comments by:		
		All test under Responsibility third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	21/11/2022	A
Contractor QA/QC *	Abdelbakh SAMY	Abdelbakh	21/11/2022	A
GARB**	Hussien Fouad	Hussien	21/11/2022	A
Employers Representative	Mohamed Ahs	Mohamed	15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	17/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	calro company		quaintly	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	755.0	2755.0	3380.0	1480.0	2060.0	1080.0	2300.0		A-1-a
(g)Cumulative Retained	755.0	3510.0	6890.0	8370.0	10430.0	11510.0	13810.0	PRO	2.15
Cumulative Retained %	3.8	17.6	34.5	41.9	52.2	57.6	69.1	WC	6.3
Cumulative Passing %	96.2	82.5	65.6	58.2	47.9	42.5	31.0	CBR	59.4

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	84.30	214.54	331.14					
Cumulative Retained %	16.86	42.91	66.23					
Cumulative Passing %	83.14	57.09	33.77					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	96.2	82.5	65.6	58.2	47.9	42.5	31.0	25.7	17.7	10.5

ATTERBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.I)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	24.6%	18.6%	5.7%

Contractor

Consultant

انتقارة لسطرق والانشاوات
 س.ت: ١٠٦٧٠٥
 ب.ق: ٥٤٦ - ٥٤٧ - ٥٤٨

المكتب
 القناتق القناتق
 أ.د. خالد فتوح


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فخر الدين	 Electric Express Train - HSR	 الهيئة العامة للإعانة للمواصلات والبنية التحتية (CAEBT)
---	---	--

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	18/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	calro company		quantity	5000 m3	

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	33	29	23	17		
Tare No.	45	7	14	46		
Tare WT. (gm)	25.34	27.46	22.87	27.12	11.16	13.35
Tare WT. + Wet WT. (gm)	66.34	81.39	71.00	54.21	11.94	14.16
Tare WT. + Dry WT. (gm)	58.69	71.00	61.44	48.72	11.82	14.03
(gm)Water WT.	7.65	10.39	9.56	5.49	0.12	0.13
(gm)Dry WT.	33.35	43.54	38.57	21.60	0.66	0.68
Moisture Content %	22.9%	23.9%	24.8%	25.4%	18.2%	19.1%
Average %					18.6%	



L.L	P.L	P.I
24.3%	18.6%	5.7%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :

Sign :

شروع
القطاع
معمل المركزي
(رقم 6)

Name :

Sign :

المشرفة نظري والإستشارات
ب.س.ت. : ١٠٦٧٠٥
ب.ف. : ٥٤٦ - ٥٤٧

Name :

Sign :

المشرف
المشرف
المشرف

	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		


PROCTOR TEST

Testing Date :	18/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Weight of empty mold :	6210.0	MAX Dry Density	2.150
Mold Volume:	2104.9	Water content %	6.3

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10521.0	10755.0	11010.0	10886	
WT. WET SOIL	4311.0	4545.0	4800.0	4676.0	
Wt. Density	2.048	2.159	2.280	2.221	

Tare No.	1	1	23	23	16	16	45	45		
Tare wt.	26.84	26.84	25.27	25.27	25.99	25.99	25.32	25.32		
Wt. Of wet soil & tare	157.2	157.2	145.5	145.5	163.6	163.6	158.7	158.7		
Wt. Of dry soil & tare	153.0	153.0	140.0	140.0	155.5	155.5	148.0	148.0		
Wt. Of water	4.2	4.2	5.5	5.5	8.1	8.1	10.7	10.7		
Wt. Of dry soil	126.2	126.2	114.7	114.7	129.5	129.5	122.7	122.7		
Water content %	3.3%	3.3%	4.8%	4.8%	6.3%	6.3%	8.7%	8.7%		
AV. Water content %	3.3%		4.8%		6.3%		8.7%			
Dry Density	1.983		2.060		2.146		2.043			



Contractor

مشروع طار السويح
 القطاع السابع
 معمل المركزي
 (رقم 6)

القاهرة لنظرة والإنشاءات
 س.ت: ١٠٦٧٠٥
 ب.ق: ٥٤٦ - ٥٤٥

Consultant






Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	21/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16444
(gm)Mold WT. + Wet WT.	21266
(gm)Wet WT.	4822
Wet Density (g/cm ³)	2.214
Dry Density (g/cm ³)	2.101
Proctor Density (g/cm ³)	2.150
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	11
Tare WT. (gm)	25.13
(gm)Tare WT. +Wet WT.	156
(gm)Tare WT. +Dry WT.	149.3
(gm)water wt.	6.7
(gm)Dry WT.	124.2
Moisture Content %	5.4

Swelling	
Mold No.	2
Date	21-11-2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

64.04	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	97.00	236.00	478.00	536.00	740.00	869.00	997.00	1213.00	1458.00
(KN)Load	1.0	2.3	4.7	5.3	7.3	8.5	9.8	11.9	14.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	5.25	13.4	39.3%	98	100	40.3%
5.00	11.89	20.0	59.4%			60.7%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consulting Engineer

Name :


Sign :

شروع اطار العمل
القطاع السابع
معمل المركزي
(رقم 6)

المشرفة نظرية والإنشآت
ب.م.ت. : ١٠٦٧.٥
ب.ا.ق. : ٥٤٣ - ٥٤٤


المشرف الرئيسي
قسم القياس

MATERIAL INSPECTION REQUEST	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		23/11/2022																	
Contractor reference	CA-Emb-13																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+950	521+980	-8		
	521+320	521+460	-7.5		
	521+560	521+610	-7.5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	21-11-2022	
2	Classification	m ³	5000	21-11-2022	
3	Proctor & O.m.c	m ³	5000	21-11-2022	
4	L.L & P.L & PI	m ³	5000	21-11-2022	
5	C.B.R	m ³	5000	23-11-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (Gomaa badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		23/11/2022	A
QA/QC *	Ahmed Abo Zaid		23/11/2022	A
GARB**	Hussien Souad		23/11/2022	A
Comments by	Riad Ghabity approval with Qc			
Employers Representative	Mohamed Ahmed		8-2-25	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		23/11/2022	
Contractor Reference	CA-Emb-13			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12.7%	
4	ASTM D 4318	Atterberg limit	19.3%	
5	ASTM D 2974	Moisture content	6.3%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	66.4%	
Comments by:		Comments by:		
		All test under Responsibility third Party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed Mohamed		23/11/2022	A
Contractor QA/QC *	Ahmed Abo Zaid		23/11/2022	A
GARB**	Hussien Gouda		23/11/2022	A
Employers Representative	Mohamed A. H.		19-1-2023	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARS MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	19/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-1B	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	225.0	1190.0	3445.0	2135.0	2932.0	1750.0	1810.0		A-1-a
(g)Cumulative Retained	225.0	1415.0	4860.0	6995.0	9927.0	11677.0	13487.0	PRO	2.15
Cumulative Retained %	1.1	7.1	24.3	35.0	49.6	58.4	67.4	WC	6.3
Cumulative Passing %	98.9	92.9	75.7	65.0	50.4	41.6	32.6	CBR	64%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
(g)Cumulative Retained	86.10	204.52	304.50				
Cumulative Retained %	17.22	40.90	60.90				
Cumulative Passing %	82.78	59.10	39.10				

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.9	92.9	75.7	65.0	50.4	41.6	32.6	27.0	19.2	12.7

ATTERBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	25.3%	19.3%	5.9%

Contractor

Consultant

مشروع القطار السريع
 القطاع السابع
 محمل المركزي
 (رقم 6)

التحليل لنتائج الاختبار
 ١٩٦٧٠٥
 ٥٥٥ - ٥٥٦ - ٥٥٧

التحليل لنتائج الاختبار
 ١٩٦٧٠٥
 ٥٥٥ - ٥٥٦ - ٥٥٧


 	Electric Express Train - HSR	 
---	------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	20/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-13	quaintity	5000 m3	


Testing Results :-

Test	Liquidity Limit				Plastic Limit	
No. of Ticks	35	29	23	15	-	-
Tare No.	24	11	10	3	2	1
Tare WT. (gm)	24.68	26.87	26.42	26.38	12.78	12.55
Tare WT. + Wet WT. (gm)	70.94	63.30	67.65	68.53	13.86	13.57
Tare WT. + Dry WT. (gm)	62.10	56.10	59.20	59.65	13.69	13.40
(gm)Water WT.	8.84	7.20	8.45	8.88	0.17	0.17
(gm)Dry WT.	37.42	29.23	32.78	33.27	0.91	0.85
Moisture Content %	23.6%	24.6%	25.8%	26.7%	18.7%	20.0%
Average %					19.3%	



L.L	P.L	P.I
25.3%	19.3%	5.9%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : 

Name :

Name :

Sign : مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

Sign : القشرة لطرق والإنشاءات
ب. ت. ١٠٦٧٠٥
ب. ف. ٠٥٦ - ٠٥٢ - ٤٤٥

Sign :



PROCTOR TEST


Testing Date :	20/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-13	Material	fill material layer	
Name Company	cairo company		quaintity	5000 m3	


Weight of empty mold :	6428.0
Mold Volume:	2104.9

MAX Dry Density	2.152
Water content %	6.3

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10896.0	11132.0	11261.0	11100	
WT. WET SOIL	4468.0	4704.0	4833.0	4672.0	
Wt. Density	2.123	2.235	2.296	2.220	

Tare No.	11	11	3	3	8	8	10	10		
Tare wt.	25.99	25.99	26.38	26.38	26.53	26.53	26.41	26.41		
Wt. Of wet soil & tare	140.0	140.0	125.9	125.9	141.0	141.0	132.2	132.2		
Wt. Of dry soil & tare	136.2	136.2	120.7	120.7	133.8	133.8	124.0	124.0		
Wt. Of water	3.8	3.8	5.2	5.2	7.2	7.2	8.2	8.2		
Wt. Of dry soil	110.2	110.2	94.3	94.3	107.3	107.3	97.6	97.6		
Water content %	3.4%	3.4%	5.5%	5.5%	6.7%	6.7%	8.4%	8.4%		
AV. Water content %	3.4%		5.5%		6.7%		8.4%			
Dry Density	2.052		2.118		2.152		2.047			



Contractor

 مشروع القطار السريع
 القطاع السابع
 محمل المركزي
 (رقم 6)

القاهرة نظري والانشاءات
 س.ت: ١٠٩٧٠٥
 ب.ف: ٥٥٥ - ٥٤٢ - ٥٤٦

Consultant

 المكتب
 الاستشاري
 الهندسي



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	23/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16444
(gm)Mold WT. + Wet WT.	21213
(gm)Wet WT.	4769
Wet Density (g/cm ³)	2.190
Dry Density (g/cm ³)	2.078
Proctor Density (g/cm ³)	2.150
Compaction %	97

Moisture Ratio After Compacted Mold	
Tare No.	11
Tare WT. (gm)	25.13
(gm)Tare WT. +Wet WT.	156
(gm)Tare WT. +Dry WT.	149.3
(gm)water wt	6.7
(gm)Dry WT.	124.2
Moisture Content %	5.4

Swelling	
Mold No.	2
Date	23/11/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0.0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

64.04	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	84.00	216.00	446.00	597.00	811.00	986.00	1123.00	1311.00	1563.00
(KN)Load	0.8	2.1	4.4	5.9	7.9	9.7	11.0	12.8	15.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % 100 نسبة
2.50	5.85	13.4	43.8%	97	100	45.3%
5.00	12.85	20.0	64.2%			66.4%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :

مشروع القطار السريع
القطاع السابع
محطة المركزية
(رقم 6)

المشرفة لطرق والإنشاءات
ب.ت. : ١٠٦٧٥٠٥
ف. : ٥٤٦ - ٥٤٥

المشرفة
ب.ت. : ١٠٦٧٥٠٥
ف. : ٥٤٦ - ٥٤٥

MATERIAL INSPECTION REQUEST						

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		26-11-2022																	
Contractor reference	CA-EMB-14																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From 521+610 520+880	To 521+680 520+960	Fill -7.5 -11.5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	25-11-2022	
2	Classification	m ³	5000	25-11-2022	
3	Proctor & O.m.c	m ³	5000	25-11-2022	
4	L.L & P.L & PI	m ³	5000	25-11-2022	
5	C.B.R	m ³	5000	26-11-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		26/11/2022	A	
QA/QC *	Ahmed Abo Zaid		26/11/2022	A	
GARB**	Hussien Fouad		26/11/2022	A	
Comments by	Final quantity approved with CoS				
Employers Representative	Mohamed Ahs		8-2-25		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company							
Electric express train	Cairo for Roads and construction Company		k.k							
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	26-11-2022							
Contractor Reference	CA-Em6-14									
Received by ER	<i>[Signature]</i>	MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.3%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.1%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	42.7%	
Comments by:			Comments by:	
			All test result Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed Mohamed	<i>Ahmed Mohamed</i>	26/11/2022	A
Contractor QA/QC *	Ahmed Abo Zaid	<i>Ahmed Abo Zaid</i>	26/11/2022	A
GARB**	Hassien Fouad	<i>Hassien Fouad</i>	26/11/2022	A
Employers Representative	Mohamed Alwa	<i>Mohamed Alwa</i>	15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 للمحطة المركزية Electric Express Train SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإعانة للمواصلات والاقتصاد وزارة النقل والاقتصاد مصر
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARSА MATROUH		
From Station 504+000 To Station 568+177				
Operating Lab		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	23-11-2022	Code	ZONE	520+500	522+000
LOCATION	Kp.521+000	CA-Emb-14	Material	fill material Layars	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		24805.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
0.00	2045.0	2312.0	2032.0	2554.0	2715.0	2615.0	2835.0		A-1-a
Cumulative Retained (g)	2045.0	4357.0	6389.0	8943.0	11658.0	14273.0	17108.0	PRO	2.18
Cumulative Retained %	8.2	17.6	25.8	36.1	47.0	57.5	69.0	WC	6.10
Cumulative Passing %	91.8	82.4	74.2	63.9	53.0	42.5	31.0	CBR	42.70

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	116.40	241.00	333.50				
Cumulative Retained %	23.28	48.20	66.70				
Cumulative Passing %	76.72	51.80	33.30				


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	91.8	82.4	74.2	63.9	53.0	42.5	31.0	23.8	16.1	10.3

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor

Consultant

التصميم وتنفيذ الإنشاءات
س.ت: ١٠٦٧٠٥
ب.ض: ٥٤٦ - ٥٤٥



المكتب
للمحطة المركزية
للمواصلات والاقتصاد



Electric Express Train - HSR
 From El Ain El Sokhna City To El Alamein - MATROUH
 Section - 7 From FOKA TO MARSA MATROUH
 From Station 504+000 To Station 568+177



PROCTOR TEST



TESTING DATE:	24-11-2022	Code	Station	520+500	522+000
LOCATION	kp:521+000	ICA-Emb-1M	Material	fill material Layars	
NAME COMPANY	cairo.company		layer thickness	5000m3	

Weight of empty mold :	5764.0
Mold Volume:	2169.0

MAX Dry Density	2.18
Water content %	6.1

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10422.0	10598.0	10786.0	10674	
WT. WET SOIL	4658.0	4834.0	5022.0	4910.0	
Wt. Density	2.148	2.229	2.315	2.264	

Tare No.	40	20	8	15	11	32	21	45		
Tare wt.	46.4	60.9	46.8	31.9	46.1	74.4	55.2	41.5		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.6	147.8	145.7	145.0	143.9	145.5	142.6	141.9		
Wt. Of water	2.4	2.2	4.3	5.0	6.1	4.5	7.4	8.1		
Wt. Of dry soil	101.2	86.9	98.9	113.1	97.8	71.1	87.4	100.4		
Water content %	2.4%	2.5%	4.3%	4.4%	6.2%	6.3%	8.5%	8.1%		
AV. Water content %	2.5%		4.4%		6.3%		8.3%			
Dry Density	2.096		2.135		2.178		2.091			



California Bearing Ratio TEST

Testing Date :	26/11/2022	Code	ZONE	520+500	522+000
Location :	kp:521+000	Ce-Emb-14	Material	fill material Layers	
Company Name	cairo company		quantity	5000m3	

- : Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9836
Wet WT. (gm)	4936
Wet Density (g/cm ³)	2.307
Dry Density (g/cm ³)	2.176
Proctor Density (g/cm ³)	2.180
Compaction %	99.8

Mositure Ratio After Compacted Mold	
Tare No.	18
Tare WT. (gm)	77.7
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	145.9
Water WT. (gm)	4.1
Dry WT. (gm)	68.2
Moisture Content %	6.0

Swelling	
Mold No.	4
Date	٢٠٢٢/١١/٢٦
Initial Height (mm)	3.00
Final Height (mm)	3.00
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.10	0.13	0.15	0.17	0.21	0.23	0.26	0.29	0.33
Load (KN)	3.0	3.9	4.5	5.1	6.3	6.9	7.8	8.7	9.9



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	5.10	13.4	38.2%	100	98	37.5%
5.00	8.70	20.0	43.4%			42.7%

Lab. Specialist

Name :

Sign :

استشارة نظرق والإنشاءات
 س.ت: ١٠٦٧٠٥
 ب.ف: ٥٤٦ - ٥٤٥

Lab. Engineer

Name :

Sign :




 Electric Express Train
 Central Lab Number 4
 Sec-7 Puka - Matrouh

Consultant Engineer


Name :

Sign :







MATERIAL INSPECTION REQUEST	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		29-11-2022							
Contractor reference	CA-Emb-15									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment		FILL MATERIAL RESULTS			
Location to be Used	From 520+960 521+140	To 521+000 521+280	Fill -11.5 -8.5			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	25-11-2022		
2	Classification	m ³	5000	25-11-2022		
3	Proctor & O.m.c	m ³	5000	25-11-2022		
4	L.L & P.L & PI	m ³	5000	25-11-2022		
5	C.B.R	m ³	5000	29-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed Mohammed		29/11/2022	A		
QA/QC *	Ahmed Abo Zaid		29/11/2022	A		
GARB**	Hussien Souey		29/11/2022	A		
Comments by	Final quality approval with Qs					
Employers Representative	Mohamed Amr		8-2-23			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST					

Location Name	Contractor Company				Designer Company					
Electric express train	Cairo for Roads and construction Company				k.k					
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		29-11-2022							
Contractor Reference	CA-EMB-15									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	9.1%	
4	ASTM D 4318	Atterberg limit	19.78%	
5	ASTM D 2974	Moisture content	6%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	57.6%	
Comments by:			Comments by:	
			All test under Responsibility Third party.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		29/11/2022	A
Contractor QA/QC *	Hassan		29/11/2022	A
GARB**	Hussien Fouad		29/11/2022	A
Employers Representative	Mohamed Awa		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فؤاد	 لنهر كيندي السوي Electric Express Train SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإستشارات م.م. أحمد محمد أحمد MOEAS
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	25/11/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-EMB-15	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		17042.00	gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
0.00	2123.0	2635.0	2344.0	1586.0	1856.0	1441.0	1251.0		A-1-a
Cumulative Retained (g)	2123.0	4758.0	7102.0	8688.0	10544.0	11985.0	13236.0	PRO	2.18
Cumulative Retained %	12.5	27.9	41.7	51.0	61.9	70.3	77.7	WC	6.00
Cumulative Passing %	87.5	72.1	58.3	49.0	38.1	29.7	22.3	CBR	57.60



B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	86.50	193.80	295.90				
Cumulative Retained %	17.30	38.76	59.18				
Cumulative Passing %	82.70	61.24	40.82				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	87.5	72.1	58.3	49.0	38.1	29.7	22.3	18.5	13.7	9.1

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	24.54%	19.78%	4.76%

Contractor

Consultant



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فندي	 SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للنقل م.د. طارق النور (CAPSUT)

PROCTOR TEST


TESTING DATE:	26-11-2023	Code	Station	520+500	522+000
LOCATION	kp:521+560	CA-EM6-15	Material	fill matrial layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	5764.0
Mold Volume:	2169.0

MAX Dry Density	2.18
Water content %	6


trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10368.0	10589.0	10782.0	10644	
WT. WET SOIL	4604.0	4825.0	5018.0	4880.0	
Wt. Density	2.123	2.225	2.314	2.250	

Tare No.	22	15	11	32	7	45	18	35		
Tare wt.	54.1	31.9	46.1	74.4	42.8	41.5	77.7	73.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.8	147.5	145.8	146.9	143.7	143.6	144.2	144.1		
Wt. Of water	2.2	2.5	4.2	3.1	6.3	6.4	5.8	5.9		
Wt. Of dry soil	93.7	115.6	99.7	72.5	100.9	102.1	66.5	70.2		
Water content %	2.3%	2.2%	4.2%	4.3%	6.2%	6.3%	8.7%	8.4%		
AV. Water content %	2.3%		4.2%		6.3%		8.6%			
Dry Density	2.076		2.134		2.177		2.072			



المشرفة منطوق والإنشاءات
10/11/2023
545-542-546

Contractor



Consultant

المشرف الفني
10/11/2023
545-542-546


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد المنجول	 SVSTRA B SHAKER	Electric Express Train - HSR	 الهيئة الوطنية للنقل القاري والبحري والجوي (CAPS.T)
---	--	-------------------------------------	--

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	26/11/2022	Code	FROM STA:	520+500	522+000
Location:	kp:521+560	CA-Emb-15	Material	fill matrial layer	
Company Name	cairo company		quantity	5000m3	

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	38	30	25	16	-	-
Tare No.	11	90	10	10	4	20
Tare WT. (gm)	46.50	62.30	43.80	43.8	59.20	60.50
Tare WT. + Wet WT. (gm)	58.40	73.90	57.40	57.40	63.40	62.70
Tare WT. + Dry WT. (gm)	56.20	71.70	54.70	54.60	62.7	62.3
Water WT. (gm)	2.20	2.20	2.70	2.80	0.70	0.36
Dry WT. (gm)	9.70	9.40	10.90	10.80	3.50	1.84
Moisture Content %	22.7%	23.4%	24.8%	25.9%	20.0%	19.6%
Average %					19.8%	



L.L	P.L	P.I
24.54%	19.78%	4.76%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------


Name :

Sign :




Name :

Sign :



Name :

Sign :



California Bearing Ratio TEST

Testing Date :	29/11/2023	Code	zone	520+500	522+000
Location :	kp:521+560		Material	fill matrial layer	
Company Name	cairo company		quaintity	5000m3	

- : Test Results


Compaction % for Mold	
Mold No.	3
Mold Vol. (cm^3)	2025
Mold WT. (gm)	5034
Mold WT. + Wet WT. (gm)	9687
Wet WT. (gm)	4653
Wet Density (g/cm^3)	2.298
Dry Density (g/cm^3)	2.167
Proctor Density (g/cm^3)	2.180
Compaction %	99.4

Mositure Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	60.1
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	144.9
Water WT. (gm)	5.1
Dry WT. (gm)	84.8
Moisture Content %	6.0

Swelling	
Mold No.	3
Date	2022/11/2
Initial Height (mm)	9.00
Final Height (mm)	9.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.12	0.15	0.19	0.23	0.26	0.30	0.34	0.39	0.49
Load (KN)	3.6	4.5	5.7	6.9	7.8	9.0	10.2	11.7	14.7



Calculations :-

Pentetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	% عند نسبة 98
2.50	6.90	13.4	51.7%	99	98	50.9%
5.00	11.70	20.0	58.4%			57.6%

Lab. Specialist

Name :

Sign :

Lab. Engineer






Name :


Sign :

Consultant Engineer

Name :




Sign :

MATERIAL INSPECTION REQUEST	    
	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		29-11-2022							
Contractor reference	CA-Emb-16									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		


Description of Materials	low embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+280	521+320	-8.5		
	521+460	521+560	-7.5		
MAR Approval No	521+000	521+060	-9	Date	
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	25-11-2022	
2	Classification	m ³	5000	25-11-2022	
3	Proctor & O.m.c	m ³	5000	25-11-2022	
4	L.L & P.L & PI	m ³	5000	25-11-2022	
5	C.B.R	m ³	5000	29-11-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed Mohammed		29/11/2022	A
QA/QC *	Ahmed Abo Zaid		29/11/2022	A
GARB**	Hussien Fouad		29/11/2022	A
Comments by	fill quantity approved with Qs			
Employers Representative	Mohd Ali		8-2-25	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company							
Electric express train	Cairo for Roads and construction Company			k.k							
Issued by Contractor	Name	Sign	Date	Time							
	ENG/ Abdelrahman Adel	<i>Abdel Rahman</i>	29-11-2022								
Contractor Reference	CA-Em6-16										
Received by ER			MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	(Lower Embankment) Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	5.8%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	5.8%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	61.8%	
Comments by:			Comments by:	
			All test results Responsibility Third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	29/11/2022	A
Contractor QA/QC *	Hassan	<i>[Signature]</i> MA	29/11/2022	A
GARB**	Hussien Fouad	<i>[Signature]</i>	29/11/2022	A
Employers Representative	Mohamed Ahmed	<i>[Signature]</i>	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للقنوات القناة السويسية (S.A.S.C.)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	25/11/2022	Code	zone	520+500	522+000
LOCATION	kp:521+000	CA-Emb-7b	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20208.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
0.00	2212.0	2780.0	2316.0	2880.0	2122.0	2010.0	2130.0		A-1-a
Cumulative Retained (g)	2212.0	4992.0	7308.0	10188.0	12310.0	14320.0	16450.0		PRO
Cumulative Retained %	10.9	24.7	36.2	50.4	60.9	70.9	81.4		WC
Cumulative Passing %	89.1	75.3	63.8	49.6	39.1	29.1	18.6		CBR



B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	135.50	265.00	343.00					
Cumulative Retained %	27.10	53.00	68.60					
Cumulative Passing %	72.90	47.00	31.40					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	89.1	75.3	63.8	49.6	39.1	29.1	18.6	13.6	8.7	5.8

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant



	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARS MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	26-11-2023	Code	zone	520+500	522+000
LOCATION	Kp:524+000	ICA-EMB-16	Material	fill matrial layar	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	5764.0
Mold Volume:	2169.0

MAX Dry Density	2.18
Water content %	5.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10230.0	10577.0	10772.0	10578	
WT. WET SOIL	4466.0	4813.0	5008.0	4814.0	
Wt. Density	2.059	2.219	2.309	2.219	

Tare No.	32	15	7	11	35	45	34	19		
Tare wt.	74.4	31.9	42.8	46.1	73.9	41.5	70.1	44.4		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.8	148.0	145.0	146.9	145.0	144.4	142.4	143.0		
Wt. Of water	2.2	2.0	5.0	3.1	5.0	5.6	7.6	7.0		
Wt. Of dry soil	73.4	116.1	102.2	100.8	71.1	102.9	72.3	98.6		
Water content %	3.0%	1.7%	4.9%	3.1%	7.0%	5.4%	10.5%	7.1%		
AV. Water content %	2.4%		4.0%		6.2%		8.8%			
Dry Density	2.012		2.134		2.173		2.040			



Contractor
 ب. ش. ت. والانشاءات
 ١٠٦٧٠٥٠
 ٥٥٥ - ٥٩٢ - ٤٦٦


 Electric Express Train
 Central Lab Number 4
 Sec-7 Foka - Matrouh

Consultant


California Bearing Ratio TEST

Testing Date :	29/11/2022	Code	zone	520+500	522+000
Location :	Kp:521+000	CA-Emb-16	Material	fill material layer	
Company Name	cairo company		quantity	5000m3	

-: Test Results


Compaction % for Mold	
Mold No.	1
Mold Vol. (cm ³)	2158
Mold WT. (gm)	4890
Mold WT. + Wet WT. (gm)	9856
Wet WT. (gm)	4966
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.174
Proctor Density (g/cm ³)	2.180
Compaction %	99.7

Moisture Ratio After Compacted Mold	
Tare No.	17
Tare WT. (gm)	59.5
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	145
Water WT. (gm)	5.0
Dry WT. (gm)	85.5
Moisture Content %	5.8

Swelling	
Mold No.	1
Date	2022/11/29
Initial Height (mm)	5.00
Final Height (mm)	5.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.16	0.18	0.25	0.29	0.32	0.35	0.39	0.42	0.51
Load (KN)	4.8	5.4	7.5	8.7	9.6	10.5	11.7	12.6	15.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	8.70	13.4	65.2%	100	98	64.0%
5.00	12.60	20.0	62.9%			61.8%

Lab. Specialist

Name :

Sign :

القاهرة لطريق وإنشاءات
س.ت: ١٠٦٧٠٥
ب.ف: ٢٤٥ - ٤٩٢ - ٠٤٦

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec-7 Fuka - Matruh

Consultant Engineer

Name :

Sign :

القاهرة لطريق وإنشاءات
س.ت: ١٠٦٧٠٥
ب.ف: ٢٤٥ - ٤٩٢ - ٠٤٦

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		2-12-2022							
Contractor reference	CA-Emb-17									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+060	521+080	-9			
	521+780	521+900	-7.5			
	520+800	520+840	-11.5			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	28-11-2022		
2	Classification	m ³	5000	28-11-2022		
3	Proctor & O.m.c	m ³	5000	28-11-2022		
4	L.L & P.L & PI	m ³	5000	28-11-2022		
5	C.B.R	m ³	5000	2-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El mahgob laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		2/12/2022	A
QA/QC *	Hassa		2/12/2022	A
GARB**	Hussien Fouad		2/12/2022	A
Comments by	fill quantity approved with Qs			
Employers Representative	Mohd Ahmed		8-2-28	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company							
Electric express train	Cairo for Roads and construction Company		k.k							
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		2-12-2022							
Contractor Reference	CA-EMB-177									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	8.9%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	8.3%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	65%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		21/12/2022	A
Contractor QA/QC *	Hassan		21/12/2022	A
GARB**	Hussien Fouad		21/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	30-11-2022	code			
LOCATION	K.P. 521+000	CA-Em6-17	ZONE	520+500	522+000
NAME COMPANY	CAIRO				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT (g)		27299.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1088.0	2908.0	3566.0	1872.0	2835.0	2319.0	3831.0		A-1-a	
Cumulative Retained (g)	1088.0	3996.0	7562.0	9434.0	12269.0	14588.0	18419.0		PRO	2.18
Cumulative Retained %	4.0	14.6	27.7	34.6	44.9	53.4	67.5		WC	8.30
Cumulative Passing %	96.0	85.4	72.3	65.4	55.1	46.6	32.5		CBR	65.00

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	175.00	296.00	363.00					
Cumulative Retained %	35.00	59.20	72.60					
Cumulative Passing %	65.00	40.80	27.40					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	96.0	85.4	72.3	65.4	55.1	46.6	32.5	21.1	13.3	8.9

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P



PROCTOR TEST


TESTING DATE:	1/12/2022	code			
LOCATION	K.P 521+000	CA-EMB-17	ZONE	520+500	522+000
NAME COMPANY	cairo				

Weight of empty mold :	6093.0
Mold Volume:	2032.0

MAX Dry Density	2.18
Water content %	8.3

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10235.0	10512.6	10756.4	10909	10807
WT. WET SOIL	4142.0	4419.6	4663.4	4816.0	4714.0
Wt. Density	2.038	2.175	2.295	2.370	2.320

Tare No.	2	2	5	6	20	12	7	6	15	9
Tare wt.	32	8.8682	31	23.23	30	22.79	34.18	29	35.25	29
Wt. Of wet soil & tare	161.0	187.3	221.0	139.1	178.0	121.0	160.2	171.0	187.0	171.0
Wt. Of dry soil & tare	158.2	182.9	213.3	133.6	169.0	114.5	149.9	160.0	172.7	158.9
Wt. Of water	2.8	4.4	7.7	5.5	9.0	6.5	10.3	11.0	14.3	12.1
Wt. Of dry soil	126.2	174.0	182.3	110.4	139.0	91.7	115.7	131.0	137.5	129.9
Water content %	2.2%	2.5%	4.2%	4.9%	6.5%	7.1%	8.9%	8.4%	10.4%	9.3%
AV. Water content %	2.4%		4.6%		6.8%		8.6%		9.8%	
Dry Density	1.991		2.080		2.149		2.181		2.112	



 	Electric Express Train - HSR	 
---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	2/12/2022	Code	ZONE	520+500	522+000
Location :	القاهرة - 521+000	CA-Em6-17			
Layer No. :	CAIRO				

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.049
Proctor Density (g/cm ³)	2.180
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. +Wet WT. (gm)	233
Tare WT. +Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	8.3

Swelling	
Mold No.	55
Date	2/12/2022
Initial Height (mm)	4.50
Final Height (mm)	4.50
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	77.00	156.00	245.00	444.00	634.00	893.00	1176.00	1341.00	1466.00
Load (KN)	0.8	1.5	2.4	4.4	6.2	8.8	11.5	13.1	14.4



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	معدل نسبة 98 %
2.50	4.35	13.4	32.6%	99	98	32.3%
5.00	13.14	20.0	65.6%			65.0%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

معمل اختبارات وأبحاث التربة
القطار السريع - فوكه - مطروح



Consultant Engineer

Name :

Sign :


القاهرة - 521+000
ب.ب.ت. : ١٠٩٣٠٥
٥٤٤ - ٥٤٣

التوقيع
أ.م.ع. المهندس

Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K					
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		4/12/2022							
Contractor reference	CA-Emb-18									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	520+840	520+880	-11.5		
	520+700	520+800	-10.5		
MAR Approval No	520+620	520+640	-10	Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	30-11-2022	
2	Classification	m ³	5000	30-11-2022	
3	Proctor & O.m.c	m ³	5000	30-11-2022	
4	L.L & P.L & PI	m ³	5000	30-11-2022	
5	C.B.R	m ³	5000	4-12-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (Gomaa Badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		4/12/2022	A
QA/QC *	Ahmed Abo Zaid		4/12/2022	A
GARB**	Hussien Fouad		4/12/2022	A
Comments by	Rel quantity approved			
Employers Representative	Mohamed A. H.		8-2-23	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		4/12/2022	
Contractor Reference	CA-Emb-18			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	7.4%	
4	ASTM D 4318	Atterberg limit	19%	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	65%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	4/12/2022	A
Contractor QA/QC *	Abdallah SAMY	Abdallah	4/12/2022	A
GARB**	Hussien Fouad	Hussien	4/12/2022	A
Employers Representative	Johny Ahmed	Johny	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	30/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	A-Emh-18	Material	fill material layer	
Name Company :	cairo company		quaintity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		21000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	3516.0	1842.0	3225.0	1415.0	2628.0	1430.0	2275.0		A-1-a
(g)Cumulative Retained	3516.0	5358.0	8583.0	9998.0	12626.0	14056.0	16331.0	PRO	2.16
Cumulative Retained %	16.7	25.5	40.9	47.6	60.1	66.9	77.8	WC	6.80
Cumulative Passing %	83.3	74.5	59.1	52.4	39.9	33.1	22.2	CBR	65%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
(g)Cumulative Retained	101.15	249.35	332.90				
Cumulative Retained %	20.23	49.87	66.58				
Cumulative Passing %	79.77	50.13	33.42				

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	83.3	74.5	59.1	52.4	39.9	33.1	22.2	17.7	11.1	7.4

ATTERBERG LIMITS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	24.7%	19.0%	5.7%

Contractor

Handwritten signature

مشروع القطار السريع
 القطاع السابع
 محمل المركزي
 (رقم 6)

مصلحة الطرق والبنى
 ١٠٦٧٠٥
 ٥٥٥ ٥٥٦ ٥٥٧

Consultant

Handwritten signature

مصلحة الطرق والبنى


 	Electric Express Train - HSR	 
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	30/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-18	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	37	28	22.7	17	-	-
Tare No.	30	15	7	4	F	B
Tare WT. (gm)	25.80	27.48	27.09	25.40	12.60	13.37
Tare WT. + Wet WT. (gm)	49.09	53.90	53.00	54.02	13.18	13.92
Tare WT. + Dry WT. (gm)	44.70	48.68	47.75	48.30	13.09	13.83
(gm)Water WT.	4.39	5.22	5.25	5.72	0.09	0.09
(gm)Dry WT.	18.90	21.20	20.66	22.90	0.49	0.46
Moisture Content %	23.2%	24.6%	25.4%	25.0%	18.4%	19.6%
Average %					19.0%	



L.L	P.L	P.I
24.7%	19.0%	5.7%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :


 مشروع المطار السريع
 القطاع السابع
 محصل المركزي
 (رقم 6)


Name :


Sign :


 القاهرة نظرو للإستشارات
 ب. ق. ١٠٧٠٥٠
 ١٠٧٠٥٠ - ١٠٧٠٥٠

Name :

Sign :




Testing Date :	1/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-18	Material	fill material lavar	
Name Company	caro company		quantity	5000 m3	

Weight of empty mold :	6428.0
Mold Volume:	2104.9

MAX Dry Density	2.16
Water content %	6.8

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10898.0	11125.0	11289.0	11126	
WT. WET SOIL	4470.0	4697.0	4861.0	4698.0	
Wt. Density	2.124	2.231	2.309	2.232	

Tare No.	4	4	12	12	16	16	23	23		
Tare wt.	24.64	24.64	27.09	27.09	24.86	24.86	22.58	22.58		
Wt. Of wet soil & tare	140.64	140.64	154.82	154.82	146.15	146.15	153.30	153.30		
Wt. Of dry soil & tare	136.89	136.89	148.70	148.70	138.40	138.40	143.00	143.00		
Wt. Of water	3.8	3.8	6.1	6.1	7.8	7.8	10.3	10.3		
Wt. Of dry soil	112.3	112.3	121.6	121.6	113.5	113.5	120.4	120.4		
Water content %	3.3%	3.3%	5.0%	5.0%	6.8%	6.8%	8.6%	8.6%		
AV.Water content %	3.3%		5.0%		6.8%		8.6%			
Dry Density	2.055		2.125		2.162		2.056			

**Contractor**

Consultant

مشروع القطار السريع
للملاحة السابغة
من مصر الى كندا

ب. ق. ٥٦ - ٥٤٣ - ٥٤٥
س. ت. ١٠٦٧٠٥
المصلحة العامة والإستشارات



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	4/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-12	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16444
(gm)Mold WT. + Wet WT.	21386
(gm)Wet WT.	4942
Wet Density (g/cm ³)	2.270
Dry Density (g/cm ³)	2.136
Proctor Density (g/cm ³)	2.162
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	10
Tare WT. (gm)	27.86
(gm)Tare WT. +Wet WT.	124.6
(gm)Tare WT. +Dry WT.	118.9
(gm)Water WT.	5.7
(gm)Dry WT.	91.0
Moisture Content %	6.3

Swelling	
Mold No.	2
Date	4/12/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Pentration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	113.00	286.00	472.00	612.00	806.00	986.00	1181.00	1325.00	1429.00
(KN)Load	1.1	2.8	4.6	6.0	7.9	9.7	11.6	13.0	14.0



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR عند نسبة 100 %
2.50	6.00	13.4	44.9%	99	100	45.5%
5.00	12.99	20.0	64.8%			65.6%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

المعمل المركزي
للتربة والاسفلت
ب. ق. ١٠٦
١٠٦ - ١٠٦
١٠٦ - ١٠٦

المكتب
المستشاري الهندسي
م. ق. ١٠٦
١٠٦ - ١٠٦
١٠٦ - ١٠٦

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		4-12-2022							
Contractor reference	CA-Emb-19									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS					
Location to be Used	From 520+640 521+140	To 520+700 521+270	Fill -10 -8			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	30-11-2022		
2	Classification	m ³	5000	30-11-2022		
3	Proctor & O.m.c	m ³	5000	30-11-2022		
4	L.L & P.L & PI	m ³	5000	30-11-2022		
5	C.B.R	m ³	5000	4-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa Badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		4/12/2022	A		
QA/QC *	Ahmed Abo Zaid		4/12/2022	A		
GARB**	Hussien Fouad		4/12/2022	A		
Comments by	Kind Quantity approved as the Q.C.					
Employers Representative	Mohamed Ahmed		8-2-25	A.W.C		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST	    
	    

Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Adel		4-12-2022																
Contractor Reference	CA-Emb-19																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.9%	
4	ASTM D 4318	Atterberg limit	21.1%	
5	ASTM D 2974	Moisture content	6.2%	
6	ASTM D 1557	Modified proctor	2.14	
7	ASTM D 1883	CBR	61%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	4/12/2022	A
Contractor QA/QC *	Abdelilah SAMY	Abdelilah	4/12/2022	A
GARB**	Hussien Fouad	Hussien	4/12/2022	A
Employers Representative	Mohamed Ahmed	Mohamed	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	30/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-19	quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20267.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	1557.0	3405.0	3980.0	2159.0	2180.0	940.0	1485.0		A-1-a
(g)Cumulative Retained	1557.0	4962.0	8942.0	11101.0	13281.0	14221.0	15706.0		PRO
Cumulative Retained %	7.7	24.5	44.1	54.8	65.5	70.2	77.5		WC
Cumulative Passing %	92.3	75.5	55.9	45.2	34.5	29.8	22.5		CBR

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	64.70	185.25	258.60					
Cumulative Retained %	12.94	37.05	51.72					
Cumulative Passing %	87.06	62.95	48.28					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	92.3	75.5	55.9	45.2	34.5	29.8	22.5	19.6	14.2	10.9

ATTERBERG LIMITS	(.L.L.)LIQUID LIMIT	(.P.L.)PLASTIC LIMIT	(.P.I.)PLASTIC INDEX
	24.9%	21.1%	3.8%

Contractor

Consultant

مشروع القطار السريع
 القطاع السابع
 محمل المركزي
 (رقم 6)

القطار نظري والاستشارات
 10/11/2022
 10/11/2022

القطار نظري والاستشارات
 10/11/2022
 10/11/2022


 	Electric Express Train - HSR	 
---	------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	30/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-19	Material		fill material layer
Name Company	cairo company		quantity		5000 m3

Testing Results :-


Test	Liquid Limit				Plastic Limit	
No. of Ticks	36	28	22	17	-	-
Tare No.	30	4	7	15	F	B
Tare WT. (gm)	25.85	25.49	27.22	28.00	11.97	12.55
Tare WT. + Wet WT. (gm)	68.83	60.28	63.87	66.29	13.29	13.39
Tare WT. + Dry WT. (gm)	61.42	53.56	56.20	58.11	13.05	13.25
(gm)Water WT.	7.41	6.72	7.67	8.18	0.24	0.14
(gm)Dry WT.	35.57	28.07	28.98	30.11	1.08	0.70
Moisture Content %	20.8%	23.9%	26.5%	27.2%	22.2%	20.0%
Average %					21.1%	



L.L	P.L	P.I
24.9%	21.1%	3.8%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : 

Sign : 


Name :

Sign :



Name :

Sign :






PROCTOR TEST

Testing Date :	1/12/2022	Code	ZONE	520+500	522+000
Location :	KR:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-19	quantity	5000 m3	

Weight of empty mold :	6428.0	MAX Dry Density	2.141
Mold Volume:	2104.9	Water content %	6.2

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10869.0	11056.0	11213.0	11045	
WT. WET SOIL	4441.0	4628.0	4785.0	4617.0	
Wt. Density	2.110	2.199	2.273	2.193	

Tare No.	10	10	8	8	45	45	7	7		
Tare wt.	26.15	26.15	25.18	25.18	27.59	27.59	25.25	25.25		
Wt. Of wet soil & tare	129.40	129.40	146.24	146.24	132.19	132.19	137.58	137.58		
Wt. Of dry soil & tare	126.55	126.55	140.76	140.76	126.00	126.00	129.00	129.00		
Wt. Of water	2.9	2.9	5.5	5.5	6.2	6.2	8.6	8.6		
Wt. Of dry soil	100.4	100.4	115.6	115.6	98.4	98.4	103.8	103.8		
Water content %	2.8%	2.8%	4.7%	4.7%	6.3%	6.3%	8.3%	8.3%		
AV. Water content %	2.8%		4.7%		6.3%		8.3%			
Dry Density	2.052		2.099		2.139		2.026			



Contractor

Consultant

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

مختبر الطرق والإنشادات
ب.م.ت. ١٠٦٧٠٥٣
٤٤٤ - ٤٤٦

المكتب الاستشاري الهندسي



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	4/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-19	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21426
(gm)Wet WT.	4873
Wet Density (g/cm ³)	2.238
Dry Density (g/cm ³)	2.114
Proctor Density (g/cm ³)	2.140
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	12
Tare WT. (gm)	26.48
(gm)Tare WT. +Wet WT.	144
(gm)Tare WT. +Dry WT.	137.5
(gm)Water WT.	6.5
(gm)Dry WT.	111.0
Moisture Content %	5.9

Swelling	
Mold No.	2
Date	4/12/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penetration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	84.00	216.00	389.00	549.00	752.00	937.00	1187.00	1244.00	1486.00
(KN)Load	0.8	2.1	3.8	5.4	7.4	9.2	11.6	12.2	14.6



Calculations :-

Penetration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR (%)
2.50	5.38	13.4	40.3%	99	100	40.8%
5.00	12.19	20.0	60.9%			61.6%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)



MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name Eng/ Abdelrahman Adel	Sign 	Date 30/10/2022	Time																
Contractor reference	CA-Emb-2																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment		FILL MATERIAL RESULTS			
Location to be Used	From 520+750 521+140 521+000	To 520+780 521+240 521+010	Fill -11 -10 -10.5			
MAR Approval No			Date			
Supplier Name						
Test Requirement	Specification		Clause			
Reference Photos	Yes attached / No		Other			
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	26-10-2022		
2	Classification	m ³	5000	26-10-2022		
3	Proctor & O.m.c	m ³	5000	26-10-2022		
4	L.L & P.L & PI	m ³	5000	26-10-2022		
5	C.B.R	m ³	5000	30-10-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	eng / Ahmed mohammed		30/10/2022	A		
QA/QC *	Ahmed Abo Zaid		30/10/2022	A		
GARB**	Hussien Foad		30/10/2022	A		
Comments by	fill quantity approved with Qs					
Employers Representative	Mohamed Ahmed		8-2-23			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company							
Electric express train	Cairo for Roads and construction Company			k.k							
Issued by Contractor	Name	Sign	Date	Time							
	ENG/ Abdelrahman Adel		30/10/2022								
Contractor Reference	CA-Emb-22										
Received by ER			MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	6.2%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	5.8%	
6	ASTM D 1557	Modified proctor	2.13	
7	ASTM D 1883	CBR	35.6%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		30/10/2022	A
Contractor QA/QC *	Klassa		30/10/2022	A
GARB**	Hussien Foad		30/10/2022	A
Employers Representative	Mohamed Ahmed		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARSA MATROUH From Station 504+000 To Station 568+177	 الهيئة العامة للتخطيط وزارة التخطيط
Opreating Lab	AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	26-10-2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-2	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test


A-gradation of bulk materials				SAMPLE WEIGHT [g]		24949.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	0.0	3251.0	2941.0	2611.0	2116.0	2136.0	2025.0		A-1-a	
Cumulative Retained (g)	0.0	3251.0	6192.0	8803.0	10919.0	13055.0	15080.0		PRO	2.13
Cumulative Retained %	0.0	13.0	24.8	35.3	43.8	52.3	60.4		WC	5.80
Cumulative Passing %	100.0	87.0	75.2	64.7	56.2	47.7	39.6		CBR	35.60

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	202.40	372.80	421.30					
Cumulative Retained %	40.48	74.56	84.26					
Cumulative Passing %	59.52	25.44	15.74					


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	87.0	75.2	64.7	56.2	47.7	39.6	23.5	10.1	6.2

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor



Consultant



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 القطار السريع Electric Express Train SVSTFA SHAKER	Electric Express Train - HSR		 الهيئة العامة للطرق والنقل البنية التحتية الهيئة العامة للإعانة CAIRO
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177				

PROCTOR TEST


TESTING DATE:	2022/10/27	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-2	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6070.0
Mold Volume:	2113.0

MAX Dry Density	2.13
Water content %	5.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10510.0	10681.0	10826.0	10630	
WT. WET SOIL	4440.0	4611.0	4756.0	4560.0	
Wt. Density	2.101	2.182	2.251	2.158	

Tare No.	16	40	19	4	11	8	73	10		
Tare wt.	33.5	46.9	44.6	59.7	46.5	46.9	43	43.8		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.9	145.7	145.6	145.1	144.7	144.1	143.1	142.8		
Wt. Of water	3.1	4.3	4.4	4.9	5.3	5.9	6.9	7.2		
Wt. Of dry soil	113.4	98.8	101.0	85.4	98.2	97.2	100.1	99.0		
Water content %	2.7%	4.4%	4.4%	5.7%	5.4%	6.1%	6.9%	7.3%		
AV. Water content %	3.5%		5.0%		5.7%		7.1%			
Dry Density	2.029		2.077		2.129		2.015			




Contractor

المشرفة لمطرق والإنشاءات
106405
ب. عبد الله - 026 - 549 - 585



Consultant



California Bearing Ratio TEST

Testing Date :	30-10-2022	Code	ZONE	520+500	522+000
Location :	kp:521+000	CA-Emb-2	Material	fill material layer	
Company Name	carro company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	6075
Mold WT. + Wet WT. (gm)	10789
Wet WT. (gm)	4714
Wet Density (g/cm ³)	2.221
Dry Density (g/cm ³)	2.108
Proctor Density (g/cm ³)	2.130
Compaction %	99.0

Mositure Ratio After Compacted Mold	
Tare No.	18
Tare WT. (gm)	77.7
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	146.3
Water WT. (gm)	3.7
Dry WT. (gm)	68.6
Moisture Content %	5.4

Swelling	
Mold No.	6
Date	30-10-2022
Initial Height (mm)	3.00
Final Height (mm)	3.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.06	0.09	0.11	0.14	0.17	0.19	0.21	0.24	0.32
Load (KN)	1.8	2.7	3.3	4.2	5.1	5.7	6.3	7.2	9.6



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	4.20	13.4	31.5%	99	98	31.2%
5.00	7.20	20.0	36.0%			35.6%

Lab. Specialist


Name :

Sign :

Lab. Engineer

Name :


Sign :



Consultant Engineer

Name :

Sign :



MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Ade	<i>Abdel Rahman</i>	4/12/2022																	
Contractor Reference	CA-Emb-20																			
Received by ER	<i>[Signature]</i>	MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.5%	
4	ASTM D 4318	Atterberg limit	19.7%	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.11	
7	ASTM D 1883	CBR	31%	
Comments by:			Comments by:	
			All test under Responsibility Third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	<i>Abdel Rahman</i>	4/12/22	A
Contractor QA/QC *	Abdallah SAMY	<i>Abdallah</i>	4/12/22	A
GARB**	Hussien Fouad	<i>Hussien</i>	4/12/22	A
Employers Representative	Mohamed Ahmed	<i>[Signature]</i>	15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	30/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	A-Emb-20	quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20611.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	311.0	1825.0	4806.0	2151.0	2219.0	1362.0	2097.0		A-2-4
(g)Cumulative Retained	311.0	2136.0	6942.0	9093.0	11312.0	12674.0	14771.0	PRO	2.11
Cumulative Retained %	1.5	10.4	33.7	44.1	54.9	61.5	71.7	WC	7.0
Cumulative Passing %	98.5	89.6	66.3	55.9	45.1	38.5	28.3	CBR	31%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
(g)Cumulative Retained	63.73	176.00	243.40				
Cumulative Retained %	12.75	35.20	48.68				
Cumulative Passing %	87.25	64.80	51.32				

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.5	89.6	66.3	55.9	45.1	38.5	28.3	24.7	18.4	14.5

ATTERBERG LIMITS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	27.2%	19.7%	7.5%

Contractor

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

المشروع نظري والإشادات
ب.ت. ١٠٦٧٠٥
٥٤٥ - ٥٤٦ - ٥٤٧

Consultant

المشروع نظري والإشادات
ب.ت. ١٠٦٧٠٥
٥٤٥ - ٥٤٦ - ٥٤٧

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فليفل	 SVS/TA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة القومية للإنفاق الهيئة القومية للإنفاق (GARBLT)


PROCTOR TEST

Testing Date :	1/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-2	quantity	5000 m3	

Weight of empty mold :	6428.0	MAX Dry Density	2.110
Mold Volume:	2104.9	Water content %	7.00

trial no :	1	2	3	4		
Wt. Of Mold+ wet soil	10845.0	11020.0	11185.0	11110		
WT. WET SOIL	4417.0	4592.0	4757.0	4682.0		
Wt. Density	2.098	2.182	2.260	2.224		

Tare No.	16	16	2	2	1	1	5	5				
Tare wt.	25.96	25.96	26.13	26.13	27.23	27.23	27.23	27.23				
Wt. Of wet soil & tare	148.2	148.2	160.5	160.5	118.6	118.6	125.5	125.5				
Wt. Of dry soil & tare	143.88	143.88	153.69	153.69	112.45	112.45	117.16	117.16				
Wt. Of water	4.3	4.3	6.8	6.8	6.1	6.1	8.4	8.4				
Wt. Of dry soil	117.9	117.9	127.6	127.6	85.2	85.2	89.9	89.9				
Water content %	3.7%	3.7%	5.3%	5.3%	7.2%	7.2%	9.3%	9.3%				
AV. Water content %	3.7%		5.3%		7.2%		9.3%					
Dry Density	2.024		2.072		2.109		2.035					



Contractor

Consultant

مشاريع
القطاع السياحي
معمل المركزي
(رقم 6)

القاهرة نظرو الإنشاءات
ب. ت. ١٠٩٧٠٥
١٠٩٧٠٥ - ١٠٩٧٠٥

المكتب
الهندسي
للإنشاءات



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	4/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	calro company	CA-Emh-20	quantity	5000 m3	

:- Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16444
(gm)Mold WT. + Wet WT.	21321
(gm)Wet WT.	4806
Wet Density (g/cm ³)	2.207
Dry Density (g/cm ³)	2.075
Proctor Density (g/cm ³)	2.110
Compaction %	98

Mositure Ratio After Compacted Mold	
Tare No.	11
Tare WT. (gm)	25.13
(gm)Tare WT. +Wet WT.	157
(gm)Tare WT. +Dry WT.	149.1
(gm)water wt	7.9
(gm)Dry WT.	124.0
Moisture Content %	6.4

Swelling	
Mold No.	2
Date	4/12/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0.0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

63.73	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	22.00	75.00	149.00	211.00	316.00	401.00	528.00	645.00	842.00
(KN)Load	0.2	0.7	1.5	2.1	3.1	3.9	5.2	6.3	8.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	2.07	13.4	15.5%	98	100	15.8%
5.00	6.32	20.0	31.6%			32.1%

Lab. Specialist

Name :

Sign :

Lab. Engineer



Name :

Sign :

Consultant Engineer

Name :

Sign :




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فكري	 SHAKER	Electric Express Train - HSR	 SASBIT	 الهيئة القومية للإتفاق
--	---	-------------------------------------	---	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	1/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-20	quaintity	5000 m3	

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	31	27	23	17	-	-
Tare No.	30	3	4	7	B	C
Tare WT. (gm)	25.83	25.25	25.21	27.27	11.96	13.37
Tare WT. + Wet WT. (gm)	52.84	47.26	51.71	51.04	12.53	14.02
Tare WT. + Dry WT. (gm)	47.35	42.64	45.91	45.63	12.43	13.92
(gm)Water WT.	5.49	4.62	5.80	5.41	0.10	0.10
(gm)Dry WT.	21.52	17.39	20.70	18.36	0.47	0.55
Moisture Content %	25.5%	26.6%	28.0%	29.5%	21.3%	18.2%
Average %					19.7%	



L.L	P.L	P.I
27.2%	19.7%	7.5%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : *Hassan*

Name :



Name :

Sign : مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

Sign :





Sign :

MATERIAL INSPECTION REQUEST	    					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		5-12-2022																	
Contractor reference	CA-Emb-21																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment			FILL MATERIAL RESULTS		
Location to be Used	From 521+920 520+880	To 522+000 520+980	Fill -7.5 -11			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	1-12-2022		
2	Classification	m ³	5000	1-12-2022		
3	Proctor & O.m.c	m ³	5000	1-12-2022		
4	L.L & P.L & PI	m ³	5000	1-12-2022		
5	C.B.R	m ³	5000	5-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa Badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		5/12/2022	A
QA/QC *	Hassan		5/12/2022	A
GARB**	Hussien Fouad		5/12/2022	A
Comments by	Final quantity approved with Res			
Employers Representative	Mohamed Ahmed		8-2-21	AWC

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Ade		5-12-2022																
Contractor Reference	CA-Emb-21																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12.6%	
4	ASTM D 4318	Atterberg limit	20.4%	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.12	
7	ASTM D 1883	CBR	48%	
Comments by:			Comments by:	
			All test under Responsibility Third party.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Alai	Abdelrahman	5/12/2022	A
Contractor QA/QC *	Abdallah SAMY	Abdallah	5/12/2022	A
GARB**	Hussien Fouad	Hussien	5/12/2022	A
Employers Representative	Mohamed A. H. A.	Mohamed	13-1-25	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	1/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-21	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		26157.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	373.0	2583.0	6135.0	2822.0	2260.0	1500.0	2681.0		A-1-a
(g)Cumulative Retained	373.0	2956.0	9091.0	11913.0	14173.0	15673.0	18354.0	PRO	2.12
Cumulative Retained %	1.4	11.3	34.8	45.5	54.2	59.9	70.2	WC	7.0
Cumulative Passing %	98.6	88.7	65.2	54.5	45.8	40.1	29.8	CBR	48%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
(g)Cumulative Retained	66.80	203.00	289.00				
Cumulative Retained %	13.36	40.60	57.80				
Cumulative Passing %	86.64	59.40	42.20				

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.6	88.7	65.2	54.5	45.8	40.1	29.8	25.8	17.7	12.6

ATTERBERG LIMITS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	24.8%	20.4%	4.4%

Contractor


Consultant



5/12/2022

 Hassan




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد شكري	 SVS TRA SHAKER	Electric Express Train - HSR	 CAE	 الهيئة القومية للإزفاق القناة السويسية (CAE)
--	---	-------------------------------------	--	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	2/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-21	Material	fill material layer	
Name Company	cairo-company		quantity	5000 m3	

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	32	27	22	18	-	-
Tare No.	46	45	10	2	B	G
Tare WT. (gm)	27.22	25.36	26.51	22.91	11.98	11.20
Tare WT. + Wet WT. (gm)	52.09	48.57	46.88	49.62	12.83	11.94
Tare WT. + Dry WT. (gm)	47.56	44.10	42.68	43.84	12.68	11.82
(gm)Water WT.	4.53	4.47	4.20	5.78	0.15	0.12
(gm)Dry WT.	20.34	18.74	16.17	20.93	0.70	0.62
Moisture Content %	22.3%	23.9%	26.0%	27.6%	21.4%	19.4%
Average %					20.4%	



L.L	P.L	P.I
24.8%	20.4%	4.4%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :

Sign :

Name :

Sign :

Name :

Sign :

Name : *Hasan*
 Sign : *Hasan*
 معمل المركزي
 القنصلية
 شارع السريخ
 رقم ١٦

Name : *Hasan*
 Sign : *Hasan*
 معمل المركزي
 القنصلية
 شارع السريخ
 رقم ١٦

Name : *Hasan*
 Sign : *Hasan*
 معمل المركزي
 القنصلية
 شارع السريخ
 رقم ١٦

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فكري	 Electric Express Train محطة مصر SVST/FA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للمرور والملاحة والنقل (GARBLT) الهيئة القومية للإنفاق القناة السويسية SUEZ CANAL AUTHORITY القناة السويسية SUEZ CANAL


PROCTOR TEST

Testing Date :	2/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-21	quantity	5000 m3	

Weight of empty mold :	6210.0	MAX Dry Density	2.120
Mold Volume:	2104.9	Water content %	7.00

trial no :	1	2	3	4		
Wt. Of Mold+ wet soil	10623.0	10811.0	10992.0	10854		
WT. WET SOIL	4413.0	4601.0	4782.0	4644.0		
Wt. Density	2.097	2.186	2.272	2.206		

Tare No.	16	16	8	8	1	1	4	4				
Tare wt.	25.69	25.69	26.29	26.29	26.74	26.74	25.48	25.48				
Wt. Of wet soil & tare	145.9	145.9	103.3	103.3	143.8	143.8	125.1	125.1				
Wt. Of dry soil & tare	142.65	142.65	99.43	99.43	135.84	135.84	116.25	116.25				
Wt. Of water	3.2	3.2	3.8	3.8	7.9	7.9	8.8	8.8				
Wt. Of dry soil	117.0	117.0	73.1	73.1	109.1	109.1	90.8	90.8				
Water content %	2.7%	2.7%	5.2%	5.2%	7.3%	7.3%	9.7%	9.7%				
AV. Water content %	2.7%		5.2%		7.3%		9.7%					
Dry Density	2.041		2.077		2.118		2.010					



Contractor

Consultant

مشاريع الطرق والبنية التحتية
القسم الثاني
معمل المركزي
رقم ٥

القاهرة لطرق والبنية التحتية
س.ت. ١٠٦٧٠٥
ب.ق. ٥٤٦ - ٥٤٧
٥٤٥ - ٥٤٨

المكتب
الاستشاري
الهندسي
Hassan

Hassan
5.12



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	5/12/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-21	Material	fill material layer	
Name Company	calro company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16444
(gm)Mold WT. + Wet WT.	21328
(gm)Wet WT.	4884
Wet Density (g/cm ³)	2.243
Dry Density (g/cm ³)	2.101
Proctor Density (g/cm ³)	2.120
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	25.26
(gm)Tare WT. +Wet WT.	158.24
(gm)Tare WT. +Dry WT.	149.85
(gm)water wt	8.4
(gm)Dry WT.	124.6
Moisture Content %	6.7

Swelling	
Mold No.	2
Date	5/12/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

Penetration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	95.00	149.00	258.00	368.00	498.00	625.00	824.00	985.00	1145.00
(KN)Load	0.9	1.5	2.5	3.6	4.9	6.1	8.1	9.7	11.2



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	3.61	13.4	27.0%	99	100	27.3%
5.00	9.65	20.0	48.2%			48.6%

Lab. Specialist

Name :

Sign :

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

Lab. Engineer

Name :

Sign :

المشرفة نظارة والاشادات
بشأن : ١٠٦٧٠٥
بشأن : ١٥٦ - ٥٩٢ - ٥٥٥

Consultant Engineer

Name :

Sign :

Hasan
2022

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K					
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		5/12/2022							
Contractor reference	CA-Emb-22									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	520+980	521+000	-11			
	521+820	521+900	-7			
MAR Approval No	521+700	521+800	-7	Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	1-12-2022		
2	Classification	m ³	5000	1-12-2022		
3	Proctor & O.m.c	m ³	5000	1-12-2022		
4	L.L & P.L & PI	m ³	5000	1-12-2022		
5	C.B.R	m ³	5000	5-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Mahgob laboratory) and the results founded meet the specifications and accepted.						
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		5/12/2022	A		
QA/QC *	Hassan		5/12/2022	A		
GARB**	Hussien Fouad		5/12/2022	A		
Comments by	Ridha Ghutaty approval with @s					
Employers Representative	Mohamed Ahs		8-2-25	Awe		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		5/12/2022	
Contractor Reference	CA-Emb-22			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.3%	
4	ASTM D 4318	Atterberg limit	18.7%	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	54.2%	
Comments by:		Comments by:		
		- All test under Responsibility third party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		5/12/2022	A
Contractor QA/QC *	Hassan		5/12/2022	A
GARB**	Hussien Fouad		5/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-2025	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	2/12/2022	code		
LOCATION	K.P. 521+560		ZONE	520+500 522+000
NAME COMPANY	CAIRO	CA-Emb-22		

1-visual inspection test

2-Gradient test


A-gradation of bulk materials				SAMPLE WEIGHT (g)		26609.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	393.0	2953.0	4820.0	3125.0	2456.0	1596.0	2427.0		A-1-a
Cumulative Retained (g)	393.0	3346.0	8166.0	11291.0	13747.0	15343.0	17770.0	PRO	2.17
Cumulative Retained %	1.5	12.6	30.7	42.4	51.7	57.7	66.8	WC	7.00
Cumulative Passing %	98.5	87.4	69.3	57.6	48.3	42.3	33.2	CBR	54.20

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	98.00	195.00	300.00					
Cumulative Retained %	19.60	39.00	60.00					
Cumulative Passing %	80.40	61.00	40.00					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.5	87.4	69.3	57.6	48.3	42.3	33.2	26.7	20.3	13.3

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	21.60	18.70	3.00

Contractor



 شركة المحجوب للمقاولات الهندسية والتشييد

 معمل اختبارات وأبحاث التربة

 القطار السريع - فوكه - مطروح

انشودة نظرة والإنشاءات

 م.ت. ١٠٦٧٠٥

 ب.ض. ٤٤٦ - ٣٤٩

Consultant

Hassan






 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فؤاد	 SVS TRA	Electric Express Train - HSR	 الهيئة العامة للنقل وزارة النقل
--	--	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	2022-12-02	Code:			
Location:	521+560		ZONE	520+500	522+000
Layer No. :	CAIRO	CA-Emb-22			

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	16	23	29	35	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	22.82	35.28	29.05	33.13	10.98	19.33
Tare WT. + Wet WT. (gm)	42.57	56.01	49.02	51.09	11.66	20.01
Tare WT. + Dry WT. (gm)	38.92	52.29	45.53	48.04	11.55	19.90
Water WT. (gm)	3.65	3.72	3.49	3.05	0.11	0.11
Dry WT. (gm)	16.10	17.01	16.48	14.91	0.57	0.57
Moisture Content %	22.7%	21.9%	21.2%	20.5%	19.1%	18.3%
Average %					18.7%	



L.L	P.L	P.I
21.6%	18.7%	3.0%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :


Sign :

Name :
 Sign :
 المعمل المختبر للتربة والمواد الجيوتقنية
 القاهرة - فوكه - مطروح

Name :

Sign :

Name : Hassan
 Sign :
 المهندس هاشم



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد مختار	 SVS TRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للقناة القناة السويسية لمصر (S.A.S.C.)

PROCTOR TEST


TESTING DATE:	3/12/2022	code		
LOCATION	K.P. 521+560		ZONE	520+500 522+000
NAME COMPANY	CAIRO	CA-Emb-22		

Weight of empty mold :	6055.0
Mold Volume:	2032.0

MAX Dry Density	2.17
Water content %	7

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10235.0	10512.6	10763.1	10666	
WT. WET SOIL	4180.0	4457.6	4708.1	4611.0	
Wt. Density	2.057	2.194	2.322	2.269	

Tare No.	1	2	3	4	5	6	7	8		
Tare wt.	33.19	27.39	29.26	34.61	35.82	30.10	32.91	36.43		
Wt. Of wet soil & tare	134.82	134.85	174.92	122.54	121.85	145.93	155.23	149.92		
Wt. Of dry soil & tare	132.2	131.9	168.7	118.5	116.4	138.0	145.7	141.3		
Wt. Of water	2.6	2.9	6.2	4.0	5.5	7.9	9.6	8.6		
Wt. Of dry soil	99.1	104.5	139.4	83.9	80.6	107.9	112.7	104.9		
Water content %	2.6%	2.8%	4.5%	4.8%	6.8%	7.3%	8.5%	8.2%		
AV. Water content %	2.7%		4.6%		7.1%		8.3%			
Dry Density	2.003		2.097		2.169		2.094			



 المحجوب	Contractor شركة المحجوب للتجارة والبناء والتشييد معمل اختبارات وأبحاث التربة القطار السريع - فوكه - مطروح
--	---

القنطرة لطريق الإنشاءات
 س.ت: ١٠٦٧٠٥
 ب.ق: ٥٢٦ - ٥٢٥

Consultant I. Hassan

California Bearing Ratio TEST

Testing Date :	5/12/2022	Code	ZONE	520+500	522+000
Location :	521+560	CA-Emb-22			
Layer No. :	CAIRO				

Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.074
Proctor Density (g/cm ³)	2.170
Compaction %	96

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. + Wet WT. (gm)	233
Tare WT. + Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	7.0

Swelling	
Mold No.	55
Date	5/12/2022
Initial Height (mm)	4.50
Final Height (mm)	4.50
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	33.00	110.00	245.00	421.00	598.00	785.00	983.00	1119.00	1198.00
Load (KN)	0.3	1.1	2.4	4.1	5.9	7.7	9.6	11.0	11.7



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	4.13	13.4	30.9%	99	98	30.6%
5.00	10.97	20.0	54.8%			54.2%

Lab. Specialist

Name :

Sign :

Lab. Engineer
 Name :
 Sign :

Consultant Engineer

Name :



Sign :

القاهرة نظروا
 ١٠٦٣٥٠٠
 ١٠٦٣٥٠٠



عمل اختبارات وإيجات التربة
 القطار السريع - فوكه - مطروح

Hassan
 MHA

MATERIAL INSPECTION REQUEST	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		6-12-2022							
Contractor reference	CA-EMB-23									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+800	521+820	-7			
	521+320	521+440	-7			
MAR Approval No	521+440	521+520	-7	Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	2-12-2022		
2	Classification	m ³	5000	2-12-2022		
3	Proctor & O.m.c	m ³	5000	2-12-2022		
4	L.L & P.L & PI	m ³	5000	2-12-2022		
5	C.B.R	m ³	5000	6-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed	Ahmed mohammed	6/12/2022	A		
QA/QC *	Hasra		6/12/2022	A		
GARB**	Hussien Fouad	Hussien	6/12/2022	A		
Comments by	Ridwaty approved with Qs					
Employers Representative	Mohamed Ahmed		8-2-25	Awe		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company							
Electric express train	Cairo for Roads and construction Company		k.k							
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		6-12-2022							
Contractor Reference	CA-Emb-23									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	7.1%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.3%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	64.7%	
Comments by:		Comments by:		
		All test under Responsibility third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel	Abdelrahman		
Contractor QA/QC *	Hassan			
GARB**	Hussien Jouda	Hussien	6-12-2022	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتيل	 لنهر الكبري السريع Electric Express Train SVSTTA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإزفاق وزارة المواصلات والاقتصاد (MOT)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	02/12/2022	Code	Station	520+500	522+000
LOCATION	kp: 520+700	CA-Emb-23	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		30411.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	4120.0	3685.0	3195.0	3145.0	3441.0	3782.0	3624.0		A-1-a
Cumulative Retained (g)	4120.0	7805.0	11000.0	14145.0	17586.0	21368.0	24992.0	PRO	2.15
Cumulative Retained %	13.5	25.7	36.2	46.5	57.8	70.3	82.2	WC	6.30
Cumulative Passing %	86.5	74.3	63.8	53.5	42.2	29.7	17.8	CBR	64.70

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	76.00	194.00	301.00				
Cumulative Retained %	15.20	38.80	60.20				
Cumulative Passing %	84.80	61.20	39.80				


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	86.5	74.3	63.8	53.5	42.2	29.7	17.8	15.1	10.9	7.1

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor

Consultant

القاهرة مطروح والإسكندرية
س.ت. ١٠٦٧٠٥
ب.ف. ٥٥٥ - ٥٩٢ - ٠٢٦



6/12/2022
Hassan MA

المكتب الاستشاري الهندسي
أ.د. خالد فتيل

	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	2-12-2022	Code	Station	520+500	522+000
LOCATION	km: 520+700	CA-Emb-23	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.15
Water content %	6.3

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10524.0	10970.0	11003.0	10954	
WT. WET SOIL	4487.0	4933.0	4966.0	4917.0	
Wt. Density	2.062	2.267	2.282	2.260	

Tare No.	26	40	8	11	18	32	17	16		
Tare wt.	55	46.4	46.8	46.1	77.7	74.4	59.5	33.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.9	144.0	144.3	144.5	144.9	144.6	142.1	140.1		
Wt. Of water	3.1	6.0	5.7	5.5	5.1	5.4	7.9	9.9		
Wt. Of dry soil	123.0	267.8	97.5	98.4	67.2	70.2	82.6	106.2		
Water content %	2.5%	2.2%	5.8%	5.6%	7.6%	7.7%	9.6%	9.3%		
AV. Water content %	2.4%		5.7%		7.6%		9.4%			
Dry Density	2.014		2.144		2.120		2.065			



Contractor

Consultant

القاهرة للطرق والإنشاءات
 س.ت: ١٠٦٧٠٥٥
 ب. ق. ٥٥٥ ٥٥٨٢ ١٠٥٦



6/12
 2022
 MA

California Bearing Ratio TEST

Testing Date :	6-12-2022	Code	Station	520+500	522+000
Location :	kp:520+700	CA-EMB-23	Material	fill material layer	
Company Name	cairo company		quantity	5000m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2168
Mold WT. (gm)	5089
Mold WT. + Wet WT. (gm)	10035
	49.46
Wet Density (g/cm ³)	2.281
Dry Density (g/cm ³)	2.145
Proctor Density (g/cm ³)	2.150
Compaction %	99.8

Moisture Ratio After Compacted Mold	
Tare No.	17
Tare WT. (gm)	59.5
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	144.6
	3398
	5.4
Dry WT. (gm)	144.6
Moisture Content %	6.3

Swelling	
Mold No.	2
Date	6-12-2022
Initial Height (mm)	2.00
Final Height (mm)	2.60
Difference	1
Sample Height (mm)	12.00
Swelling Ratio %	5%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.08	0.12	0.21	0.25	0.31	0.35	0.39	0.44	0.51
Load (KN)	2.4	3.6	6.3	7.5	9.3	10.5	11.7	13.2	15.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	7.50	13.4	56.2%	100	98	55.2%
5.00	13.20	20.0	65.9%			64.7%

Lab. Specialist

Name :

Sign :

القاهرة للطرق والانشاءات
 ١٠٦٧٠٥
 ب ق ٥٥٢ - ٥٥٦

Lab. Engineer

Name :

Sign :

Electric Express Train
 Central Lab Number 4
 Soc 7/Pala - Matrouh


Consultant Engineer

Name :




Sign :

6/12/2022
 ١٠٦٧٠٥
 ب ق ٥٥٢ - ٥٥٦

MATERIAL INSPECTION REQUEST	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		7-12-2022							
Contractor reference	CA-EMB-24									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment					FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill							
	521+520	521+560	-7							
	521+900	522+000	-7							
	521+000	521+050	-8.5							
MAR Approval No					Date					
Supplier Name										
Test Requirement					Specification	Clause				
Reference Photos	Yes attached / No				Other					
Item	Description	Unit	Quantity	Arrival Date	Note					
1	Sieve analysis	m ³	5000	3-12-2022						
2	Classification	m ³	5000	3-12-2022						
3	Proctor & O.m.c	m ³	5000	3-12-2022						
4	L.I & P.I & PI	m ³	5000	3-12-2022						
5	C.B.R	m ³	5000	7-12-2022						
Comments by:					Comments by:					
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.					Test result for estimated quantities of about 5000 m3					
APPROVAL STATUS										
Organisation	Name	Sign	Date	A-AWC-R						
Contractor	Eng / Ahmed mohammed		7/12/2022	A						
QA/QC *	Hassan		7/12/2022	A						
GARB**	Hussien Fouad		7/12/2022	A						
Comments by	fill quantity approved with Ccs									
Employers Representative	Mohamed Ahmed		8-2-23	A						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Ade		7-12-2022	
Contractor Reference	CA-Emb-24			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-2-4)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.6%	
4	ASTM D 4318	Atterberg limit	16.9%	
5	ASTM D 2974	Moisture content	7.2%	
6	ASTM D 1557	Modified proctor	2.11	
7	ASTM D 1883	CBR	55.8%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		7/12/2022	A
Contractor QA/QC *	Hassan		7/12/2022	A
GARB**	Hassan Fouad		7/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتيل	 SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARSА MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للإحصاء وزارة التخطيط والتنمية الاقتصادية (SAGI)
		Opreating Lab		
		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	03/12/2022	Code			
LOCATION	K.P(521+000)	CA-Emb-24	ZONE	520+500	522+000
NAME COMPANY	cairo company				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		42845.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	5231.0	3987.0	3752.0	4521.0	3937.0	4126.0	4652.0		A-2-4
Cumulative Retained (g)	5231.0	9218.0	12970.0	17491.0	21428.0	25554.0	30206.0	PRO	2.11
Cumulative Retained %	12.2	21.5	30.3	40.8	50.0	59.6	70.5	WC	7.20
Cumulative Passing %	87.8	78.5	69.7	59.2	50.0	40.4	29.5	CBR	55.80

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	62.00	154.00	270.00				
Cumulative Retained %	12.40	30.80	54.00				
Cumulative Passing %	87.60	69.20	46.00				


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	87.8	78.5	69.7	59.2	50.0	40.4	29.5	25.8	20.4	13.6

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	24.85%	16.90%	7.94%

Contractor

Consultant

استشارة مخطوطات والإنشاءات
س ٢٠٢٢
١٠٦٣٠٥
٥٤٥ - ٥٤٢ - ٥٤٦



7/12/2022
Hassan
المكتب الاستشاري
الهندسي


 	Electric Express Train - HSR	 
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	12/03/2022	Code			
Location:	K.P (S21+000)		ZONE	520+500	522+000
Company Name	cairo company	CA-Emb-24			

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	36	30	23	17	-	-
Tare No.	16	15	26	11	90	21
Tare WT. (gm)	33.40	31.60	55.00	46.3	62.60	54.70
Tare WT. + Wet WT. (gm)	67.50	70.10	85.60	74.10	65.40	58.80
Tare WT. + Dry WT. (gm)	61.60	63.10	79.60	67.80	65.0	58.2
Water WT. (gm)	5.90	7.00	6.00	6.30	0.40	0.60
Dry WT. (gm)	28.20	31.50	24.60	21.50	2.40	3.50
Moisture Content %	20.9%	22.2%	24.4%	29.3%	16.7%	17.1%
Average %					16.9%	



L.L	P.L	P.I
24.85%	16.90%	7.94%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Sign :
-------------------------------------	-----------------------------------	---

	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		


PROCTOR TEST

TESTING DATE:	3-12-2022	Code			
LOCATION	K.P.(521+000)		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Em6-24			

Weight of empty mold :	6037.0	MAX Dry Density	2.11
Mold Volume:	2176.0	Water content %	7.2


trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10265.0	10423.0	10952.0	10681	
WT. WET SOIL	4228.0	4386.0	4915.0	4644.0	
Wt. Density	1.943	2.016	2.259	2.134	

Tare No.	8	40	17	18	90	19	17	33		
Tare wt.	46.8	46.4	59.5	77.7	62.5	44.4	59.5	73.6		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	145.6	141.1	145.3	146.2	144.1	143.1	142.2	143.5		
Wt. Of water	4.4	8.9	4.7	3.8	5.9	6.9	7.8	6.5		
Wt. Of dry soil	123.0	267.8	85.8	68.5	81.6	98.7	82.7	69.9		
Water content %	3.6%	3.3%	5.5%	5.5%	7.2%	7.0%	9.4%	9.3%		
AV. Water content %	3.5%		5.5%		7.1%		9.4%			
Dry Density	1.878		1.910		2.109		1.951			



Contractor

القاهرة للإنشاء والإستشارات
ب. ص. ١٠٦٧٠٥
ب. ق. ٥٤٥ - ٥٤٢ - ٥٤٦



Consultant

Hassan
7/12/2022

 ENGINEERING CONSULTING OFFICE المكتب الهندسي الاستشاري أ. د. خالد فؤاد	 SVS/TA SHAKER	Electric Express Train - HSR	 الهيئة العامة للنقل والبنية التحتية (CAE)	 الهيئة العامة للإحصاء مصر
---	--	-------------------------------------	---	---

California Bearing Ratio TEST


Testing Date :	07-12-2022	Code			
Location :	K.P(521+000)	CA-Emb-24	ZONE	520+500	522+000
Company Name	cairo company				

Test Results :-

Compaction % for Mold		Moisture Ratio After Compacted Mold		Swelling	
Mold No.	3	Tare No.	8	Mold No.	3
Mold Vol. (cm ³)	2025	Tare WT. (gm)	46.8	Date	07-12-2022
Mold WT. (gm)	5034	Tare WT. +Wet WT. (gm)	150	Initial Height (mm)	4.00
Mold WT. + Wet WT. (gm)	9617	Tare WT. +Dry WT. (gm)	143	Final Height (mm)	4.55
Wet WT. (gm)	4583	3398	7.0	Difference	1
Wet Density (g/cm ³)	2.263	Dry WT. (gm)	96.2	Sample Height (mm)	11.90
Dry Density (g/cm ³)	2.110	Moisture Content %	7.3	Swelling Ratio %	5%
Proctor Density (g/cm ³)	2.110				
Compaction %	100.0				



Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.08	0.13	0.17	0.23	0.29	0.32	0.38	0.50
Load (KN)	0.9	2.4	3.9	5.1	6.9	8.7	9.6	11.4	15.0



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	5.10	13.4	38.2%	100	98	37.4%
5.00	11.40	20.0	56.9%			55.8%

Lab. Specialist Name:  Sign: 	Lab. Engineer Name:  Sign: 	Consultant Engineer Name:  Sign: 
---	---	---

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		10-12-2022							
Contractor reference	CA-EMB-25									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment		FILL MATERIAL RESULTS		
Location to be Used	From	To	Fill		
	521+050	521+080	-8.5		
	520+800	520+880	-11		
MAR Approval No	520+700	520+770	-10	Date	
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	6-12-2022	
2	Classification	m ³	5000	6-12-2022	
3	Proctor & O.m.c	m ³	5000	6-12-2022	
4	L.L & P.L & PI	m ³	5000	6-12-2022	
5	C.B.R	m ³	5000	10-12-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		10/12/2022	A
QA/QC *	Hassan		10/12/2022	A
GARB**	Hussien Fouad		10/12/2022	A
Comments by	Rid Gantaty approval with BS			
Employers Representative	Mohamed Ahmed		8-2-23	Awc

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Adel	<i>Abdel Rahman</i>	10-12-2022																
Contractor Reference	CA-EMB-25																		
Received by ER	<i>[Signature]</i>	MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12.6%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	5.8%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	51.4%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	10/12/2022	A
Contractor QA/QC *	Hassan	<i>[Signature]</i>	10/12/2022	A
GARB**	Hussien Fouad	<i>[Signature]</i>	10/12/2022	A
Employers Representative	Mohamed Ahmed	<i>[Signature]</i>	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

1-visual inspection test

2-Gradient test


<u>A-gradation of bulk materials</u>			SAMPLE WEIGHT [g]			25054.00		gm		table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS		soil classify
Mass retained (g)	2265.0	2502.0	2421.0	2356.0	2654.0	2125.0	2786.0			A-1-a
Cumulative Retained (g)	2265.0	4767.0	7188.0	9544.0	12198.0	14323.0	17109.0			PRO
Cumulative Retained %	9.0	19.0	28.7	38.1	48.7	57.2	68.3		WC	5.80
Cumulative Passing %	91.0	81.0	71.3	61.9	51.3	42.8	31.7		CBR	51.50

<u>B-soft material gradation</u>				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	83.00	195.00	301.00					
Cumulative Retained %	16.60	39.00	60.20					
Cumulative Passing %	83.40	61.00	39.80					

[illegible]

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor



Consultant

Hasse

10/12 2022


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SYSTRA SHAKER	Electric Express Train - HSR	 الهيئة العامة للنقل لدى وكالات النقل (CAEGLT)
--	--	-------------------------------------	--

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	07/12/2022	Code	FROM STA:	520+500	522+000
Location:	kp:521+500		Material:	fill material layer	
Company Name	cairo company	CA-Emb-25	quantity	5000m3	



Testing Results :-

Test	Liquidity Limit				Plastic Limit	
No. of Ticks	36	31	21	16	-	-
Tare No.	20	16	40	7	10	18
Tare WT. (gm)	60.90	33.90	46.40	42.8	43.70	77.70
Tare WT. + Wet WT. (gm)	82.60	51.60	68.30	69.20	47.60	79.30
Tare WT. + Dry WT. (gm)	78.70	48.20	63.80	63.60	47.0	79.0
Water WT. (gm)	3.90	3.40	4.50	5.60	0.65	0.28
Dry WT. (gm)	17.80	14.30	17.40	20.80	3.25	1.32
Moisture Content %	21.9%	23.8%	25.9%	26.9%	20.0%	21.2%
Average %					20.6%	



L.L	P.L	P.I
24.86%	20.61%	4.25%

Lab. Specialist	Lab. Engineer	Consultant Engineer
Name :	Name :	Name : Hk 8ca
Sign :	Sign :	Sign : 10/12/2022

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. نادر فكري	 SVSCTA SHAKER	Electric Express Train - HSR		 الهيئة العامة للنقل وزارة النقل مصر
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177				


PROCTOR TEST


TESTING DATE:	07/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+500	CA-Emb-25	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0	MAX Dry Density	2.17
Mold Volume:	2176.0	Water content %	5.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10654.0	10895.0	11037.0	10864	
WT. WET SOIL	4617.0	4858.0	5000.0	4827.0	
Wt. Density	2.122	2.233	2.298	2.218	

Tare No.	8	27	19	25	33	90	32	10		
Tare wt.	46.8	54.1	44.4	75.8	73.6	62.5	74.4	33.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.2	143.2	145.6	146.8	145.6	145.1	144.3	141.4		
Wt. Of water	2.8	6.8	4.4	3.2	4.4	4.9	5.7	8.6		
Wt. Of dry soil	123.0	267.8	101.2	71.0	72.0	82.6	69.9	107.5		
Water content %	2.3%	2.5%	4.3%	4.5%	6.1%	5.9%	8.2%	8.0%		
AV. Water content %	2.4%		4.4%		6.0%		8.1%			
Dry Density	2.072		2.138		2.167		2.053			



Contractor 	Consultant  Hassan 10/12/2022
---	---

California Bearing Ratio TEST

Testing Date :	10-12-2022	Code	ZONE	520+500	522+000
Location :	kp:521+500	CA-EMB-25	Material	fill material layer	
Company Name	cairo company		quantity	5000m3	

- : Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9810
Wet WT. (gm)	4910
Wet Density (g/cm ³)	2.294
Dry Density (g/cm ³)	2.163
Proctor Density (g/cm ³)	2.170
Compaction %	99.9

Mositure Ratio After Compacted Mold	
Tare No.	17
Tare WT. (gm)	59.5
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	145
3398	5.0
Dry WT. (gm)	85.5
Moisture Content %	5.8

Swelling	
Mold No.	4
Date	10-12-2022
Initial Height (mm)	6.00
Final Height (mm)	6.60
Difference	1
Sample Height (mm)	11.90
Swelling Ratio %	5%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.02	0.06	0.11	0.15	0.20	0.26	0.28	0.35	0.45
Load (KN)	0.6	1.8	3.3	4.5	6.0	7.8	8.4	10.5	13.5




Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	4.50	13.4	33.7%	100	98	33.1%
5.00	10.50	20.0	52.4%			51.4%

Lab. Specialist

Name :


Sign :


 ٥٥٥ - ٥٥٤ - ٥٥٣

Lab. Engineer

Name :


Sign :


 Electric Express
 Central Lab Number
 507 Paki - Matruh


Consultant Engineer

Name :



Sign :


 Hassa
 10/12/2022

MATERIAL INSPECTION REQUEST	    
	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		11/12/2022							
Contractor reference	CA-Emb-28									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment						FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill									
	520+770 521+140	520+800 521+300	-10 -7.5									
MAR Approval No							Date					
Supplier Name												
Test Requirement							Specification	Clause				
Reference Photos	Yes attached / No						Other					
Item	Description	Unit	Quantity	Arrival Date	Note							
1	Sieve analysis	m ³	5000	7-12-2022								
2	Classification	m ³	5000	7-12-2022								
3	Proctor & O.m.c	m ³	5000	7-12-2022								
4	L.L & P.L & PI	m ³	5000	7-12-2022								
5	C.B.R	m ³	5000	11-12-2022								
Comments by:						Comments by:						
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.						Test result for estimated quantities of about 5000 m3						
APPROVAL STATUS												
Organisation	Name	Sign	Date	A-AWC-R								
Contractor	Eng / Ahmed mohammed		11/12/2022	A								
QA/QC *	Hassan		11/12/2022	A								
GARB**	Hussien Fouad		11/12/2022	A								
Comments by	Risk quantity approval with Qs											
Employers Representative	Mehmed Ahmed		8-2-23	A								

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Adel		11/12/2022																
Contractor Reference	CA-Emb-26																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	15%	
4	ASTM D 4318	Atterberg limit	19.62%	
5	ASTM D 2974	Moisture content	6.5%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	50%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		11/12/2022	A
Contractor QA/QC *	Hassan		11/12/2022	A
GARB**	Hussien Fouad		11/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتيل	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177		 الهيئة القومية للإنفاق سلطة قناة السويس SUEZ CANAL AUTHORITY
		Opreating Lab AL Nuby Central Lab		
		PARTICLE SIZE DISTRIBUTION OF SOIL		

TESTING DATE:	07/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:524+000	CA-Emb-28	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		22813.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	1215.0	1425.0	1675.0	1758.0	2191.0	1875.0	2352.0		A-1-a
Cumulative Retained (g)	1215.0	2640.0	4315.0	6073.0	8264.0	10139.0	12491.0	PRO	2.15
Cumulative Retained %	5.3	11.6	18.9	26.6	36.2	44.4	54.8	WC	6.50
Cumulative Passing %	94.7	88.4	81.1	73.4	63.8	55.6	45.2	CBR	50.00



B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	109.00	241.00	334.00				
Cumulative Retained %	21.80	48.20	66.80				
Cumulative Passing %	78.20	51.80	33.20				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.7	88.4	81.1	73.4	63.8	55.6	45.2	35.4	23.4	15.0

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	23.25%	19.62%	3.64%

Contractor

Consultant




 	Electric Express Train - HSR	 
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	08/12/2022	Code	ZONE	520+500	522+000
Location:	kp:521+500	CA-Emb-28	Material	fill material layers	
Company Name	cairo company		quantity	5000m3	

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	36	30	24	18	-	-
Tare No.	15	17	7	40	33	73
Tare WT. (gm)	31.40	59.60	43.70	46.4	73.50	34.50
Tare WT. + Wet WT. (gm)	54.20	86.90	71.60	68.90	76.60	37.20
Tare WT. + Dry WT. (gm)	50.40	81.90	66.30	64.40	76.1	36.8
Water WT. (gm)	3.80	5.00	5.30	4.50	0.50	0.45
Dry WT. (gm)	19.00	22.30	22.60	18.00	2.60	2.25
Moisture Content %	20.0%	22.4%	23.5%	25.0%	19.2%	20.0%
Average %					19.6%	



L.L	P.L	P.I
23.25%	19.62%	3.64%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :

Sign :

Name :

Sign :

Name :

Sign :



Handwritten signature and date 11/12/2022.

	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	8-12-2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-26	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.15
Water content %	6.5

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10348.0	10756.0	11020.0	10792	
WT. WET SOIL	4311.0	4719.0	4983.0	4755.0	
Wt. Density	1.981	2.169	2.290	2.185	

Tare No.	10	7	16	15	17	90	11	26		
Tare wt.	43.7	42.8	33.1	31.4	59.6	62.4	46.6	54.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.8	142.6	144.9	144.8	144.3	144.5	142.0	142.3		
Wt. Of water	3.2	7.4	5.1	5.2	5.7	5.5	8.0	7.7		
Wt. Of dry soil	123.0	267.8	111.8	113.4	84.7	82.1	95.4	87.4		
Water content %	2.6%	2.8%	4.6%	4.6%	6.7%	6.7%	8.4%	8.8%		
AV. Water content %	2.7%		4.6%		6.7%		8.6%			
Dry Density	1.929		2.074		2.146		2.012			



Contractor

مكتب استشارات وهندسة
107405
س ت ٥٤٢ - ٥٤٥



Consultant

11/12/2022 Hasea
مكتب استشارات وهندسة

California Bearing Ratio TEST

Testing Date :	11-12-2022	Code	ZONE	520+500	522+000
Location :	kp:521+000	CA-Emb-26	Material	fill material layers	
Company Name	cairo company		quantity	5000m3	

Test Results


Compaction % for Mold	
Mold No.	1
Mold Vol. (cm ³)	2158
Mold WT. (gm)	4890
Mold WT. + Wet WT. (gm)	9820
Wet WT. (gm)	4930
Wet Density (g/cm ³)	2.285
Dry Density (g/cm ³)	2.147
Proctor Density (g/cm ³)	2.150
Compaction %	99.9

Moisture Ratio After Compacted Mold	
Tare No.	16
Tare WT. (gm)	33.9
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	143
3398	7.0
Dry WT. (gm)	109.1
Moisture Content %	6.4

Swelling	
Mold No.	1
Date	11-12-2022
Initial Height (mm)	8.00
Final Height (mm)	8.25
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	2%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.02	0.04	0.08	0.12	0.17	0.22	0.28	0.34	0.45
Load (KN)	0.6	1.2	2.4	3.6	5.1	6.6	8.4	10.2	13.5



Calculations :-

Penetration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	3.60	13.4	27.0%	100	98	26.5%
5.00	10.20	20.0	50.9%			50.0%

Lab. Specialist

Name :
Signature :


Lab. Engineer

Name :
Signature :
Electric Express Train
Central Lab Number 4
Sec-7 Fuka - Matruh

Consultant Engineer

Name : H. Kassa
Signature :
2022


MATERIAL INSPECTION REQUEST	    				
	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		12/12/2022																	
Contractor reference	CA-Emb-27																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Under embankment					FILL MATERIAL RESULTS	
Location to be Used	From	To	Fill				
	521+300	521+320	-7.5				
	521+320	521+440	-6.5				
MAR Approval No	521+560	521+635	-6.5	Date			
Supplier Name							
Test Requirement		Specification	Clause				
Reference Photos	Yes attached / No	Other					
Item	Description	Unit	Quantity	Arrival Date	Note		
1	Sieve analysis	m ³	5000	8-12-2022			
2	Classification	m ³	5000	8-12-2022			
3	Proctor & O.m.c	m ³	5000	8-12-2022			
4	L.L & P.L & PI	m ³	5000	8-12-2022			
5	C.B.R	m ³	5000	12-12-2022			

Comments by:	Comments by:
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.	Test result for estimated quantities of about 5000 m3

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		12/12/2022	A
QA/QC *	Hassan		12/12/2022	A
GARB**	Hussien Fouad		12/12/2022	A
Comments by	Rabab Gabaly approved with Qs			
Employers Representative	Mohamed Ahmed		8-2-28	Avc

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST					

Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Adel		12/12/2022																
Contractor Reference	CA-Emb-27																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.8%	
4	ASTM D 4318	Atterberg limit	20.61%	
5	ASTM D 2974	Moisture content	6%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	48.5%	
Comments by:			Comments by:	
			All test under Responsibility Third party.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		12/12/2022	
Contractor QA/QC *	Hassan		12/12/2022	
GARB**	Hussien Fouad		12/12/2022	
Employers Representative	Mohamed Ahmed		13-1-25	B

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للإستشارات المواصلات والنقل (4981)
		Opreating Lab		
		AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	08/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+560	CA-Emb-27	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		14527.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	872.0	983.0	1210.0	1213.0	1423.0	1323.0	1612.0		A-1-a	
Cumulative Retained (g)	872.0	1855.0	3065.0	4278.0	5701.0	7024.0	8636.0		PRO	2.17
Cumulative Retained %	6.0	12.8	21.1	29.4	39.2	48.4	59.4		WC	6.00
Cumulative Passing %	94.0	87.2	78.9	70.6	60.8	51.6	40.6		CBR	48.50


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	80.10	192.00	317.00					
Cumulative Retained %	16.02	38.40	63.40					
Cumulative Passing %	83.98	61.60	36.60					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.0	87.2	78.9	70.6	60.8	51.6	40.6	34.1	25.0	14.8

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	24.89%	20.61%	4.29%

Contractor

Consultant



12/12/2022 Hassan



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فكري	 SYSTRA	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSА MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للإعانة الميناء والخطوط (CAE)

PROCTOR TEST


TESTING DATE:	08/12/2022	Code	ZONE	520+500	522+000
LOCATION	Kp:521+560	CA-Emb-27	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.17
Water content %	6

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10652.0	10987.0	11060.0	10985	
WT. WET SOIL	4615.0	4950.0	5023.0	4948.0	
Wt. Density	2.121	2.275	2.308	2.274	

Tare No.	26	7	8	21	4	21	33	18		
Tare wt.	54.9	42.8	46.8	55.2	59.7	55.2	73.6	77.7		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.3	142.1	145.0	145.2	144.2	143.8	143.6	144.1		
Wt. Of water	3.7	7.9	5.0	4.8	5.8	6.2	6.4	5.9		
Wt. Of dry soil	123.0	267.8	98.2	90.0	84.5	88.6	70.0	66.4		
Water content %	3.0%	2.9%	5.1%	5.3%	6.9%	7.0%	9.1%	8.9%		
AV. Water content %	3.0%		5.2%		6.9%		9.0%			
Dry Density	2.060		2.162		2.159		2.086			



Contractor

Consultant



Hassan




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA	Electric Express Train - HSR	 وزارة النقل المركز القومي للبحوث (CART)
--	---	-------------------------------------	--

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	09/12/2022	Code	FROM STA:	520+500	522+000
Location:	kp: 521+560		Material:	fill material layer	
Company Name	cairo company	CA-Emb-27	Layer Thickness :	5000m3	

Testing Results :-

Test	Liquidity Limit				Plastic Limit	
No. of Ticks	37	29	20	17	-	-
Tare No.	17	90	20	26	22	11
Tare WT. (gm)	59.90	62.90	60.10	54.9	54.10	46.60
Tare WT. + Wet WT. (gm)	87.40	94.90	93.00	89.60	56.20	48.20
Tare WT. + Dry WT. (gm)	82.30	88.70	86.30	82.30	55.9	47.9
Water WT. (gm)	5.10	6.20	6.70	7.30	0.35	0.28
Dry WT. (gm)	22.40	25.80	26.20	27.40	1.75	1.32
Moisture Content %	22.8%	24.0%	25.6%	26.6%	20.0%	21.2%
Average %					20.6%	



L.L	P.L	P.I
24.89%	20.61%	4.29%

Lab. Specialist	Lab. Engineer	Consultant Engineer
Name :	Name :	Name :
Sign :	Sign :	Sign :





Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	12/12/2022	Code	ZONE	520+500	522+000
Location :	kpi:521+560	CA-Emb-27	Material	fill material layers	
Company Name	cairo company		quantity	5000m3	

Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	5075
Mold WT. + Wet WT. (gm)	9950
Wet WT. (gm)	4875
Wet Density (g/cm ³)	2.297
Dry Density (g/cm ³)	2.168
Proctor Density (g/cm ³)	2.170
Compaction %	99.9

Moisture Ratio After Compacted Mold	
Tare No.	8
Tare WT. (gm)	46.88
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	144.2
Water WT. (gm)	5.8
Dry WT. (gm)	97.3
Moisture Content %	6.0

Swelling	
Mold No.	6
Date	٢٠٢٢/١٢/١٢
Initial Height (mm)	4.00
Final Height (mm)	4.35
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	3%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.05	0.09	0.14	0.18	0.21	0.24	0.29	0.33	0.42
Load (KN)	1.5	2.7	4.2	5.4	6.3	7.2	8.7	9.9	12.6



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	5.40	13.4	40.4%	100	98	39.7%
5.00	9.90	20.0	49.4%			48.5%

Lab. Specialist

Name :

Sign :

مختبر مطبوعه والاستشارات
١٠٩٧٤٠٠
٥٥٥ - ٥٤٢ - ٥٤٦

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec-7 Foka - Matrouh

Consultant Engineer

Name :

Sign :

مختبر مطبوعه والاستشارات
١٠٩٧٤٠٠
٥٥٥ - ٥٤٢ - ٥٤٦

MATERIAL INSPECTION REQUEST						

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		13 - 12 - 2022							
Contractor reference	CA-Emb-28									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+635 520+880	521+700 520+995	-6.5 -10.5			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No		Other			
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	11-12-2022		
2	Classification	m ³	5000	11-12-2022		
3	Proctor & O.m.c	m ³	5000	11-12-2022		
4	L.L & P.L & PI	m ³	5000	11-12-2022		
5	C.B.R	m ³	5000	13-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		13/12/2022	A		
QA/QC *	Hassan		13/12/2022	A		
GARB**	Hussien Fouad		13/12/2022	A		
Comments by	Bill Quantity Approved with QS					
Employers Representative	Mohamed Ahmed		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	13-12-2022	
Contractor Reference	CA-EMB-28			
Received by ER	<i>[Signature]</i>	MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment - Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.2%	
4	ASTM D 4318	Atterberg limit	21.07%	
5	ASTM D 2974	Moisture content	7.5%	
6	ASTM D 1557	Modified proctor	2.13	
7	ASTM D 1883	CBR	45.7%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed Mohamed	Ahmed Mohamed	13/12/2022	A
Contractor QA/QC *	Hassan	<i>[Signature]</i>	13/12/2022	<i>[Signature]</i>
GARB**	Hussien Fouad	<i>[Signature]</i>	13/12/2022	A
Employers Representative	Mohd Ahs	<i>[Signature]</i>	15-1-25	P

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فؤاد	 SVSRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإعانة الهيئة العامة للإعانة
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000		Material	fill material layers	
NAME COMPANY	cairo company	CA-Emb-28	quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		19765.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1325.0	1672.0	1991.0	2179.0	1874.0	1984.0	1987.0		A-1-a	
Cumulative Retained (g)	1325.0	2897.0	4888.0	7067.0	8941.0	10925.0	12912.0		PRO	2.13
Cumulative Retained %	6.7	14.7	24.7	35.8	45.2	55.3	65.3		WC	7.50
Cumulative Passing %	93.3	85.3	75.3	64.2	54.8	44.7	34.7		CBR	45.70



B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	92.40	213.60	338.70					
Cumulative Retained %	18.48	42.72	67.74					
Cumulative Passing %	81.52	57.28	32.26					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	93.3	85.3	75.3	64.2	54.8	44.7	34.7	28.3	19.9	11.2

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	24.52%	21.07%	3.45%

Contractor

Consultant



Hasan
13/12/2022




 	Electric Express Train - HSR	 
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

TESTING DATE:	12/12/2022	Code	ZONE	520+500	522+000
LOCATION	كبر: 521+000	CA-EM6-28	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	


Testing Results :-


Test	Liquid Limit				Plastic Limit	
No. of Ticks	38	30	22	18	-	-
Tare No.	18	45	32	21	15	40
Tare WT. (gm)	77.70	41.50	74.40	55.2	31.90	46.40
Tare WT. + Wet WT. (gm)	98.30	70.10	94.50	75.30	34.50	49.20
Tare WT. + Dry WT. (gm)	94.50	64.60	90.50	71.20	34.1	48.7
Water WT. (gm)	3.80	5.50	4.00	4.10	0.45	0.49
Dry WT. (gm)	16.80	23.10	16.10	16.00	2.15	2.31
Moisture Content %	22.6%	23.8%	24.8%	25.6%	20.9%	21.2%
Average %					21.1%	



L.L	P.L	P.I
24.52%	21.07%	3.45%

Lab. Specialist	Lab. Engineer	Consultant Engineer
Name :	Name :	Name : Hassan
Sign :	Sign :	Sign : 13/12/2022







 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SYSTEM D SHAKE	Electric Express Train - HSR		 الهيئة العامة للإعانة الميناء والموانئ والبحر (CAAB)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
		From Station 504+000 To Station 568+177		


PROCTOR TEST


TESTING DATE:	12/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-EMB-28	Material	fill material layers	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0	MAX Dry Density	2.13
Mold Volume:	2176.0	Water content %	7.5

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10587.0	10897.0	11032.0	10785	
WT. WET SOIL	4550.0	4860.0	4995.0	4748.0	
Wt. Density	2.091	2.233	2.295	2.182	

Tare No.	40	16	22	20	8	15	26	4		
Tare wt.	46.4	33.9	54.1	60.9	46.8	31.9	55	60.1		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	144.9	139.4	144.2	144.7	142.3	141.2	141.2	141.8		
Wt. Of water	5.1	10.6	5.8	5.3	7.7	8.8	8.8	8.2		
Wt. Of dry soil	123.0	267.8	90.1	83.8	95.5	109.3	86.2	81.7		
Water content %	4.1%	4.0%	6.4%	6.3%	8.1%	8.1%	10.2%	10.0%		
AV. Water content %	4.1%		6.4%		8.1%		10.1%			
Dry Density	2.010		2.099		2.124		1.981			



Contractor 		Consultant  
---	---	--

California Bearing Ratio TEST

Testing Date :	13/12/2022	Code	FROM STA	520+500	522+000
Location :	kp:521+000	CA-Emb-28	Material	fill material layer	
Company Name	cairo company		quantity	5000m3	

Test Results


Compaction % for Mold	
Mold No.	3
Mold Vol. (cm ³)	2168
Mold WT. (gm)	5089
Mold WT. + Wet WT. (gm)	10030
Wet WT. (gm)	4941
Wet Density (g/cm ³)	2.279
Dry Density (g/cm ³)	2.123
Proctor Density (g/cm ³)	2.130
Compaction %	99.7

Moisture Ratio After Compacted Mold	
Tare No.	15
Tare WT. (gm)	31.9
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	141.9
Water WT. (gm)	8.1
Dry WT. (gm)	110.0
Moisture Content %	7.4

Swelling	
Mold No.	3
Date	13/12/2022
Initial Height (mm)	2.00
Final Height (mm)	2.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.06	0.11	0.14	0.20	0.23	0.27	0.31	0.41
Load (KN)	0.9	1.8	3.3	4.2	6.0	6.9	8.1	9.3	12.3



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	98 عند نسبة 98
2.50	4.20	13.4	31.5%	100	98	30.9%
5.00	9.30	20.0	46.4%			45.7%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :


Electric Express Train
 Central Lab Number 4
 Sec-7 Fuka - Matrouh





 المكتب الاستشاري الهندسي

 ا.د. خالد فكري

MATERIAL INSPECTION REQUEST	    
	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		15-12-2022							
Contractor reference	CA-Emb-29									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment		FILL MATERIAL RESULTS			
Location to be Used	From	To	Fill			
	520+995	521+000	-10.5			
	521+000	521+080	-8			
MAR Approval No	521+440	521+550	-6.5	Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	11-12-2022		
2	Classification	m ³	5000	11-12-2022		
3	Proctor & O.m.c	m ³	5000	11-12-2022		
4	L.L & P.L & PI	m ³	5000	11-12-2022		
5	C.B.R	m ³	5000	15-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		15/12/2022	A		
QA/QC *	Hassan		15/12/2022	A		
GARB**	Hussien Fomard		15/12/2022	A		
Comments by	fill quantity approved with Qs					
Employers Representative	Mohamed A hnd		8-2-23	Avc		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		15-12-2022	
Contractor Reference	CA-Emb-29			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	low embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	9.9%	
4	ASTM D 4318	Atterberg limit	19.99%	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.12	
7	ASTM D 1883	CBR	45.6%	
Comments by:		Comments by:		
		All test under Responsibility Third party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		15/12/2022	A
Contractor QA/QC *	Klassen		15/12/2022	A
GARB**	Hussien Fouad		15/12/2022	A
Employers Representative	Mohd Ans		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 لحار كهربائي سريع Electric Express Train SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإنتاج للمواصلات والاقتصاد (SAGI)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARSA MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-29	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT (g)		27072.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	2785.0	2849.0	2101.0	2260.0	2230.0	2455.0	2562.0		A-1-a	
Cumulative Retained (g)	2785.0	5634.0	7735.0	9995.0	12225.0	14680.0	17242.0		PRO	2.12
Cumulative Retained %	10.3	20.8	28.6	36.9	45.2	54.2	63.7		WC	7.00
Cumulative Passing %	89.7	79.2	71.4	63.1	54.8	45.8	36.3		CBR	45.60

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	120.60	254.00	364.00					
Cumulative Retained %	24.12	50.80	72.80					
Cumulative Passing %	75.88	49.20	27.20					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	89.7	79.2	71.4	63.1	54.8	45.8	36.3	27.6	17.9	9.9

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	23.88%	19.99%	3.89%

Contractor

Consultant

مستشار
10-7-2022
525-549-29



15/12/2022

المكتب
الاستشاري الهندسي
أ.د. خالد قنديل


 	Electric Express Train - HSR	 
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	12/12/2022	Code	ZONE	520+500	522+000
Location:	km:521+000	CA-Emb-29	Material	fill material layer	
Company Name	cairo-company		quantity	5000 m3	

Testing Results :-

Test	Liquidity Limit				Plastic Limit	
No. of Ticks	36	28	21	15	-	-
Tare No.	26	8	4	49	25	10
Tare WT. (gm)	55.00	46.80	60.10	33.9	75.80	43.70
Tare WT. + Wet WT. (gm)	78.50	69.50	86.50	60.20	79.20	47.20
Tare WT. + Dry WT. (gm)	74.20	65.20	81.30	54.90	78.7	46.6
Water WT. (gm)	4.30	4.30	5.20	5.30	0.55	0.60
Dry WT. (gm)	19.20	18.40	21.20	21.00	2.85	2.90
Moisture Content %	22.4%	23.4%	24.5%	25.2%	19.3%	20.7%
Average %					20.0%	



L.L	P.L	P.I
23.88%	19.99%	3.89%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------


Name :

Sign :

القاهرة لطرق والأنفاق
ب س ت ١٩٧٧.٥
٥٥٥ - ٥٩٢ - ٥٩٦

Name :

Sign :



Name :

Sign :

15/12/2022




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 القطار السريع Electric Express Train SVSTCA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإعانة الميناء والخطوط البحرية (CAPSULT)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177				


PROCTOR TEST

TESTING DATE:	12/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Em6-28	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6037.0	MAX Dry Density	2.12
Mold Volume:	2176.0	Water content %	7

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10452.0	10752.0	10975.0	10685	
WT. WET SOIL	4415.0	4715.0	4938.0	4648.0	
Wt. Density	2.029	2.167	2.269	2.136	

Tare No.	32	21	7	73	19	45	10	25		
Tare wt.	74.4	55.2	42.8	42.9	44.4	41.5	43.7	75.8		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	145.2	139.8	144.6	144.6	142.9	142.8	141.2	143.8		
Wt. Of water	4.8	10.2	5.4	5.4	7.1	7.2	8.8	6.2		
Wt. Of dry soil	123.0	267.8	101.8	101.7	98.5	101.3	97.5	68.0		
Water content %	3.9%	3.8%	5.3%	5.3%	7.2%	7.1%	9.0%	9.1%		
AV. Water content %	3.9%		5.3%		7.2%		9.1%			
Dry Density	1.954		2.058		2.118		1.958			



Contractor

المشروع لخطوط القطار السريع
محطة فوكا - مرسى مطروح
15/12/2022



Consultant

Hassan
15/12/2022



California Bearing Ratio TEST

Testing Date :	15/12/2022	Code	ZONE	520+500	522+000
Location :	kp:521+000	CA-Emb-29	Material	fill material layer	
Company Name	cairo company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	5076
Mold WT. + Wet WT. (gm)	9850
Wet WT. (gm)	4804
Wet Density (g/cm ³)	2.264
Dry Density (g/cm ³)	2.117
Proctor Density (g/cm ³)	2.120
Compaction %	99.8

Moisture Ratio After Compacted Mold	
Tare No.	20
Tare WT. (gm)	60.9
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	144.2
Water WT. (gm)	5.8
Dry WT. (gm)	83.3
Moisture Content %	7.0

Swelling	
Mold No.	6
Date	٢٠٢٢/١٢/١٥
Initial Height (mm)	4.00
Final Height (mm)	4.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.02	0.07	0.10	0.15	0.19	0.22	0.26	0.31	0.40
Load (KN)	0.6	2.1	3.0	4.5	5.7	6.6	7.8	9.3	12.0



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	98 عند نسبة %
2.50	4.50	13.4	33.7%	100	98	33.1%
5.00	9.30	20.0	46.4%			45.6%

Lab. Specialist

Name :

Sign :

استشارة نظرية والإستشارات
 س.ت ١٠٦٧٠٥
 ب.ت ١٠٦٧٠٥ - ١٠٦٧٠٥

Lab. Engineer

Name :

Sign :


 Electric Express Train
 Central Lab Number 4
 Sec-7 Fuka - Matrouh

Consultant Engineer

Name :

Sign :

Hassan
 15/12/2022

 الاستشارة
 الإستشاري الهندسي
 أ.د. خالد خليل

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K															
Issued by Contractor	Name	Sign	Date	Time															
	Eng/ Abdelrahman Adel		1-11-2022																
Contractor reference	C A-Emb-3																		
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment					FILL MATERIAL RESULTS	
Location to be Used	From	To	Fill				
	521+010 520+620	521+080 520+690	-10.5 -10.5				
MAR Approval No				Date			
Supplier Name							
Test Requirement				Specification	Clause		
Reference Photos	Yes attached / No			Other			
Item	Description	Unit	Quantity	Arrival Date	Note		
1	Sieve analysis	m ³	5000	28-10-2022			
2	Classification	m ³	5000	28-10-2022			
3	Proctor & O.m.c	m ³	5000	28-10-2022			
4	L.L & P.L & PI	m ³	5000	28-10-2022			
5	C.B.R	m ³	5000	1-11-2022			
Comments by:			Comments by:				
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3				
APPROVAL STATUS							
Organisation	Name	Sign	Date	A-AWC-R			
Contractor	Eng / Ahmed mohammed		1/11/2022	A			
QA/QC *	Ahmed Abo Zaid		1/11/2022	A			
GARB**	Hussein Fouad		1/11/2022	A			
Comments by	Rel quantity approved with QS						
Employers Representative	Mohamed Ahs		8-2-23				

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company							
Electric express train	Cairo for Roads and construction Company			k.k							
Issued by Contractor	Name	Sign	Date	Time							
	ENG/ Abdelrahman Adel		1-11-2022								
Contractor Reference	CA-Emb-3										
Received by ER			MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.1%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	42.6%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		11/11/2022	A
Contractor QA/QC *	Hassan		11/11/2022	A
GARB**	Hussein Fouad		11/11/2022	A
Employers Representative	Mohamed Ahmed		15-1-2025	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARSА MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للإسكان القوية للإسكان (CAEGL)
		Operating Lab	AL Nuby Central Lab	

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	27-10-2022	Code	ZONE	520+500	522+000
LOCATION	kp.521+000	CA-Emb-3	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test



A-gradation of bulk materials				SAMPLE WEIGHT [g]		23286.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	2968.0	2842.0	2513.0	1516.0	1654.0	1369.0		A-1-a
Cumulative Retained (g)	0.0	2968.0	5810.0	8323.0	9839.0	11493.0	12862.0	PRO	2.16
Cumulative Retained %	0.0	12.7	25.0	35.7	42.3	49.4	55.2	WC	6.80
Cumulative Passing %	100.0	87.3	75.0	64.3	57.7	50.6	44.8	CBR	42.60

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	122.40	258.20	353.50					
Cumulative Retained %	24.48	51.64	70.70					
Cumulative Passing %	75.52	48.36	29.30					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	87.3	75.0	64.3	57.7	50.6	44.8	33.8	21.6	13.1

ATTEBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor



Consultant



	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	2022-10-27	Code	ZONE	520+500	522+000
LOCATION	kpt: 521+000	CA-521-3	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6070.0
Mold Volume:	2113.0

MAX Dry Density	2.16
Water content %	6.8


trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10335.0	10741.0	10954.0	10741	
WT. WET SOIL	4265.0	4671.0	4884.0	4671.0	
Wt. Density	2.018	2.211	2.311	2.211	

Tare No.	10	45	7	73	18	90	11	21		
Tare wt.	43.7	41.5	42.8	42.9	77.8	62.5	46.1	55.2		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.5	147.8	144.8	145.1	145.2	144.2	141.2	142.2		
Wt. Of water	2.5	2.2	5.2	4.9	4.8	5.8	8.8	7.8		
Wt. Of dry soil	103.8	106.3	102.0	102.2	67.4	81.7	95.1	87.0		
Water content %	2.4%	2.1%	5.1%	4.8%	7.1%	7.1%	9.3%	9.0%		
AV. Water content %	2.2%		4.9%		7.1%		9.1%			
Dry Density	1.974		2.106		2.158		2.026			




Contractor





Consultant



California Bearing Ratio TEST

Testing Date :	1-11-2022	Code	zone	520+500	522+000
Location :	Kp:521+000	CA-Emb-3	Material	fill material layer	
Company Name	caro company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9838
Wet WT. (gm)	4938
Wet Density (g/cm ³)	2.307
Dry Density (g/cm ³)	2.160
Proctor Density (g/cm ³)	2.160
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	10
Tare WT. (gm)	43.7
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	143.2
Water WT. (gm)	6.8
Dry WT. (gm)	99.5
Moisture Content %	6.8

Swelling	
Mold No.	4
Date	1-11-2022
Initial Height (mm)	1.00
Final Height (mm)	1.00
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.04	0.03	0.12	0.14	0.17	0.22	0.26	0.39	0.32
Load (KN)	1.2	2.4	3.6	4.2	5.1	6.6	7.8	8.7	9.6



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	4.20	13.4	31.5%	100	98	30.8%
5.00	8.70	20.0	43.4%			42.6%

Lab. Specialist

Name :

Sign :

المكتب الاستشاري الهندسي
أ. د. خالد فنديل

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec 7 Peka - Matruh

Consultant Engineer

Name :

Sign :

المكتب الاستشاري الهندسي
أ. د. خالد فنديل

Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K					
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		15-12-2022							
Contractor reference	CA-EMB-30									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+550	521+560	-6.5		
	521+700	521+800	-6.5		
	520+800	520+880	-10.5		
	521+800	521+810	-6.5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No		Other		
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	11-12-2022	
2	Classification	m ³	5000	11-12-2022	
3	Proctor & O.m.c	m ³	5000	11-12-2022	
4	L.L & P.L & PI	m ³	5000	11-12-2022	
5	C.B.R	m ³	5000	15-12-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		15/12/2022	A	
QA/QC *	Hassan		15/12/2022	A	
GARB**	Hussien Fouad		15/12/2022	A	
Comments by	Rel quantity appx with es				
Employers Representative	Mohamed Ali		8-2-25		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Ahmed Mohamed		15-12-2022	
Contractor Reference	CA-Emb-30			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.5%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	48.5%	
Comments by:		Comments by:		
		All test under Responsibility Third Party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed mohamed		15/11/2022	A
Contractor QA/QC *	Hassan		15/11/2022	A
GARB**	Hussein Fouad		15/11/2022	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	 الهيئة القومية للإنتاج القوي والطارق (E.R.T.C.)
Opreating Lab		AL Nuby Central Lab	

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11/12/2022	Code	ZONE	520+500	522+000
LOCATION	Kp: 521+000	CA-Emb-30	Material	fill material layar	
NAME COMPANY	cairo company		quantity	5000m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		17299.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1252.0	1325.0	1452.0	1978.0	1752.0	1452.0	2495.0		A-1-a	
Cumulative Retained (g)	1252.0	2577.0	4029.0	6007.0	7759.0	9211.0	11706.0		PRO	2.16
Cumulative Retained %	7.2	14.9	23.3	34.7	44.9	53.2	67.7		WC	6.50
Cumulative Passing %	92.8	85.1	76.7	65.3	55.1	46.8	32.3		CBR	48.50



B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	99.90	220.00	314.00					
Cumulative Retained %	19.98	44.00	62.80					
Cumulative Passing %	80.02	56.00	37.20					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	92.8	85.1	76.7	65.3	55.1	46.8	32.3	25.9	18.1	12.0

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Handwritten signature and date: 15/12/2022



Electric Express Train - HSR
 From El Ain El Sokhna City To El Alamein - MATROUH
 Section - 7 From FOKA TO MARSA MATROUH
 From Station 504+000 To Station 568+177



PROCTOR TEST


TESTING DATE:	12-12-2022	Code	ZONE	520+500	522+000
LOCATION	Kp:521+000	CA-EMB-30	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000m3	

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.16
Water content %	6.5


trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10562.0	10899.0	11058.0	10912	
WT. WET SOIL	4525.0	4862.0	5021.0	4875.0	
Wt. Density	2.080	2.234	2.307	2.240	

Tare No.	11	16	22	26	7	17	90	4		
Tare wt.	46.9	33.9	54.1	54.9	42.8	59.5	62.9	60.1		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.2	142.1	145.4	145.4	143.1	144.1	142.9	142.7		
Wt. Of water	3.8	7.9	4.6	4.6	6.9	5.9	7.1	7.3		
Wt. Of dry soil	123.0	267.8	91.3	90.5	100.3	84.6	80.0	82.6		
Water content %	3.1%	2.9%	5.0%	5.1%	6.9%	7.0%	8.9%	8.8%		
AV. Water content %	3.0%		5.1%		6.9%		8.9%			
Dry Density	2.019		2.127		2.158		2.058			



Contractor

مشارقة بنسطة والإستشارات
 ب. س. ت. ١٠٩٦٠٥
 ٥٥٥ - ٥٥٨ - ١٦٦



Consultant

15/12/2022 Hassan

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد فاضل	 SVS/TA	Electric Express Train - HSR	 الهيئة العامة للنقل Ministry of Transport
---	---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	15/12/2022	Code	ZONE	520+500	522+000	
Location :	kp:521+000	CA-Em6-3c	Material	fill material layer		
Company Name	cairo company		quantity	5000m3		

Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9820
Wet WT. (gm)	4920
Wet Density (g/cm ³)	2.299
Dry Density (g/cm ³)	2.160
Proctor Density (g/cm ³)	2.160
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	19
Tare WT. (gm)	44.4
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	143.6
Water WT. (gm)	6.4
Dry WT. (gm)	99.2
Moisture Content %	6.5

Swelling	
Mold No.	4
Date	٢٠٢٢/١٢/١٥
Initial Height (mm)	7.00
Final Height (mm)	7.30
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	3%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.04	0.09	0.14	0.17	0.24	0.27	0.31	0.33	0.44
Load (KN)	1.2	2.7	4.2	5.1	7.2	8.1	9.3	9.9	13.2



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	98 عند نسبة %
2.50	5.10	13.4	38.2%	100	98	37.4%
5.00	9.90	20.0	49.4%			48.5%

Lab. Specialist

Name :

Sign :

المشرفة لطرق والإنشاءات
ب. س. ١٠٦٧٠٥
٥٥٥ - ٥٩٣ - ٥٢٦

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec-7 Fuka - Matruh

Consultant Engineer

Name :

Sign :

15/12/2022
Hassan

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		2-11-2022							
Contractor reference	CA-Emb-4									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From 521+320	To 521+500	Fill -8.5		
MAR Approval No		Date			
Supplier Name					
Test Requirement		Specification	Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	29-10-2022	
2	Classification	m ³	5000	29-10-2022	
3	Proctor & O.m.c	m ³	5000	29-10-2022	
4	L.L & P.L & PI	m ³	5000	29-10-2022	
5	C.B.R	m ³	5000	2-11-2022	
Comments by:		Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.		Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed Mohammed		21/11/2022	A	
QA/QC *	Ahmed Abozaid		21/11/2022	A	
GARB**	Hussien Fouad		21/11/2022	A	
Comments by	fill quantity approved with @s				
Employers Representative	Mohamed Ahmed		8-2-23		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Ade		2-11-2022																	
Contractor Reference	CA-Emb-4																			
Received by ER			MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	8.5%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	5.3%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	44.1%	
Comments by:			Comments by:	
			All test under Responsibility Third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman Adel	2/11/2022	A
Contractor QA/QC *	Hassan		2/11/2022	A
GARB**	Hussien Fouad	Hussien Fouad	2/11/2022	A
Employers Representative	Mohamed Aly		13-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للإحصاء مصر
		Operating Lab	AL Nuby Central Lab	

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	29/10/2022	Code	ZONE	520+500	522+000
LOCATION	521+000	CA-EMB-4	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		29893.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	3532.0	3550.0	3965.0	3765.0	2606.0	3012.0	2968.0		A-1-a
Cumulative Retained (g)	3532.0	7082.0	11047.0	14812.0	17418.0	20430.0	23398.0		PRO
Cumulative Retained %	11.8	23.7	37.0	49.6	58.3	68.3	78.3		WC
Cumulative Passing %	88.2	76.3	63.0	50.4	41.7	31.7	21.7		CBR


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	39.90	225.30	305.30					
Cumulative Retained %	7.98	45.06	61.06					
Cumulative Passing %	92.02	54.94	38.94					


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	88.2	76.3	63.0	50.4	41.7	31.7	21.7	20.0	11.9	8.5

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor

Consultant





PROCTOR TEST


TESTING DATE:	2022/10/29	Code	ZONE	520+500	522+000
LOCATION	lp: 521+000	CA-Emb-4	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6190.0
Mold Volume;	2169.0

MAX Dry Density	2.18
Water content %	5.3

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10656.0	10986.0	11165.0	11013	
WT. WET SOIL	4466.0	4796.0	4975.0	4823.0	
Wt. Density	2.059	2.211	2.294	2.224	A-I-a

Tare No.	22	20	18	34	11	40	73	25		
Tare wt.	54.1	60.9	77.7	70.2	46.1	46.4	42.9	75.8		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	148.0	147.5	147.2	146.8	144.2	145.1	141.5	143.5		
Wt. Of water	2.0	2.5	2.8	3.2	5.8	4.9	8.5	6.5		
Wt. Of dry soil	93.9	86.6	69.5	76.6	98.1	98.7	98.6	67.7		
Water content %	2.1%	2.9%	4.0%	4.2%	5.9%	5.0%	8.6%	9.6%		
AV.Water content %	2.5%		4.1%		5.4%		9.1%			
Dry Density	2.009		2.124		2.175		2.038			



Contractor

Consultant

California Bearing Ratio TEST

Testing Date :	2-11-2022	Code	ZONE	520+500	522+000
Location :	kp: 52f+000	CA-EMB-U	Material	fill material layer	
Company Name	cairo company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	1
Mold Vol. (cm ³)	2158
Mold WT. (gm)	4890
Mold WT. + Wet WT. (gm)	9840
Wet WT. (gm)	4950
Wet Density (g/cm ³)	2.294
Dry Density (g/cm ³)	2.179
Proctor Density (g/cm ³)	2.180
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	60.1
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	145.5
Water WT. (gm)	4.5
Dry WT. (gm)	85.4
Moisture Content %	5.3

Swelling	
Mold No.	1
Date	2-11-2022
Initial Height (mm)	2.00
Final Height (mm)	2.00
Difference	0
Sample Height (mm)	12.00
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.06	0.10	0.13	0.18	0.23	0.27	0.30	0.37
Load (KN)	0.9	1.8	3.0	3.9	5.4	6.9	8.1	9.0	11.1



Calculations : -

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	3.90	13.4	29.2%	100	98	28.6%
5.00	9.00	20.0	44.9%			44.1%

Lab. Specialist

Name :

Sign :

القاهرة - طريق القاهرة والجيزة
106705
055 - 054 - 054

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec-7 Puka - Matrouh


Consultant Engineer

Name :

Sign :

المكتب
الإستشاري الهندسي
أ.د. خالد فتحي

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel	<i>[Signature]</i>	2/11/2022																	
Contractor reference	CA-Emb-5																			
Received by ER	<i>[Signature]</i>	MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From 520+620 521+680 521+500	To 520+700 521+760 521+650	Fill -10.5 -8.5 -9	<i>[Signature]</i> Date	
MAR Approval No					
Supplier Name					
Test Requirement	Specification		Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	1-11-2022	
2	Classification	m ³	5000	1-11-2022	
3	Proctor & O.m.c	m ³	5000	1-11-2022	
4	L.L & P.L & PI	m ³	5000	1-11-2022	
5	C.B.R	m ³	5000	2-11-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed	<i>[Signature]</i>	2/11/2022	A
QA/QC *	Ahmed Abo Zaid	<i>[Signature]</i>	2/11/2022	A
GARB**	Hussien Souad	<i>[Signature]</i>	2/11/2022	A
Comments by	Lil quantity approved with @s			
Employers Representative	Mohamed Ahmed	<i>[Signature]</i>	8-2-25	Awe

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company							
Electric express train	Cairo for Roads and construction Company			k.k							
Issued by Contractor	Name	Sign	Date	Time							
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	2/11/2022								
Contractor Reference	CA-Emb-5										
Received by ER	<i>Abdelrahman Adel</i>	<i>Abdelrahman Adel</i>	MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.25%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.3%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	44.1%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	ENG/ahmed mohamed	<i>Ahmed mohamed</i>	2/11/2022	A
Contractor QA/QC *	<i>Ahmed Abo Zaid</i>	<i>Ahmed Abo Zaid</i>	2/11/2022	A
GARB**	<i>Hussien Fouad</i>	<i>Hussien Fouad</i>	2/11/2022	A
Employers Representative	<i>Mohamed</i>	<i>Mohamed</i>	15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARSALA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للنقل الهيئة العامة للنقل م.ت.
		Opreating Lab AL Nuby Central Lab		
		PARTICLE SIZE DISTRIBUTION OF SOIL		

TESTING DATE:	29-10-2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+560	CA-Emb-5	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test


A-gradation of bulk materials				SAMPLE WEIGHT [g]		13999.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	1985.0	1430.0	2133.0	985.0	1422.0	1533.0		A-1-a
Cumulative Retained (g)	0.0	1985.0	3415.0	5548.0	6533.0	7955.0	9488.0	PRO	2.15
Cumulative Retained %	0.0	14.2	24.4	39.6	46.7	56.8	67.8	WC	6.30
Cumulative Passing %	100.0	85.8	75.6	60.4	53.3	43.2	32.2	CBR	44.10

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	104.00	240.60	341.00					
Cumulative Retained %	20.80	48.12	68.20					
Cumulative Passing %	79.20	51.88	31.80					



C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.82	75.61	60.37	53.33	43.17	32.22	25.52	16.72	10.25

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor



Consultant





Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA TO MARSA MATROUH
From Station 504+000 To Station 568+177



PROCTOR TEST


TESTING DATE:	2022/10/30	Code	ZONE	520+500	522+000
LOCATION	kp:521+560	C-1-EMB-S	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6190.0
Mold Volume:	2169.0

MAX Dry Density	2.15
Water content %	6.3

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10526.0	11030.0	11140.0	10752	
WT. WET SOIL	4336.0	4840.0	4950.0	4562.0	
Wt. Density	1.999	2.231	2.282	2.103	

Tare No.	16	40	11	15	33	25	35	8		
Tare wt.	33.9	46.4	46.1	31.9	73.6	75.8	73.9	46.8		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.0	146.8	144.6	145.0	145.0	144.6	142.0	143.8		
Wt. Of water	3.0	3.2	5.4	5.0	5.0	5.4	8.0	6.2		
Wt. Of dry soil	113.1	100.4	98.5	113.1	71.4	68.8	68.1	97.0		
Water content %	2.7%	3.2%	5.5%	4.4%	7.0%	7.8%	11.7%	6.4%		
AV. Water content %	2.9%		5.0%		7.4%		9.1%			
Dry Density	1.942		2.126		2.124		1.928			



Contractor

(Handwritten signature and stamp of the contractor)



Consultant

(Handwritten signature and stamp of the consultant)

California Bearing Ratio TEST

Testing Date :	2/11/2022	Code	ZONE	520+500	522+000
Location :	kp:521+560	CA-Em'b-S	Material	fill material layer	
Company Name	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	6075
Mold WT. + Wet WT. (gm)	10982
Wet WT. (gm)	4907
Wet Density (g/cm ³)	2.312
Dry Density (g/cm ³)	2.159
Proctor Density (g/cm ³)	2.160
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	17
Tare WT. (gm)	59.5
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	144
Water WT. (gm)	6.0
Dry WT. (gm)	84.5
Moisture Content %	7.1

Swelling	
Mold No.	6
Date	02/11/2022
Initial Height (mm)	6.00
Final Height (mm)	6.00
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.09	0.13	0.16	0.19	0.22	0.25	0.28	0.30	0.35
Load (KN)	2.7	3.9	4.8	5.7	6.6	7.5	8.4	9.0	10.5



Calculations :-

Penetration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	5.70	13.4	42.7%	100	98	41.9%
5.00	9.00	20.0	44.9%			44.1%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Electric Express Train
 Central Lab Number 4
 Sec-7 Fuks - Matrouh

Consultant/Engineer

Name :

Sign :

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K					
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		6-11-2022							
Contractor reference	CA-Emb-6									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+650	521+680	-9			
	521+140	521+280	-9.5			
	521+000	521+030	-10			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	2-11-2022		
2	Classification	m ³	5000	2-11-2022		
3	Proctor & O.m.c	m ³	5000	2-11-2022		
4	L.L & P.L & PI	m ³	5000	2-11-2022		
5	C.B.R	m ³	5000	6-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		6/11/2022	A		
QA/QC *	Ahmed Abo Zaid		6/11/2022	A		
GARB**	Hussien Fawad		6/11/2022	A		
Comments by	At quantity approved with Qs					
Employers Representative	Mohamed Ali		8-2-22	Auc		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		6-11-2022	
Contractor Reference	CA-Emb-6			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10%	
4	ASTM D 4318	Atterberg limit	16.6 %	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.21	
7	ASTM D 1883	CBR	63.6%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	6/11/2022	A
Contractor QA/QC *	Abdullah SAMY	Abdullah	6/11/2022	A
GARB**	Hussien Fouad	Hussien	6/11/2022	A
Employers Representative	Mohamed Ahmed	Mohamed	15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	21/11/2022	code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-6	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		17500.00	gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	1124.0	2296.0	4534.0	2234.0	1828.0	905.0	870.0		A-1-a
(g)Cumulative Retained	1124.0	3420.0	7954.0	10188.0	12016.0	12921.0	13791.0		2.21
Cumulative Retained %	6.4	19.5	45.5	58.2	68.7	73.8	78.8		7.00
Cumulative Passing %	93.6	80.5	54.5	41.8	31.3	26.2	21.2		64%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
(g)Cumulative Retained	52.00	151.00	263.20				
Cumulative Retained %	10.40	30.20	52.64				
Cumulative Passing %	89.60	69.80	47.36				

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	93.6	80.5	54.5	41.8	31.3	26.2	21.2	19.0	14.8	10.0

ATTERBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	24.6%	16.6%	8%

Contractor

Consultant

مشروع انطار السويق
 القطاع السابع
 محمل المركزي
 (رقم 6)

اتحادية الطرق والإنشاءات
 ١٠٦٧٠٥٠
 ٥٤٥ - ٥٤٦ - ٥٤٧

المكتب
 الاستشاري الهندسي
 د. خالد قنديل


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 Electric Express Train - HSR	 الهيئة القومية للإنفاق للمواصلات والاقتصاد (GASULT)
---	---	--

Plasticity and Liquidity Test -Atterberg Limits

TESTING DATE:	2/11/2022	code	ZONE	520+500	522+000
LOCATION	KP:521+000	CA-Emb-6	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	34	28	22	16	-	-
Tare No.	7	46	30	14	8	6
Tare WT. (gm)	26.98	27.36	25.75	22.81	12.11	11.02
Tare WT. + Wet WT. (gm)	43.05	43.16	47.08	42.25	12.84	11.84
Tare WT. + Dry WT. (gm)	40.21	40.15	42.72	38.02	12.73	11.73
(gm)Water WT.	2.84	3.01	4.36	4.23	0.11	0.11
(gm)Dry WT.	13.23	12.79	16.97	15.21	0.62	0.71
Moisture Content %	21.5%	23.5%	25.7%	27.8%	17.7%	15.5%
Average %					16.6%	



L.L	P.L	P.I
24.6%	16.6%	8.0%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :

Sign :

مشروع الطراز
القطاع السابع
معمل المركزي
(رقم 6)

Name :

Sign :

التقارير نظري والاشيوات
س.ت. ١٠٦٧٠٥
ب.ت. ٥٩٦ - ٥٩٧

Name :

Sign :

المكتب
الاستشاري الهندسي
أ.د. خالد قنديل



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA TO MARSA MATROUH
From Station 504+000 To Station 568+177




PROCTOR TEST

TESTING DATE:	21/11/2022	code	ZONE	520+500	522+000
LOCATION	KP:521+000	CA-EMB-6	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6210.0	MAX Dry Density	2.21
Mold Volume:	2104.9	Water content %	7

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10785.0	11132.0	11208.0	11192	
WT. WET SOIL	4575.0	4922.0	4998.0	4982.0	
Wt. Density	2.173	2.338	2.374	2.367	

Tare No.	12	12	16	16	2	2	14	14		
Tare wt.	26.1	26.1	25.98	25.98	22.82	22.82	22.88	22.88		
Wt. Of wet soil & tare	128.2	128.2	138.6	138.6	172.3	172.3	153.9	153.9		
Wt. Of dry soil & tare	124.8	124.8	132.1	132.1	162.1	162.1	143.6	143.6		
Wt. Of water	3.3	3.3	6.5	6.5	10.2	10.2	10.3	10.3		
Wt. Of dry soil	98.7	98.7	106.1	106.1	139.3	139.3	120.7	120.7		
Water content %	3.4%	3.4%	6.1%	6.1%	7.4%	7.4%	8.5%	8.5%		
AV. Water content %	3.4%		6.1%		7.4%		8.5%			
Dry Density	2.102		2.204		2.212		2.182			



Contractor

Hasrat
 مشروع الخط السريع
 القطاع السابع
 محصل المركزي
 (رقم 6)

المقاومة لنظرق والإنشادات
 س.ت. ١٠٩٧٠٥
 ب.ض. ٥٥٩ - ٥٥٩

Consultant

[Signature]
 المكتب
 القاهرة

California Bearing Ratio TEST

Testing Date :	6/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-6	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

-: Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21564
(gm)Wet WT.	5011
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.160
Proctor Density (g/cm ³)	2.210
Compaction %	98

Mositure Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	25.25
(gm)Tare WT. +Wet WT.	145.9
(gm)Tare WT. +Dry WT.	138.5
(gm)Water WT.	7.4
(gm)Dry WT.	113.3
Moisture Content %	6.5

Swelling	
Mold No.	2
Date	6/11/2022
(mm)Initial Height	5.00
(mm)Final Height	5.00
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Pentration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	124.00	247.00	367.00	597.00	810.00	961.00	1228.00	1310.00	1485.00
(KN)Load	1.2	2.4	3.6	5.9	7.9	9.4	12.0	12.8	14.6



Calculations :-

Pentration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	عدد نسبة 97
2.50	5.85	13.4	43.8%	98	97	43.5%
5.00	12.84	20.0	64.1%			63.6%

Lab. Specialist

Name :

Sign :

مشروع مطار السويح
القطاع السابع
معمل المركزي
(رقم 6)

Lab. Engineer

Name :

Sign :

مختبر الطرق والاسفلتات
1067005
1067005

Consultant Engineer

Name :

Sign :

مختبر الطرق والاسفلتات
1067005
1067005

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		7/11/2022	A
QA/QC *	Ahmed Abo Zeid		7/11/2022	A
GARB**	Hussien Fouad		7/11/2022	A
Comments by	Link quantity approved with @s			
Employers Representative	Mohamed Ahsa		8-2-25	

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	7/11/2022																	
Contractor Reference	CA-Emb-7																			
Received by ER	<i>[Signature]</i>	MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	8.9%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.9 %	
6	ASTM D 1557	Modified proctor	2.2	
7	ASTM D 1883	CBR	66%	
Comments by:			Comments by:	
			All test under Responsibility third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng/ahmed mohamed	<i>Ahmed Mohamed</i>	7/11/2022	A
Contractor QA/QC *	<i>Ahmed Abo Zaid</i>	<i>[Signature]</i>	7/11/2022	A
GARB**	<i>Hussien Fouad</i>	<i>[Signature]</i>	7/11/2022	A
Employers Representative	<i>Mohamed Ahmed</i>	<i>[Signature]</i>	15-1-2025	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	4/11/2022	code	ZONE	520+500	522+000
Location	KP:521+000	Emb-7	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 M3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		18000.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
(g)Mass retained	0.0	1703.0	5200.0	2701.0	1540.0	809.0	1290.0		A-1-a
(g)Cumulative Retained	0.0	1703.0	6903.0	9604.0	11144.0	11953.0	13243.0	PRO	2.20
Cumulative Retained %	0.0	9.5	38.4	53.4	61.9	66.4	73.6	WC	7.90
Cumulative Passing %	100.0	90.5	61.7	46.6	38.1	33.6	26.4	CBR	66.5%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	85.00	250.00	332.00					
Cumulative Retained %	17.00	50.00	66.40					
Cumulative Passing %	83.00	50.00	33.60					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	90.5	61.7	46.6	38.1	33.6	26.4	21.9	13.2	8.9

ATTERBERG LIMTS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	N.P	N.P	N.P

Contractor

Consultant

مشروع مطار السخنة
 القطاع السابع
 معمل المركزي
 (رقم 6)

القاهرة نظري والإستشارات
 ب. ق. ١٠٦٧٠٥ - ١٠٦٧٠٦
 ٢٥٥ - ٢٥٦ - ٢٥٧

المكتب
 القاهرة نظري والإستشارات
 ب. ق. ١٠٦٧٠٥ - ١٠٦٧٠٦
 ٢٥٥ - ٢٥٦ - ٢٥٧



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA TO MARSA MATROUH
From Station 504+000 To Station 568+177




PROCTOR TEST

TESTING DATE:	4/11/2022	code	ZONE	520+500	522+000
Location	KP: 521+000		Material	fill material layer	
NAME COMPANY	cairo company	CA-Emb-7	quantity	5000 M3	

Weight of empty mold :	6428.0	MAX Dry Density	2.20
Mold Volume:	2104.9	Water content %	7.9

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10953.0	11225.0	11429.0	11201	
WT. WET SOIL	4525.0	4797.0	5001.0	4773.0	
Wt. Density	2.150	2.279	2.376	2.268	

Tare No.	12	12	45	45	9	9	5	5		
Tare wt.	26.1	26.1	25.28	25.28	26.98	26.98	26.54	25.54		
Wt. Of wet soil & tare	128.2	128.2	126.2	126.2	131.9	131.9	142.0	142.0		
Wt. Of dry soil & tare	124.8	124.8	121.3	121.3	124.2	124.2	131.6	131.6		
Wt. Of water	3.3	3.3	4.9	4.9	7.7	7.7	10.3	10.3		
Wt. Of dry soil	98.7	98.7	96.0	96.0	97.2	97.2	105.1	106.1		
Water content %	3.4%	3.4%	5.1%	5.1%	7.9%	7.9%	9.8%	9.7%		
AV. Water content %	3.4%		5.1%		7.9%		9.8%			
Dry Density	2.079		2.169		2.202		2.065			



Contractor

مشروع
 القطاع السابع
 محصيل المركب
 (رقم 6)

المشروع لطرق والإسكان
 ب. ق. ١٠٧٠٥
 ٢٤٤ - ٥٤٣ - ٥٤٦

Consultant

المشروع
 القطاع السابع
 محصيل المركب
 (رقم 6)



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	7-11-2022	Code	ZONE	520+500	522+000
Location :	kp:521+000	CA-Emb-7	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 M3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21564
(gm)Wet WT.	5011
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.147
Proctor Density (g/cm ³)	2.200
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	25.25
(gm)Tare WT. +Wet WT.	145.9
(gm)Tare WT. +Dry WT.	137.82
(gm)Water WT.	8.1
(gm)Dry WT.	112.6
Moisture Content %	7.2

Swelling	
Mold No.	2
Date	7-11-2022
(mm)Initial Height	5.00
(mm)Final Height	5.00
Difference	0.0
(mm)Sample Height	11.0
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penteration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	125.00	325.00	489.00	585.00	754.00	1056.00	1244.00	1358.00	1564.00
(KN)Load	1.2	3.2	4.8	5.7	7.4	10.3	12.2	13.3	15.3



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	5.73	13.4	42.9%	98	99	43.6%
5.00	13.31	20.0	66.5%			67.4%

Lab. Specialist

Name :

Sign :

شروع الطريق السريع
القطاع السابع
معمل المركزي
(رقم 6)

Lab. Engineer

Name :

Sign :

المقابلة لظروف الإنشاءات
ب. ش. ١٠٦٧٠٥
٥٤٥ - ٥٤٦ - ٥٤٧


Consultant Engineer

Name :

Sign :


المقابلة لظروف الإنشاءات
ب. ش. ١٠٦٧٠٥
٥٤٥ - ٥٤٦ - ٥٤٧

MATERIAL INSPECTION REQUEST	    				
	الهيئة العامة للإعانة الهيئة العامة للإعانة الهيئة العامة للإعانة الهيئة العامة للإعانة الهيئة العامة للإعانة				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		13-11-2022							
Contractor reference	CA-Emb-8									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		


Description of Materials	low embankment			FILL MATERIAL RESULTS		
Location to be Used	From 521+540 521+140	To 521+560 521+300	Fill -8.5 -9			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	10-11-2022		
2	Classification	m ³	5000	10-11-2022		
3	Proctor & O.m.c	m ³	5000	10-11-2022		
4	L.L & P.L & PI	m ³	5000	10-11-2022		
5	C.B.R	m ³	5000	13-11-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (Gomaa badr laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		13/11/2022	A
QA/QC *	Ahmed Abozaid		13/11/2022	A
GARB**	Hussien Fouad		13/11/2022	A
Comments by	Bid quantity Approved with @s			
Employers Representative	Mohamed Ahmed		8-2-23	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	18-11-2022	
Contractor Reference	CA-EMB-8-???			
Received by ER	<i>[Signature]</i>	MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	5.3%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	8.4%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	71.2%	
Comments by:		Comments by:		
		All test under Responsibility third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	<i>Ahmed Mohamed</i>	<i>Ahmed Mohamed</i>	18/11/2022	A
Contractor QA/QC *	<i>Ahmed Abo Zaied</i>	<i>Ahmed Abo Zaied</i>	18/11/2022	A
GARB**	<i>Hussein Fouad</i>	<i>Hussein Fouad</i>	18/11/2022	A
Employers Representative	<i>Mohamed Ahs</i>	<i>Mohamed Ahs</i>	18-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	7/11/2022	code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-8	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		17000.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
(g)Mass retained	1959.0	2315.0	2432.0	1498.0	1925.0	935.0	1481.0		A-1-a	
(g)Cumulative Retained	1959.0	4274.0	6706.0	8204.0	10129.0	11064.0	12545.0		PRO	2.17
Cumulative Retained %	11.5	25.1	39.4	48.3	59.6	65.1	73.8		WC	8.4
Cumulative Passing %	88.5	74.9	60.6	51.7	40.4	34.9	26.2		CBR	71%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	176.00	339.00	398.00					
Cumulative Retained %	35.20	67.80	79.60					
Cumulative Passing %	64.80	32.20	20.40					

C-General gradient										
(in)sieve size	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	88.5	74.9	60.6	51.7	40.4	34.9	26.2	17.0	8.4	5.3

ATTERBERG LIMITS	(. L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	N.P	N.P	N.P

Contractor

Consultant

مشروع الطرق والبنية التحتية
 القطاع السابع
 معمل المركزي
 (رقم 6)

القاهرة لطرق والبنية التحتية
 س.ت. ١٠٦٧٠٥
 ب.ق. ٥٥٦ - ٥٥٥

القاهرة
 س.ت. ١٠٦٧٠٥
 ب.ق. ٥٥٦ - ٥٥٥


PROCTOR TEST

Testing Date :	8/11/2022	code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
NAME COMPANY	cairo company		quaintily	5000 m3	

Weight of empty mold :	6428.0	MAX Dry Density	2.17
Mold Volume:	2104.9	Water content %	8.4

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	11069.0	11265.0	11376.0	11251	
WT. WET SOIL	4641.0	4837.0	4948.0	4823.0	
Wt. Density	2.205	2.298	2.351	2.291	

Tare No.	1	1	7	7	15	16	8	8		
Tare wt.	26.8	26.8	26.69	26.69	27.5	27.1	26.54	25.54		
Wt. Of wet soil & tare	152.0	152.0	120.8	120.8	146.6	156.0	142.0	142.0		
Wt. Of dry soil & tare	146.8	146.8	114.8	114.8	137.0	146.4	131.6	131.6		
Wt. Of water	5.2	5.2	6.1	6.1	9.6	9.6	10.3	10.3		
Wt. Of dry soil	120.0	120.0	88.1	88.1	109.5	119.3	105.1	106.1		
Water content %	4.3%	4.3%	6.9%	6.9%	8.7%	8.0%	9.8%	9.7%		
AV.Water content %	4.3%		6.9%		8.4%		9.8%			
Dry Density	2.113		2.150		2.169		2.087			



Contractor

Consultant

المكتب
العلمي
البحري



Electric Express Train - HSR



California Bearing Ratio TEST

Testing Date :	11/11/2022	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-EMB-8	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
(gm)Mold WT.	16553
(gm)Mold WT. + Wet WT.	21564
(gm)Wet WT.	5011
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.147
Proctor Density (g/cm ³)	2.170
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	4
Tare WT. (gm)	25.25
(gm)Tare WT. +Wet WT.	145.9
(gm)Tare WT. +Dry WT.	137.82
(gm)Water WT.	8.1
(gm)Dry WT.	112.6
Moisture Content %	7.2

Swelling	
Mold No.	2
Date	11/11/2022
(mm)Initial Height	4.0
(mm)Final Height	4.0
Difference	0
(mm)Sample Height	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penetration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(kg)Load Reading	165.00	291.00	457.00	638.00	805.00	923.00	1264.00	1455.00	1687.00
(KN)Load	1.6	2.9	4.5	6.3	7.9	9.0	12.4	14.3	16.5



Calculations :-

Penetration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR (%)
2.50	6.25	13.4	46.8%	99	99	46.9%
5.00	14.26	20.0	71.2%	99	99	71.2%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :


Sign :

شروع اعمار السكك الحديدية
القطاع السابع
معمل المركزي
(رقم 6)

القاهرة نظروا والإشراف
107 100 100
107 100 100

مجلس إدارة
مجلس إدارة
مجلس إدارة

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		14/11/2022																	
Contractor reference	CA-Emb-9																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		


Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+300	521+320	-9		
	521+560	521+680	-8.5		
	521+320	521+370	-8		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	10-11-2022	
2	Classification	m ³	5000	10-11-2022	
3	Proctor & O.m.c	m ³	5000	10-11-2022	
4	L.L & P.L & PI	m ³	5000	10-11-2022	
5	C.B.R	m ³	5000	14-11-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (el nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	eng / Ahmed mohammed		14/11/2022	A
QA/QC *	Ahmed Abo Zeid		14/11/2022	A
GARB**	Hussien Sallam		14/11/2022	A
Comments by	fill quantity approved with CS			
Employers Representative	Mohamed Ahmed		8-2-25	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company								
Electric express train	Cairo for Roads and construction Company			k.k								
Issued by Contractor	Name	Sign	Date	Time								
	ENG/ Abdelrahman Adel		14/11/2022									
Contractor Reference	CA-Emb-9 -											
Received by ER				MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	12.4%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.4%	
6	ASTM D 1557	Modified proctor	2.165	
7	ASTM D 1883	CBR	42.6%	
Comments by:		Comments by:		
		All test under Responsibility third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed Mohamed		14/11/2022	A
Contractor QA/QC *	Ahmed Abo Zeid		14/11/2022	A
GARB**	Hussien Fouad		14/11/2022	A
Employers Representative	Mohamed Ahmed		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للقواصة والسكك الحديدية (CAERU)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	10/11/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	KA-Emh-9	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		28776.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	2732.0	2956.0	2636.0	2685.0	2730.0	2963.0	2894.0		A-1-a	
Cumulative Retained (g)	2732.0	5688.0	8324.0	11009.0	13739.0	16702.0	19596.0		PRO	2.165
Cumulative Retained %	9.5	19.8	28.9	38.3	47.7	58.0	68.1		WC	6.40
Cumulative Passing %	90.5	80.2	71.1	61.7	52.3	42.0	31.9		CBR	42.60

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	96.40	203.00	305.40					
Cumulative Retained %	19.28	40.60	61.08					
Cumulative Passing %	80.72	59.40	38.92					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	90.5	80.2	71.1	61.7	52.3	42.0	31.9	25.8	18.9	12.4

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P

Contractor

Consultant





Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA TO MARS MATROUH
From Station 504+000 To Station 568+177



PROCTOR TEST


TESTING DATE:	10-11-2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	CA-Emb-9	Material	fill material layer	
NAME COMPANY	cairo company		quantity	5000 m3	

Weight of empty mold :	6190.0
Mold Volume:	2169.0

MAX Dry Density	2.165
Water content %	6.4


trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10623.0	10926.0	11185.0	10978	
WT. WET SOIL	4433.0	4736.0	4995.0	4788.0	
Wt. Density	2.044	2.183	2.303	2.207	

Tare No.	8	11	15	16	4	22	45	7		
Tare wt.	46.8	46.5	31.3	33.2	59.5	54	41.1	42.8		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.2	147.8	145.3	145.0	144.5	144.3	141.8	141.5		
Wt. Of water	2.8	2.2	4.7	5.0	5.5	5.7	8.2	8.5		
Wt. Of dry soil	100.4	101.3	114.0	111.8	85.0	90.3	100.7	98.7		
Water content %	2.8%	2.2%	4.1%	4.5%	6.5%	6.3%	8.1%	8.6%		
AV. Water content %	2.5%		4.3%		6.4%		8.4%			
Dry Density	1.994		2.094		2.165		2.037			



Contractor

القاهرة للطرق والإنشاءات
 ب.ت. ١٠٦٧٠٥
 ب.ف. ٥٨٦ - ٥٨٧ - ٥٨٨



Consultant

القاهرة للطرق والإنشاءات
 ب.ت. ١٠٦٧٠٥
 ب.ف. ٥٨٦ - ٥٨٧ - ٥٨٨

California Bearing Ratio TEST

Testing Date :	14-11-2022	Code	ZONE	520+500	522+000
Location :	Kp:521+000	CA-EMB-5	Material	fill material layer	
Company Name	cairo company		quantity	5000 m3	

- : Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2168
Mold WT. (gm)	5089
Mold WT. + Wet WT. (gm)	10078
Wet WT. (gm)	4989
Wet Density (g/cm ³)	2.301
Dry Density (g/cm ³)	2.166
Proctor Density (g/cm ³)	2.170
Compaction %	99.8

Moisture Ratio After Compacted Mold	
Tare No.	16
Tare WT. (gm)	33.9
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	143.2
Water WT. (gm)	6.8
Dry WT. (gm)	109.3
Moisture Content %	6.2

Swelling	
Mold No.	2
Date	14-11-2022
Initial Height (mm)	3.00
Final Height (mm)	3.00
Difference	0
Sample Height (mm)	11.90
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.07	0.09	0.13	0.16	0.19	0.22	0.26	0.29	0.33
Load (KN)	2.1	2.7	3.9	4.8	5.7	6.6	7.8	8.7	9.9



Calculations :-

Penetration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	4.80	13.4	36.0%	100	98	35.3%
5.00	8.70	20.0	43.4%			42.6%

Lab. Specialist

Name :
 التوقيع لمختبر الطرق والاسفلت
 ١٠٦٧٠٥
 ب ف

Lab. Engineer

Name :

Sign :



Electric Express Train
 Central Lab Number 4
 Sec-7 Puka - Matruh

Consultant Engineer

Name :

Sign :

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		18/12/2022							
Contractor reference	CA-Emb-31									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+810	521+900	-6.5		
	520+620	520+700	-9.5		
	520+800	520+825	-10		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	14-12-2022	
2	Classification	m ³	5000	14-12-2022	
3	Proctor & O.m.c	m ³	5000	14-12-2022	
4	L.L & P.L & PI	m ³	5000	14-12-2022	
5	C.B.R	m ³	5000	18-12-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		18-12-2022	A	
QA/QC *	Abdallah SAMY		18-12-2022	A	
GARB**	Hussien Fouad		18-12-2022	A	
Comments by	A sample quantity approval with @s		18-12-2022	A	
Employers Representative	Mohamed AWS		8-2-23	A	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		18/12/2022	
Contractor Reference	CA-Emb-31			
Received by ER		MAR	C1	C2
			C3	DD

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	15%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.5%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	70.6%	
Comments by:		Comments by:		
		All test under Responsibility Third Party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		15-12-2022	A
Contractor QA/QC *	Hassan		18-12-2022	A
GARB**	Hussein Fouad		18-12-2022	A
Employers Representative	Mohamed Ahmed		19-1-23	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 Electric Express Train SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإزاحة الميناء والخطوط (MATROUH)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11/12/2022	Code			
LOCATION	Kp:521+660		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-31			

1-visual inspection test

2-Gradient test


A-gradation of bulk materials				SAMPLE WEIGHT [g]		20233.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1225.0	1321.0	1236.0	1490.0	1652.0	1532.0	2142.0		A-1-a	
Cumulative Retained (g)	1225.0	2546.0	3782.0	5272.0	6924.0	8456.0	10598.0		PRO	2.15
Cumulative Retained %	6.1	12.6	18.7	26.1	34.2	41.8	52.4		WC	7.50
Cumulative Passing %	93.9	87.4	81.3	73.9	65.8	58.2	47.6		CBR	70.60

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	75.30	210.00	342.00					
Cumulative Retained %	15.06	42.00	68.40					
Cumulative Passing %	84.94	58.00	31.60					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	93.9	87.4	81.3	73.9	65.8	58.2	47.6	40.4	27.6	15.0

ATTEBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor



Consultant



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVS TRA	Electric Express Train - HSR		 الهيئة العامة للإعانة للمواصلات واقتصاد (CAE)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
		From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	12-12-2022	Code			
LOCATION	kp:521+560	CA-Emb-31	Station	520+500	522+000
NAME COMPANY	cairo company				

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.15
Water content %	7.5

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10532.0	10897.0	11078.0	10912	
WT. WET SOIL	4495.0	4860.0	5041.0	4875.0	
Wt. Density	2.066	2.233	2.317	2.240	

Tare No.	25	33	35	4	22	8	17	16		
Tare wt.	75.8	73.6	73.9	60.1	54.1	46.8	59.5	33.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	145.2	140.1	145.8	145.1	143.1	142.4	141.9	139.4		
Wt. Of water	4.8	9.9	4.2	4.9	6.9	7.6	8.1	10.6		
Wt. Of dry soil	123.0	267.8	71.9	85.0	89.0	95.6	82.4	105.5		
Water content %	3.9%	3.7%	5.8%	5.8%	7.8%	7.9%	9.8%	10.0%		
AV. Water content %	3.8%		5.8%		7.9%		9.9%			
Dry Density	1.990		2.111		2.148		2.038			




Contractor

المقاول
10-12-2022
521-560



Consultant

Abdelhameed



California Bearing Ratio TEST

Testing Date :	18/12/2022	Code	zone	520+500	522+000
Location :	kp:521+560	CA-Emb-3	Material	fill material layer	
Company Name	cairo company		quantity	5000 m3	

Test Results


Compaction % for Mold	
Mold No.	3
Mold Vol. (cm ³)	2025
Mold WT. (gm)	5034
Mold WT. + Wet WT. (gm)	9695
Wet WT. (gm)	4661
Wet Density (g/cm ³)	2.302
Dry Density (g/cm ³)	2.146
Proctor Density (g/cm ³)	2.150
Compaction %	99.8

Moisture Ratio After Compacted Mold	
Tare No.	73
Tare WT. (gm)	33.3
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	142.1
Water WT. (gm)	7.9
Dry WT. (gm)	108.8
Moisture Content %	7.3

Swelling	
Mold No.	3
Date	2022/12/18
Initial Height (mm)	4.00
Final Height (mm)	4.00
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.0%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.07	0.14	0.20	0.24	0.31	0.37	0.42	0.48	0.60
Load (KN)	2.1	4.2	6.0	7.2	9.3	11.1	12.6	14.4	18.0



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	98 عند نسبة 98
2.50	7.20	13.4	53.9%	100	98	53.0%
5.00	14.40	20.0	71.9%			70.6%

Lab. Specialist
 Name :
 Sign :

Lab. Engineer
 Name :
 Sign :
 Electric Express Train
 Central Lab Number 4
 Sec-7 Paka - Matrooh

Consultant Engineer
 Name :
 Sign :


MATERIAL APPROVAL REQUEST








Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Adel		18/12/2022																	
Contractor Reference	CA-Emb-32																			
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.9%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6%	
6	ASTM D 1557	Modified proctor	2.18	
7	ASTM D 1883	CBR	60.2%	
Comments by:		Comments by:		
		All test under Responsibility Thirty party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		18-12-2022	A
Contractor QA/QC *	Hassan		18-12-2022	A
GARB**	Hussien Fouad		18-12-2022	A
Employers Representative	Mahmoud Ahmed		15-1-25	A



* Designer

** Alignment/Bridges: Culvert only

MATERIAL INSPECTION REQUEST	    				
	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		18/12/2022							
Contractor reference	CA-Emb-32									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment					FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill							
	520+825	520+880	-10							
	520+700	520+800	-9.5							
MAR Approval No	520+880	520+900	-10			Date				
Supplier Name										
Test Requirement			Specification			Clause				
Reference Photos	Yes attached / No		Other							
Item	Description	Unit	Quantity	Arrival Date	Note					
1	Sieve analysis	m ³	5000	14-12-2022						
2	Classification	m ³	5000	14-12-2022						
3	Proctor & O.m.c	m ³	5000	14-12-2022						
4	L.L & P.L & PI	m ³	5000	14-12-2022						
5	C.B.R	m ³	5000	18-12-2022						
Comments by:					Comments by:					
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.					Test result for estimated quantities of about 5000 m3					
APPROVAL STATUS										
Organisation	Name	Sign	Date	A-AWC-R						
Contractor	eng / Ahmed mohammed		18-12-2022	A						
QA/QC *	Abdallah SANY		18-12-2022							
GARB**			18-12-2022							
Comments by	Req. quantity approval		18-12-2022							
Employers Representative	Mohamed A. H.		8-2-25							

* Designer

** Alignment / Bridges: Culvert Only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للإستشارات مصر
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARSALA MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	14/12/2022	Code			
LOCATION	kp:521+000		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-32			

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		27953.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	2114.0	2452.0	2489.0	2722.0	2352.0	2641.0	3142.0		A-1-a	
Cumulative Retained (g)	2114.0	4566.0	7055.0	9777.0	12129.0	14770.0	17912.0		PRO	2.18
Cumulative Retained %	7.6	16.3	25.2	35.0	43.4	52.8	64.1		WC	6.00
Cumulative Passing %	92.4	83.7	74.8	65.0	56.6	47.2	35.9		CBR	60.20


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	73.00	200.00	305.90					
Cumulative Retained %	14.60	40.00	61.18					
Cumulative Passing %	85.40	60.00	38.82					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	92.4	83.7	74.8	65.0	56.6	47.2	35.9	30.7	21.6	13.9

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Signature of Consultant



 	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST



TESTING DATE:	15-12-2022	Code			
LOCATION	kp:521+000		Station	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-32			

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.18
Water content %	6

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10652.0	10971.0	11082.0	10955	
WT. WET SOIL	4615.0	4934.0	5045.0	4918.0	
Wt. Density	2.121	2.267	2.318	2.260	

Tare No.	8	15	21	7	90	16	17	45		
Tare wt.	46.8	31.9	55.2	42.8	62.5	33.9	59.5	41.5		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.6	142.2	145.7	145.0	144.5	142.5	142.9	141.2		
Wt. Of water	3.4	7.8	4.3	5.0	5.5	7.5	7.1	8.8		
Wt. Of dry soil	123.0	267.8	90.5	102.2	82.0	108.6	83.4	99.7		
Water content %	2.8%	2.9%	4.8%	4.9%	6.7%	6.9%	8.5%	8.8%		
AV. Water content %	2.8%		4.8%		6.8%		8.7%			
Dry Density	2.062		2.163		2.171		2.080			



Consultant

Abdo Sam



 	Electric Express Train - HSR	 
---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	18/12/2022	Code	FROM STA :	520+500	522+000
Location :	kp:521+000	CAE mb-32			
Company Name	cairo company				

:- Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9840
Wet WT. (gm)	4940
Wet Density (g/cm ³)	2.308
Dry Density (g/cm ³)	2.179
Proctor Density (g/cm ³)	2.180
Compaction %	99.9

Moisture Ratio After Compacted Mold	
Tare No.	8
Tare WT. (gm)	46.8
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	144.2
Water WT. (gm)	5.8
Dry WT. (gm)	97.4
Moisture Content %	6.0

Swelling	
Mold No.	4
Date	18-12-2022
Initial Height (mm)	9.00
Final Height (mm)	9.10
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.1%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.04	0.09	0.14	0.19	0.25	0.31	0.37	0.41	0.57
Load (KN)	1.2	2.7	4.2	5.7	7.5	9.3	11.1	12.3	17.1




Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	% عند نسبة 98
2.50	5.70	13.4	42.7%	100	98	41.9%
5.00	12.30	20.0	61.4%			60.2%




Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Sign :
--	--	--

MATERIAL INSPECTION REQUEST	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		20/12/2022							
Contractor reference	CA-Emb-33									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower embankment			FILL MATERIAL RESULTS		
Location to be Used	From	To	Fill			
	520+900	521+000	-10			
	520+880	520+970	-9.5			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	16-12-2022		
2	Classification	m ³	5000	16-12-2022		
3	Proctor & O.m.c	m ³	5000	16-12-2022		
4	L.L & P.L & PI	m ³	5000	16-12-2022		
5	C.B.R	m ³	5000	20-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		20-12-2022	A
QA/QC *	Abdallah SANY		20-12-2022	A
GARB**	Hussien Fouad		20-12-2022	A
Comments by	fill quantity approval with QCS		20-12-2022	A
Employers Representative	Mohamed Awa		8-2-23	

* Designer

** Alignment / Bridges: Culvert Only

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials		lower embankment Soil (A-1-a)		
Location of stock		K.p (521+000) No (2)		
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.4%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	61.7%	
Comments by:			Comments by:	
			All test under Responsibility third party	

* Designer
** Alignment/Bridges: Culvert only

		Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	
Operating Lab AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	16/12/2022	Code	ZONE	520+500	522+000
LOCATION	kp:521+000	A-Emb-33			
NAME COMPANY	caire company				

1-visual inspection test

2-Gradient test


A-gradation of bulk materials				SAMPLE WEIGHT [g]		29372.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	2050.0	2490.0	2533.0	2852.0	2521.0	2650.0	3152.0		A-1-a	
Cumulative Retained (g)	2050.0	4540.0	7073.0	9925.0	12446.0	15096.0	18248.0		PRO	2.17
Cumulative Retained %	7.0	15.5	24.1	33.8	42.4	51.4	62.1		WC	6.00
Cumulative Passing %	93.0	84.5	75.9	66.2	57.6	48.6	37.9		CBR	61.70

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	66.30	190.00	310.00					
Cumulative Retained %	13.26	38.00	62.00					
Cumulative Passing %	86.74	62.00	38.00					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	93.0	84.5	75.9	66.2	57.6	48.6	37.9	32.9	23.5	14.4

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor



Consultant





 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فاضل	 SYSTRA SHAKER	Electric Express Train - HSR		 الهيئة العامة للطرق والنقل الجوي GACA
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
		From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	17/12/2022	Code			
LOCATION	kp:521+000		Station	520+500	522+000
NAME COMPANY	cairo company	A-Emb-33			

Weight of empty mold :	6037.0
Mold Volume:	2176.0

MAX Dry Density	2.17
Water content %	6

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10352.0	10875.0	11065.0	10876	
WT. WET SOIL	4315.0	4838.0	5028.0	4839.0	
Wt. Density	1.983	2.223	2.311	2.224	


Tare No.	16	40	7	19	73	26	20	35		
Tare wt.	33.9	46.4	42.8	44.4	72.9	55	60.9	73.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.5	142.1	145.1	145.2	145.1	144.1	143.1	144.2		
Wt. Of water	3.5	7.9	4.9	4.8	4.9	5.9	6.9	5.8		
Wt. Of dry soil	123.0	267.8	102.3	100.8	72.2	89.1	82.2	70.3		
Water content %	2.8%	2.9%	4.8%	4.8%	6.8%	6.6%	8.4%	8.3%		
AV. Water content %	2.9%		4.8%		6.7%		8.3%			
Dry Density	1.927		2.122		2.165		2.053			



Contractor
 شركة مصر للطرق والبنية التحتية
 ب.م.ت. ١٠٦٧٠٥
 ٥٤٥ - ٥٤٣ - ٥٤٦



Consultant
 Modest



California Bearing Ratio TEST

Testing Date :	20/12/2022	Code	zone	520+500	522+000
Location :	Kp:521+000	CA-Emb-33	Material	fill material	
Company Name	cairo company		quantity	5000m3	

-: Test Results


Compaction % for Mold	
Mold No.	5
Mold Vol. (cm ³)	2122
Mold WT. (gm)	5075
Mold WT. + Wet WT. (gm)	9955
Wet WT. (gm)	4880
Wet Density (g/cm ³)	2.300
Dry Density (g/cm ³)	2.170
Proctor Density (g/cm ³)	2.170
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	10
Tare WT. (gm)	43.7
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	144
Water WT. (gm)	6.0
Dry WT. (gm)	100.3
Moisture Content %	6.0

Swelling	
Mold No.	5
Date	20-12-2022
Initial Height (mm)	7.00
Final Height (mm)	7.05
Difference	0.05
Sample Height (mm)	120.00
Swelling Ratio %	0.04%

Loading Reading :

46.50	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.10	0.15	0.20	0.24	0.29	0.33	0.37	0.42	0.59
Load (KN)	3.0	4.5	6.0	7.2	8.7	9.9	11.1	12.6	17.7



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	98 عند نسبة %
2.50	7.20	13.4	53.9%	100	98	52.9%
5.00	12.60	20.0	62.9%			61.7%

Lab. Specialist
 Name :
 Sign :

Lab. Engineer
 Name :
 Sign :
 Electric Express Train
 Central Lab Number 4
 Sec-7 Puka Matrouh

Consultant Engineer
 Name :
 Sign :

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		20-12-2022																	
Contractor reference	C A-Emb-34																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	520+970	521+000	-9.5		
	521+140	521+315	-7		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	16-12-2022	
2	Classification	m ³	5000	16-12-2022	
3	Proctor & O.m.c	m ³	5000	16-12-2022	
4	L.L & P.L & PI	m ³	5000	16-12-2022	
5	C.B.R	m ³	5000	20-12-2022	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El mahjoub laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		2-12-2022	A	
QA/QC *	Abdallah S. Ali		2-12-2022	A	
GARB**	Hussien Fouad		2-12-2022	A	
Comments by	fill quantity approved with @s				
Employers Representative	Mohamed Ali		8-2-25	A	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company				Designer Company					
Electric express train	Cairo for Roads and construction Company				k.k					
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		20-12-2022							
Contractor Reference	CA-Emb-34									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.9%	
4	ASTM D 4318	Atterberg limit	19.2%	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	48.4%	
Comments by:		Comments by:		
		All test under Responsibility Third party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		20/12/2022	A
Contractor QA/QC *	Hassan		20/12/2022	A
GARB**	Hussien Fouad		20/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	17/12/2022	code			
LOCATION	K.P 521+000		ZONE	520+500	522+000
NAME COMPANY	CAIRO	CA-Emb-34			

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20863.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	165.0	1876.0	2387.0	2765.0	1986.0	4402.8		A-1-a
Cumulative Retained (g)	0.0	165.0	2041.0	4428.0	7193.0	9179.0	13581.8	PRO	2.155%
Cumulative Retained %	0.0	0.8	9.8	21.2	34.5	44.0	65.1	WC	6.8%
Cumulative Passing %	100.0	99.2	90.2	78.8	65.5	56.0	34.9	CBR	48.4%


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	132.00	240.00	329.00					
Cumulative Retained %	26.40	48.00	65.80					
Cumulative Passing %	73.60	52.00	34.20					

C-General gradlent										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	99.2	90.2	78.8	65.5	56.0	34.9	25.7	18.1	11.9

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	24.9%	19.2%	5.7%

Contractor

Consultant




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR	 الهيئة العامة للإستراتيجية للحديد والقطار الكهربائي (إ.م.م.م.)
---	--	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits




Testing Date:	2022-12-17	Code:	ZONE	520+500	522+000
Location:	521+000				
Layer No. :	CAIRO	CA-Emb-34			

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	18	23	29	34	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	34.65	30.32	22.65	30.76	10.22	20.65
Tare WT. + Wet WT. (gm)	54.30	44.87	43.43	55.32	10.98	21.11
Tare WT. + Dry WT. (gm)	50.27	41.95	39.37	50.60	10.86	21.04
Water WT. (gm)	4.03	2.92	4.06	4.72	0.12	0.07
Dry WT. (gm)	15.62	11.63	16.72	19.84	0.64	0.39
Moisture Content %	25.8%	25.1%	24.3%	23.8%	18.9%	19.5%
Average %					19.2%	



L.L	P.L	P.I
24.9%	19.2%	5.7%

Lab. Specialist Name:  Sign: 	Lab. Engineer Name:  Sign: 	Consultant Engineer Name: Hassan Sign: 
--	--	---



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للغذاء والدواء SASRI

PROCTOR TEST



TESTING DATE:	18/12/2022	code		
LOCATION	K.P 521+000		ZONE	520+500 522+000
NAME COMPANY	CAIRO	CA-6mb-3u		

Weight of empty mold :	6058.0
Mold Volume:	2032.0

MAX Dry Density	2.155
Water content %	6.8%

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10081.4	10664.5	10739.7	10636.1	
WT. WET SOIL	4023.4	4606.5	4681.7	4578.1	
Wt. Density	1.980	2.267	2.304	2.253	

Tare No.	2	2	5	6	20	12	12	12		
Tare wt.	30.34	28.56	22.77	28.98	30.57	30.65	30.79	28.98		
Wt. Of wet soil & tare	167.7	155.87	155.98	174.73	155.87	167.43	155.48	166.98		
Wt. Of dry soil & tare	163.4	150.72	148.2	166.25	147.56	158.009999	145.82	155.97		
Wt. Of water	4.3	5.2	7.8	8.5	8.3	9.4	9.7	11.0		
Wt. Of dry soil	133.0	122.2	125.4	137.3	117.0	127.4	115.0	127.0		
Water content %	3.2%	4.2%	6.2%	6.2%	7.1%	7.4%	8.4%	8.7%		
AV. Water content %	3.7%		6.2%		7.2%		8.5%			
Dry Density	1.909		2.145		2.148		2.076			



20/12/2022

Hassan



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد قنديل	 Electric Express Train - HSR	 الهيئة العامة للإعانة الميناء والخطوط (SARL)
--	---	---

California Bearing Ratio TEST

Testing Date :	20/12/2022	Code	ZONE	520+500	522+000
Location :	521+000	CA-EMB-3U			
Layer No. :	CAIRO				

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.078
Proctor Density (g/cm ³)	2.155
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. + Wet WT. (gm)	233
Tare WT. + Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	6.8

Swelling	
Mold No.	55
Date	20/12/2022
Initial Height (mm)	5.00
Final Height (mm)	5.00
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :


Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	71.00	160.00	270.00	390.00	540.82	690.00	840.00	960.00	1250.00
Load (KN)	0.7	1.6	2.6	3.8	5.3	6.8	8.2	9.4	12.3




Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	عدد نسبة 98
2.50	3.82	13.4	28.6%	99	98	29.7%
5.00	9.41	20.0	47.0%			48.4%

Lab. Specialist	Lab. Engineer	Consultant Engineer
Name :	Name :	Name : Hassan
Sign :	Sign :	Sign :








Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		25-12-2022																	
Contractor reference	CA-EMB-35																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS					
Location to be Used	From 521+315 521+560 521+700	To 521+320 521+700 521+780	Fill -7 -6 -6			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No	Other				
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	21-12-2022		
2	Classification	m ³	5000	21-12-2022		
3	Proctor & O.m.c	m ³	5000	21-12-2022		
4	L.L & P.L & PI	m ³	5000	21-12-2022		
5	C.B.R	m ³	5000	25-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El mahjoub laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		25/12/2022	A		
QA/QC *	Abdallah SAMY		25/12/2022	A		
GARB**	Hussien Fouad		25/12/2022	A		
Comments by	Risk quantity approval with CS					
Employers Representative	Mohamed Akh		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company						
Electric express train	Cairo for Roads and construction Company			k.k						
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		26-12-2022							
Contractor Reference	CA-Emb-35									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.6%	
4	ASTM D 4318	Atterberg limit	18.7%	
5	ASTM D 2974	Moisture content	6.7%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	48.4%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		25/12/2022	A
Contractor QA/QC *	Hassan		25/12/2022	A
GARB**	Hussien Fouad		25/12/2022	A
Employers Representative	Mohamed Ahmed		15-1-25	D

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	22/12/2022	code		ZONE	520+500	522+000
LOCATION	K.P 521+000		CA-5m6-35			
NAME COMPANY	CAIRO					

1-visual inspection test


2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		19548.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	120.0	243.0	1575.0	2657.0	2986.0	1875.0	3563.0		A-1-a
Cumulative Retained (g)	120.0	363.0	1938.0	4595.0	7581.0	9456.0	13019.0	PRO	2.157
Cumulative Retained %	0.6	1.9	9.9	23.5	38.8	48.4	66.6	WC	6.7%
Cumulative Passing %	99.4	98.1	90.1	76.5	61.2	51.6	33.4	CBR	48.4%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	132.00	249.00	327.00					
Cumulative Retained %	26.40	49.80	65.40					
Cumulative Passing %	73.60	50.20	34.60					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	99.4	98.1	90.1	76.5	61.2	51.6	33.4	24.6	16.8	11.6

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	23.6%	18.7%	4.9%



Consultant

25/12/2022 Hassan




 	Electric Express Train - HSR	
---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	2022-12-22	Code:	CA-Emb-35	ZONE	520+500	522+000
Location:	521+000					
Layer No. :	CAIRO					

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	19	21	28	33	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	33.42	30.45	22.87	28.89	10.87	12.65
Tare WT. + Wet WT. (gm)	56.43	44.87	34.64	47.54	11.87	13.76
Tare WT. + Dry WT. (gm)	51.91	42.07	32.42	44.12	11.71	13.59
Water WT. (gm)	4.52	2.80	2.22	3.42	0.16	0.17
Dry WT. (gm)	18.49	11.62	9.55	15.23	0.84	0.94
Moisture Content %	24.5%	24.1%	23.2%	22.5%	19.3%	18.1%
Average %					18.7%	



L.L	P.L	P.I
23.6%	18.7%	4.9%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Hassan Sign : 25/12/2022
--	--	--





 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد قنديل	 SVSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		 الهيئة العامة للقنوات القناة السويسية (SUA)


PROCTOR TEST

TESTING DATE:	23/12/2022	code		
LOCATION	K.P. 521+000	CA-Emb-38	ZONE	520+500 522+000
NAME COMPANY	CAIRO			

Weight of empty mold :	6055.0	MAX Dry Density	2.157
Mold Volume:	2032.0	Water content %	6.70%

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10102.7	10653.4	10730.6	10604.6	
WT. WET SOIL	4047.7	4598.4	4675.6	4549.6	
Wt. Density	1.992	2.263	2.301	2.239	

Tare No.	2	2	5	6	20	12	12	12		
Tare wt.	30.12	28.87	29.44	22.8	26.79	28.99	22.99	33.84		
Wt. Of wet soil & tare	156.9	156.76	138.98	156.43	160.91	163.89	145.78	168.93		
Wt. Of dry soil & tare	152.4	151.73	132.85	148.49	151.82	155.07	136.16	157.52		
Wt. Of water	4.5	5.0	6.1	7.9	9.1	8.8	9.6	11.4		
Wt. Of dry soil	122.2	122.9	103.4	125.7	125.0	126.1	113.2	123.7		
Water content %	3.7%	4.1%	5.9%	6.3%	7.3%	7.0%	8.5%	9.2%		
AV. Water content %	3.9%		6.1%		7.1%		8.9%			
Dry Density	1.917		2.145		2.148		2.057			



Consultant

25/12/2022 Hassan



المكتب الاستشاري الهندسي
أ. د. خالد قنديل

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد قنديل	 Electric Express Train - HSR	 الهيئة العامة للإعانة الميناء والقناة والملاحة (ASBL)
--	---	--

California Bearing Ratio TEST

Testing Date :	25/12/2022	Code	CA-8mb-35	ZONE	520+500	522+000
Location :	821+000					
Layer No. :	CAIRO					

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.080
Proctor Density (g/cm ³)	2.157
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. + Wet WT. (gm)	233
Tare WT. + Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	6.7

Swelling	
Mold No.	55
Date	5/12/2022
Initial Height (mm)	4.50
Final Height (mm)	4.50
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	82.00	184.00	299.00	419.00	561.22	702.00	857.14	979.59	1275.51
Load (KN)	0.8	1.8	2.9	4.1	5.5	6.9	8.4	9.6	12.5



Calculations :-

Penetration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR (at 98% compaction)
2.50	4.11	13.4	30.8%	99	98	29.7%
5.00	9.60	20.0	47.9%			48.4%

Lab. Specialist

Name :

Sign :

Lab. Engineer
Name :
معمل اختبارات وإبحاث التربة
القطار السريع - فوكه - مطروح
المحجوب


Consultant Engineer

Name : Walsan




Sign :

المكتب الاستشاري الهندسي
أ. د. خالد قنديل

MATERIAL INSPECTION REQUEST	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		25-12-2022							
Contractor reference	CA-Emb-36									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+780	521+800	-6			
	521+900	522+000	-6.5			
	521+440	521+545	-6			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	21-12-2022		
2	Classification	m ³	5000	21-12-2022		
3	Proctor & O.m.c	m ³	5000	21-12-2022		
4	L.L & P.L & PI	m ³	5000	21-12-2022		
5	C.B.R	m ³	5000	25-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El mahjoub laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	eng / Ahmed mohammed		25/12/22	A		
QA/QC *	Abdallah SAMY		25/12/22	A		
GARB**	Hussien Fouad		25/12/22	A		
Comments by	File quantity approved with Bs					
Employers Representative	Mohamed Ali		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	25-12-2022																	
Contractor Reference	CA-Emb-36																			
Received by ER	<i>[Signature]</i>	MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.7%	
4	ASTM D 4318	Atterberg limit	17%	
5	ASTM D 2974	Moisture content	6.2%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	48.4%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel	<i>Abdelrahman Adel</i>	25/12/2022	A
Contractor QA/QC *	Hassan	<i>Hassan</i>	25/12/2022	A
GARB**	Hussien Fouad	<i>Hussien Fouad</i>	25/12/2022	A
Employers Representative	Mohamed Ahmed	<i>Mohamed Ahmed</i>	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSFA SHAKER	Electric Express Train - HSR		 الهيئة العامة للنقل Ministry of Transport EGYPT
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
		From Station 504+000 To Station 568+177		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	22/12/2022	code		ZONE	520+500	522+000
LOCATION	K.P. 521+000					
NAME COMPANY	CAIRO	CA-Emb-36				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		20884.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	0.0	56.0	1432.0	2576.0	2698.0	1987.0	4595.0		A-1-a	
Cumulative Retained (g)	0.0	56.0	1488.0	4064.0	6762.0	8749.0	13344.0		PRO	2.159
Cumulative Retained %	0.0	0.3	7.1	19.5	32.4	41.9	63.9		WC	6.20%
Cumulative Passing %	100.0	99.7	92.9	80.5	67.6	58.1	36.1		CBR	48.4%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	103.00	205.00	296.00					
Cumulative Retained %	20.60	41.00	59.20					
Cumulative Passing %	79.40	59.00	40.80					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.0	99.7	92.9	80.5	67.6	58.1	36.1	28.7	21.3	14.7

ATTEBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	21.5%	17.0%	4.5%

Contractor	معمل اختبارات وأبحاث التربة القطار السريع - فوكا - مطروح
------------	---

Consultant	Hassan 25/12/2022
------------	----------------------


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA	Electric Express Train - HSR	 الهيئة العامة للنقل وزارة النقل مصر
--	---	-------------------------------------	--

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	2022-12-22	Code:	ZONE	520+500	522+000
Location:	521+000	CA-8m6-36			
Layer No. :	CAIRO				

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	17	22	28	33	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	28.43	30.54	28.54	24.54	11.87	10.56
Tare WT. + Wet WT. (gm)	39.54	44.38	39.76	44.58	13.75	11.67
Tare WT. + Dry WT. (gm)	37.49	41.89	37.80	41.20	13.48	11.51
Water WT. (gm)	2.05	2.49	1.96	3.38	0.27	0.16
Dry WT. (gm)	9.06	11.35	9.26	16.66	1.61	0.95
Moisture Content %	22.6%	21.9%	21.1%	20.3%	16.6%	17.3%
Average %					17.0%	



L.L	P.L	P.I
21.5%	17.0%	4.5%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :


Sign :

Name :

Sign :

Name :

Sign :



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTRA شركة صستر	Electric Express Train - HSR		 الهيئة الوطنية للأمن والسلامة (SASRI)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
		From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	23/12/2022	code		
LOCATION	K.P. 521+000		ZONE	520+500 522+000
NAME COMPANY	CAIRO	CA-Emb-6		

Weight of empty mold :	6055.0
Mold Volume:	2032.0

MAX Dry Density	2.159
Water content %	6.20%

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10019.4	10625.0	10712.3	10588.4	
WT. WET SOIL	3964.4	4570.0	4657.3	4533.4	
Wt. Density	1.951	2.249	2.292	2.231	

Tare No.	2	2	5	6	20	12	17	22		
Tare wt.	37.31	36.38	29.54	34.98	38.65	30.87	28.55	33.12		
Wt. Of wet soil & tare	156.9	168.32	165.43	156.76	167.98	135.69	156.8	160.87		
Wt. Of dry soil & tare	153.3	163.75	158.11	150.09	159.86	128.93	147.37	151.18		
Wt. Of water	3.5	4.6	7.3	6.7	8.1	6.8	9.4	9.7		
Wt. Of dry soil	116.0	127.4	128.6	115.1	121.2	98.1	118.8	118.1		
Water content %	3.0%	3.6%	5.7%	5.8%	6.7%	6.9%	7.9%	8.2%		
AV. Water content %	3.3%		5.7%		6.8%		8.1%			
Dry Density	1.888		2.145		2.146		2.064			



Contractor

Consultant

شركة المحجوب للمقاولات الهندسية والبناء
معمل اختيار التربة والحدوث التربة
القطار السريع - فوكا - ماطرويه
معمل اختيار التربة والحدوث التربة
القطار السريع - فوكا - ماطرويه

25/12/2022
Hassan
2022
المكتب الاستشاري الهندسي
أ.د. خالد قنديل

California Bearing Ratio TEST

Testing Date :	25/12/2022	Code		
Location :	521+000		ZONE	520+500
Layer No. :	CAIRO	CA-8mb-36		522+000

Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.090
Proctor Density (g/cm ³)	2.159
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. +Wet WT. (gm)	233
Tare WT. +Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	6.2

Swelling	
Mold No.	55
Date	25/12/2022
Initial Height (mm)	4.50
Final Height (mm)	4.50
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	62.00	164.00	280.00	397.96	530.00	675.00	820.00	950.00	1240.00
Load (KN)	0.6	1.6	2.7	3.9	5.2	6.6	8.0	9.3	12.2



Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	معدل نسبة 98 %
2.50	3.90	13.4	29.2%	99	98	29.7%
5.00	9.31	20.0	46.5%			48.4%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :

MATERIAL INSPECTION REQUEST						

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K															
Issued by Contractor	Name	Sign	Date	Time															
	Eng/ Abdelrahman Adel		25-12-2022																
Contractor reference	CA-Emb-37																		
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+545	521+560	-6			
	521+800	521+900	-6			
	520+900	520+990	-9			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	21-12-2022		
2	Classification	m ³	5000	21-12-2022		
3	Proctor & O.m.c	m ³	5000	21-12-2022		
4	L.L & P.L & PI	m ³	5000	21-12-2022		
5	C.B.R	m ³	5000	25-12-2022		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (El mahjoub laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		25/12/2022	A		
QA/QC *	Abdallah Sany		25/12/2022	A		
GARB**	Hussien Fomad		25/12/2022	A		
Comments by	fill quantity approved with G3					
Employers Representative	Mohamed Ali		8-2-23	AUC		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		25-12-2022	
Contractor Reference	CA-Emb-37			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.6%	
4	ASTM D 4318	Atterberg limit	17.5%	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	44.5	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		25/12/2022	A
Contractor QA/QC *	Hassan		25/12/2022	A
GARB**	Hussien Fouad		25/12/2022	A
Employers Representative	Mohamed Ahmed		13-1-23	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	22/12/2022	code			
LOCATION	K.P 520+500	CA-6mb-37	ZONE	520+500	522+000
NAME COMPANY	CAIRO				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT (g)		25412.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	726.0	2313.0	2741.0	2841.0	1842.0	2336.0	3524.0		A-1-a
Cumulative Retained (g)	726.0	3039.0	5780.0	8621.0	10463.0	12799.0	16323.0	PRO	2.15
Cumulative Retained %	2.9	12.0	22.7	33.9	41.2	50.4	64.2	WC	6.8%
Cumulative Passing %	97.1	88.0	77.3	66.1	58.8	49.6	35.8	CBR	44.5%

B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	87.00	174.00	296.00				
Cumulative Retained %	17.40	34.80	59.20				
Cumulative Passing %	82.60	65.20	40.80				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	97.1	88.0	77.3	66.1	58.8	49.6	35.8	29.5	23.3	14.6

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	23.20	17.50	5.70

Contractor

 شركة المهندسين المعماريين والهندسة المدنية والبيئية

 عمل اختبارات وأبحاث التربة

 المهندس الاستشاري

 المهندس الاستشاري

 المهندس الاستشاري

Consultant

Her 3/2

 25 12 2022


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد قنديل	 SVSIFA SHAKER	Electric Express Train - HSR	 الهيئة العامة للنقل مصر
--	--	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	2022-12-22	Code:	ZONE	520+500	522+000
Location:	520+500	CA-EMB-37			
Layer No. :	CAIRO				

Testing Results :-

Test	Liqud Limit				Plastic Limit	
No. of Ticks	16	23	29	35	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	37.90	35.40	29.32	35.90	19.75	22.03
Tare WT. + Wet WT. (gm)	52.50	56.39	53.43	50.41	20.56	23.22
Tare WT. + Dry WT. (gm)	49.63	52.45	48.99	47.78	20.44	23.04
Water WT. (gm)	2.87	3.94	4.44	2.63	0.12	0.18
Dry WT. (gm)	11.73	17.05	19.67	11.88	0.69	1.01
Moisture Content %	24.4%	23.1%	22.6%	22.2%	17.3%	17.7%
Average %					17.5%	



L.L	P.L	P.I
23.2%	17.5%	5.7%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name :

Sign

Name :

Sign :

Name :

Sign :

25/12/2022
Hassa



المكتبة
الهندسية
أ. د. خالد قنديل

California Bearing Ratio TEST

Testing Date :	25/12/2022	Code	ZONE	520+500	522+000
Location :	520+500	CAIRO	CA-Em6-37		
Layer No. :					

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20473.58
Wet WT. (gm)	4774
Wet Density (g/cm ³)	2.219
Dry Density (g/cm ³)	2.078
Proctor Density (g/cm ³)	2.150
Compaction %	98

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. +Wet WT. (gm)	233
Tare WT. +Dry WT. (gm)	221
Water WT. (gm)	12.0
Dry WT. (gm)	190.0
Moisture Content %	6.8

Swelling	
Mold No.	55
Date	25/12/2022
Initial Height (mm)	4.50
Final Height (mm)	4.50
Difference	0
Sample Height (mm)	122.00
Swelling Ratio %	0%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	52.00	143.00	253.00	370.00	505.00	640.00	785.00	910.00	1235.00
Load (KN)	0.5	1.4	2.5	3.6	4.9	6.3	7.7	8.9	12.1



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	3.63	13.4	27.2%	99	98	29.7%
5.00	8.92	20.0	44.5%			48.4%

Lab. Specialist

Name :

Sign :

المختبر
 ١٠٠٧٠٠٠
 ٥٥٥ - ٥٥٥

Lab. Engineer

Name :

Sign :

المختبر
 ١٠٠٧٠٠٠
 ٥٥٥ - ٥٥٥


Consultant Engineer

Name :

Sign :

المختبر
 ١٠٠٧٠٠٠
 ٥٥٥ - ٥٥٥

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		3/1/2023																	
Contractor reference	CA-Emb-38																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	520+990	521+000	-9		
	520+620	520+700	-9		
	520+700	520+795	-9		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	1-1-2023	
2	Classification	m ³	5000	1-1-2023	
3	Proctor & O.m.c	m ³	5000	1-1-2023	
4	L.L & P.L & PI	m ³	5000	1-1-2023	
5	C.B.R	m ³	5000	3-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El mahjoub laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		3-1-2023	A
QA/QC *	Abdallah SAMY		3-1-2023	
GARB**	Hussien Fouad		3-1-2023	
Comments by	Rid Amaty approval with Qc		3-1-2023	A
Employers Representative	Mohamed Ahmed		8-2-23	QWC

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company						
Electric express train	Cairo for Roads and construction Company			k.k						
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		3/1/2023							
Contractor Reference	CA-Emb-38									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.9%	
4	ASTM D 4318	Atterberg limit	18.6%	
5	ASTM D 2974	Moisture content	6.9%	
6	ASTM D 1557	Modified proctor	2.14	
7	ASTM D 1883	CBR	45.1%	
Comments by:			Comments by:	
			All test under Responsibility Third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Ahmed Mohamed		3-1-2023	A
Contractor QA/QC *	Abdallah SAMY		3-1-2023	
GARB**	Hussien Fouad		3-1-2023	A
Employers Representative	Mohd Ohs		13-1-23	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARS MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	30/12/2023	code	ZONE	520+500	522+000
LOCATION	520+500	CA-Emb-38	Material	embankment	
NAME COMPANY	Cairo				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		19795.00	gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS
Mass retained (g)	167.0	1148.0	2219.0	3188.0	2391.0	1476.0	2418.0	
Cumulative Retained (g)	167.0	1315.0	3534.0	6722.0	9113.0	10589.0	13007.0	PRO
Cumulative Retained %	0.8	6.6	17.9	34.0	46.0	53.5	65.7	WC
Cumulative Passing %	99.2	93.4	82.1	66.0	54.0	46.5	34.3	CBR
								2.149
								6.9%
								45.5%


B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	90.00	199.00	298.00				
Cumulative Retained %	18.00	39.80	59.60				
Cumulative Passing %	82.00	60.20	40.40				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	99.2	93.4	82.1	66.0	54.0	46.5	34.3	28.1	20.6	13.9

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	22.70	18.60	4.10

Contractor

Consultant




 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SVSTRA SHAKER	Electric Express Train - HSR	 الهيئة العامة للغذاء والدواء SARBIT
--	--	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date:	2023/12/31	Code:				
Location:	520+500		ZONE	520+500	TO STA:	522+000
NAME COMPANY :	Cairo	A-Emb-38				

Testing Results :-

Test	Liquid Limit				Plastic Limit	
No. of Ticks	16	23	29	35	-	-
Tare No.	20	7	21	25	5	23
Tare WT. (gm)	23.29	32.97	33.15	14.08	20.06	13.42
Tare WT. + Wet WT. (gm)	42.38	41.95	46.34	22.59	20.92	13.95
Tare WT. + Dry WT. (gm)	38.70	40.27	43.95	21.08	20.78	13.87
Water WT. (gm)	3.68	1.68	2.39	1.51	0.14	0.08
Dry WT. (gm)	15.41	7.30	10.80	7.00	0.72	0.45
Moisture Content %	23.9%	23.0%	22.2%	21.6%	19.4%	17.8%
Average %					18.6%	



L.L	P.L	P.I
22.7%	18.6%	4.1%



Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Sign :
--	--	--

PROCTOR TEST


TESTING DATE:	11/12/2023	code	Station	520+500	522+000
LOCATION	520+500		Material	embankment	
NAME COMPANY	Cairo	CA-Emb-38			

Weight of empty mold :	6055.0
Mold Volume:	2032.0

MAX Dry Density	2.149
Water content %	6.9%

trial no :	1	2	3	4	5
Wt. Of Mold+ wet soil	10023.5	10639.2	10724.5	10621	
WT. WET SOIL	3968.5	4584.2	4669.5	4565.9	
Wt. Density	1.953	2.256	2.298	2.247	

Tare No.	2	2	5	6	20	12	7	6		
Tare wt.	30.21	28.98	34.87	22.98	34.87	29.65	34.56	38.65		
Wt. Of wet soil & tare	156.9	155.87	176.76	155.98	156.87	155.89	156.87	156.23		
Wt. Of dry soil & tare	152.3	150.76	168.86	148.08	148.84	147.03	147.24	146.82		
Wt. Of water	4.5	5.1	7.9	7.9	8.0	8.9	9.6	9.4		
Wt. Of dry soil	122.1	121.8	134.0	125.1	114.0	117.4	112.7	108.2		
Water content %	3.7%	4.2%	5.9%	6.3%	7.0%	7.5%	8.5%	8.7%		
AV. Water content %	4.0%		6.1%		7.3%		8.6%			
Dry Density	1.879		2.126		2.142		2.069			



California Bearing Ratio TEST

Testing Date :	2023/1/2	Code	FROM STA :	520+500	TO STA :	522+000
Location :	520+500	CA-Emb-38				
NAME COMPANY	Cairo		Material :	embankment		

- : Test Results


Compaction % for Mold	
Mold No.	55
Mold Vol. (cm ³)	2151
Mold WT. (gm)	15700
Mold WT. + Wet WT. (gm)	20261
Wet WT. (gm)	4561
Wet Density (g/cm ³)	2.120
Dry Density (g/cm ³)	2.119
Proctor Density (g/cm ³)	2.149
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	5
Tare WT. (gm)	31
Tare WT. +Wet WT. (gm)	212
Tare WT. +Dry WT. (gm)	200.3
Water WT. (gm)	11.7
Dry WT. (gm)	169.3
Moisture Content %	6.9%

Swelling	
Mold No.	55
Date	2023/1/3
Intial Height (mm)	2.10
Final Height (mm)	2.10
Difference	0
Sample Height (mm)	121.00
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (kg)	58.00	170.00	280.00	401.00	520.00	655.00	800.00	930.00	1290.00
Load (KN)	0.6	1.7	2.7	3.9	5.1	6.4	7.8	9.1	12.6



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	3.93	13.4	29.4%	99	98	29.1%
5.00	9.11	20.0	45.5%			45.1%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :


Sign :

Consultant Engineer

Name :

Sign :

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel	<i>Abdelrahman Adel</i>	5-1-2023							
Contractor reference	CA-EMB-39									
Received by ER	<i>[Signature]</i>	MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		


Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	520+795	520+800	-9		
	520+800	520+900	-9.5		
	521+320	521+415	-6		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	1-1-2023	
2	Classification	m ³	5000	1-1-2023	
3	Proctor & O.m.c	m ³	5000	1-1-2023	
4	L.L & P.L & PI	m ³	5000	1-1-2023	
5	C.B.R	m ³	5000	5-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed	<i>Ahmed mohammed</i>	5/1/2023	A
QA/QC *	<i>Abdelkhalik SHAW</i>	<i>Abdelkhalik</i>	5/1/2023	<i>[Signature]</i>
GARB**	<i>Hussien Fouad</i>	<i>[Signature]</i>	5/1/2023	<i>[Signature]</i>
Comments by	<i>fill quantity approved with QCs</i>			
Employers Representative	<i>Mohamed Ahmed</i>	<i>[Signature]</i>	8-2-23	<i>AWC</i>

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		5-1-2023	
Contractor Reference	CA-Emb-39			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	14.9%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.4%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	50%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		5/1/2023	A
Contractor QA/QC *	Hassan		5/1/2023	A
GARB**	Hussien Fouad		5/1/2023	A
Employers Representative	Mohamed Ahmed		15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 القطار السريع Electric Express Train SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	 الهيئة القومية للإزقة الهيئة العامة للنقل واللوجستيات (CAST)
Opreating Lab	AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	1-1-2023	Code	ZONE	520+500	522+000
LOCATION	K.P. (521+000)	CA-Emb-39			
NAME COMPANY	At Kahera				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		24732.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1252.0	1652.0	2232.0	2423.0	2752.0	2852.0	2162.0		PRO	A-1-a
Cumulative Retained (g)	1252.0	2904.0	5136.0	7559.0	10311.0	13163.0	15325.0			2.16
Cumulative Retained %	5.1	11.7	20.8	30.6	41.7	53.2	62.0		WC	6.80
Cumulative Passing %	94.9	88.3	79.2	69.4	58.3	46.8	38.0		CBR	50.00


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	83.40	184.00	304.00					
Cumulative Retained %	16.68	36.80	60.80					
Cumulative Passing %	83.32	63.20	39.20					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.9	88.3	79.2	69.4	58.3	46.8	38.0	31.7	24.0	14.9

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Hassan
5/1/2023



		Electric Express Train - HSR		
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSА MATROUH		
From Station 504+000 To Station 568+177				

PROCTOR TEST


TESTING DATE:	1-1-2023	code			
LOCATION	K.P (521+000)		ZONE	520+500	522+000
NAME COMPANY	المشرفة للطرق والإنشاءات ب. ق. ٥٤٦ - ٥٤٣ - ٥٤٥	CA-6mb-39			

Weight of empty mold :	6070.0
Mold Volume:	2113.0


MAX Dry Density	2.16
Water content %	6.4

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10452.0	10658.0	10932.0	10852	
WT. WET SOIL	4382.0	4588.0	4862.0	4782.0	
Wt. Density	2.074	2.171	2.301	2.263	

Tare No.	7	10	4	11	17	45	18	33		
Tare wt.	42.9	43.9	59.5	46.4	59.9	41.3	77.8	73.6		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.5	147.2	145.9	145.2	144.5	143.4	143.6	143.3		
Wt. Of water	2.5	2.8	4.1	4.8	5.5	6.6	6.4	6.7		
Wt. Of dry soil	104.6	103.3	86.4	98.8	84.6	102.1	65.8	69.7		
Water content %	2.4%	2.7%	4.7%	4.9%	6.5%	6.5%	9.7%	9.6%		
AV. Water content %	2.6%		4.8%		6.5%		9.7%			
Dry Density	2.022		2.072		2.161		2.064			



Contractor



Consultant

Handwritten signature: 2023 Hasser



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أحمد خالد قنديل	 SUSTRA شركة سوسترا مصر	Electric Express Train - HSR	 الهيئة العامة للنقل وزارة النقل والاقتصاد السعودية
---	---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	5-1-2023	Code	FROM STA :	520+500	522+000
Location :	K.P (521+000)	CA-Emb-39			
Company Name	Al Kahera				

Test Results :-


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2168
Mold WT. (gm)	5082
Mold WT. + Wet WT. (gm)	10050
Wet WT. (gm)	4968
Wet Density (g/cm ³)	2.292
Dry Density (g/cm ³)	2.155
Proctor Density (g/cm ³)	2.160
Compaction %	100

Moisture Ratio After Compacted Mold	
Tare No.	32
Tare WT. (gm)	74.4
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	145.5
Water WT. (gm)	4.5
Dry WT. (gm)	71.1
Moisture Content %	6.3

Swelling	
Mold No.	2
Date	5-1-2023
Initial Height (mm)	7.00
Final Height (mm)	7.10
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.1%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.07	0.12	0.17	0.22	0.27	0.31	0.34	0.43
Load (KN)	0.9	2.1	3.6	5.1	6.6	8.1	9.3	10.2	12.9



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR عند نسبة 98 %
2.50	5.10	13.4	38.2%	100	98	37.5%
5.00	10.20	20.0	50.9%			50.0%

Lab. Specialist	Lab. Engineer	Consultant Engineer
Name :	Name :	Name : Hasan
Sign :	Sign :	Sign :



MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name Eng/ Abdelrahman Adel	Sign 	Date 5-1-2023	Time																
Contractor reference	CA-Emb-40																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From 521+415 521+760 521+140	To 521+440 521+900 521+300	Fill -6 -5.5 -6.5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	1-1-2023	
2	Classification	m ³	5000	1-1-2023	
3	Proctor & O.m.c	m ³	5000	1-1-2023	
4	L.L & P.L & PI	m ³	5000	1-1-2023	
5	C.B.R	m ³	5000	5-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed	Ahmed mohammed	5/1/2023	A	
QA/QC *	Abdullah Sany	Abdullah Sany	5/1/2023	A	
GARB**	Hussien Fouad	Hussien Fouad	5/1/2023	A	
Comments by	Ritwaty appal with Os				
Employers Representative	Mohamed Ali	Mohamed Ali	8-2-23		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		5-1-2023	
Contractor Reference	CA-EMB-40			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.2%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.5%	
6	ASTM D 1557	Modified proctor	2.14	
7	ASTM D 1883	CBR	54.1%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		5/1/2023	A
Contractor QA/QC *	Hassan		5/1/2023	A
GARB**	Hussien Fouad		5/1/2023	A
Employers Representative	Mo hamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي د. خالد قنديل	 SYSTRA SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	 الهيئة القومية للإنتفاخ القوي والسكك الحديدية (EG.R.T)
Opreating Lab	AL Nuby Central Lab		

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	1-1-2023	Code	ZONE	520+500	522+000
LOCATION	K.P (521+500)	CA-Emb-40			
NAME COMPANY	Al Kahera				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		23707.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1325.0	1541.0	1875.0	2280.0	2145.0	2390.0	2252.0		A-1-a 2.14 7.50 54.10	
Cumulative Retained (g)	1325.0	2866.0	4741.0	7021.0	9166.0	11556.0	13808.0			
Cumulative Retained %	5.6	12.1	20.0	29.6	38.7	48.7	58.2			
Cumulative Passing %	94.4	87.9	80.0	70.4	61.3	51.3	41.8			
									PRO	2.14
									WC	7.50
									CBR	54.10


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	93.80	230.00	341.60					
Cumulative Retained %	18.76	46.00	68.32					
Cumulative Passing %	81.24	54.00	31.68					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.4	87.9	80.0	70.4	61.3	51.3	41.8	33.9	22.5	13.2

ATTERBERG LIMTS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Handwritten signature and date: 5/1/2023



 	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSА MATROUH From Station 504+000 To Station 568+177		

PROCTOR TEST


TESTING DATE:	1-1-2023	code			
LOCATION	K.P (521+500)		ZONE	520+500	522+000
NAME COMPANY	At Kahera	CA-Em6-40			

Weight of empty mold :	6037.0
Mold Volume:	2176.0


MAX Dry Density	2.16
Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10365.0	10752.0	11060.0	10685	
WT. WET SOIL	4328.0	4715.0	5023.0	4648.0	
Wt. Density	1.989	2.167	2.308	2.136	

Tare No.	10	7	16	15	17	90	11	26		
Tare wt.	43.7	42.9	33.1	31.4	59.6	62.4	46.6	54.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.2	147.5	144.3	144.1	144.2	144.3	141.3	142.6		
Wt. Of water	2.8	2.5	5.7	5.9	5.8	5.7	8.7	7.4		
Wt. Of dry soil	103.5	104.6	111.2	112.7	84.6	81.9	94.7	87.7		
Water content %	2.7%	2.4%	5.1%	5.2%	6.9%	7.0%	9.2%	8.4%		
AV. Water content %	2.5%		5.2%		6.9%		8.8%			
Dry Density	1.940		2.060		2.159		1.963			



Contractor



Consultant



 KK ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي د. خالد قنديل	Electric Express Train - IHSR	 وزارة النقل والبنى التحتية (KASBL)  الهيئة العامة للإحصاء
---	--------------------------------------	--

California Bearing Ratio TEST

Testing Date :	5-1-2023	Code	FROM STA :	520+500	522+000
Location :	K.P (S21+S00)	CA-Emb-up			
Company Name	Al-Kalhera				

Test Results :-


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9830
Wet WT. (gm)	4930
Wet Density (g/cm ³)	2.304
Dry Density (g/cm ³)	2.148
Proctor Density (g/cm ³)	2.140
Compaction %	100

Moisture Ratio After Compacted Mold	
Tare No.	15
Tare WT. (gm)	31.9
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	142
Water WT. (gm)	8.0
Dry WT. (gm)	110.1
Moisture Content %	7.3

Swelling	
Mold No.	4
Date	5-1-2023
Initial Height (mm)	5.15
Final Height (mm)	5.15
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.1%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.04	0.08	0.14	0.19	0.24	0.28	0.33	0.37	0.48
Load (KN)	1.2	2.4	4.2	5.7	7.2	8.4	9.9	11.1	14.4



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR عند نسبة 98 %
2.50	5.70	13.4	42.7%	100	98	41.7%
5.00	11.10	20.0	55.4%			54.1%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Hassa Sign :
--	--	---



Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K																				
Issued by Contractor	Name	Sign	Date	Time																					
	Eng/ Abdelrahman Adel		5-1-2023																						
Contractor reference	CA - Emb-41																								
Received by ER		MIR	<table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <tr> <td style="width: 5%;">C1</td> <td style="width: 5%;">C2</td> <td style="width: 5%;">C3</td> <td style="width: 5%;">DD</td> <td style="width: 5%;">MM</td> <td style="width: 5%;">YY</td> <td style="width: 5%;">HH</td> <td style="width: 5%;">MM</td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>							C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM																		

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+300	521+320	-6.5		
	521+560	521+760	-5.5		
	520+900	521+000	-8.5		
521+440	521+560	-5.5			
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m³	5000	1-1-2023	
2	Classification	m³	5000	1-1-2023	
3	Proctor & O.m.c	m³	5000	1-1-2023	
4	L.L & P.L & PI	m³	5000	1-1-2023	
5	C.B.R	m³	5000	5-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		5/1/2023	A	
QA/QC *	Abdallah SAMY		5/1/2023	A	
GARB**	Hussien Fouad		5/1/2023	A	
Comments by	Bill quantity approval with Qs				
Employers Representative	Mohamed Ali		8-2-23		

* Designer
 ** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name ENG/ Abdelrahman Adel	Sign 	Date 5-1-2023	Time															
Contractor Reference	CA-646-41																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.6%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	57.5%	
Comments by:		Comments by:		
		All test under Responsibility third Party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel		5/1/2023	A
Contractor QA/QC *	Hassan		5/1/2023	A
GARB**	Hussien Fouad		5/1/2023	A
Employers Representative	Mohd Ahs		15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SYSTRA	Electric Express Train - HSR		 الهيئة القومية للإتفاق للمواصلات القاهرة
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	1-1-2023	Code			
LOCATION	K.P (521+500)	CA-Emb-41	ZONE	520+500	522+000
NAME COMPANY	At Kahera				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		26916.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	1456.0	1821.0	2452.0	2654.0	2852.0	2984.0	2301.0		A-1-a
Cumulative Retained (g)	1456.0	3277.0	5729.0	8383.0	11235.0	14219.0	16520.0	PRO	2.16
Cumulative Retained %	5.4	12.2	21.3	31.1	41.7	52.8	61.4	WC	6.80
Cumulative Passing %	94.6	87.8	78.7	68.9	58.3	47.2	38.6	CBR	57.50


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	132.20	257.50	350.00					
Cumulative Retained %	26.44	51.50	70.00					
Cumulative Passing %	73.56	48.50	30.00					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.6	87.8	78.7	68.9	58.3	47.2	38.6	28.4	18.7	11.6

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Handwritten signature: Hassan



	Electric Express Train - HSR		
	From El Ain El Sokhna City To El Alamein - MATROUH		
	Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177			

PROCTOR TEST


TESTING DATE:	1-4-2023	code			
LOCATION	K.P (521+000)		ZONE	520+500	522+000
NAME COMPANY	Al Kahera	CA-Emb-41			

Weight of empty mold :	6190.0
Mold Volume:	2169.0

MAX Dry Density	2.17
Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10752.0	11023.0	11215.0	10960	
WT. WET SOIL	4562.0	4833.0	5025.0	4770.0	
Wt. Density	2.103	2.228	2.317	2.199	


Tare No.	40	16	20	19	22	33	34	45		
Tare wt.	46.4	33.9	60.9	44.4	54.1	73.6	70.2	41.5		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	148.0	147.5	145.0	146.3	145.0	144.0	142.0	143.0		
Wt. Of water	2.0	2.5	5.0	3.7	5.0	6.0	8.0	7.0		
Wt. Of dry soil	101.6	113.6	84.1	101.9	90.9	70.4	71.8	101.5		
Water content %	2.0%	2.2%	5.9%	3.6%	5.5%	8.5%	11.1%	6.9%		
AV. Water content %	2.1%		4.8%		7.0%		9.0%			
Dry Density	2.060		2.126		2.165		2.017			



Lab. Engineer

Name :

Sign :



Consultant Engineer

Name :

Hassan



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د خالد قنديل	 SVSRA	Electric Express Train - HSR	 الهيئة العامة للنقل وزارة النقل والبنية التحتية (GABRI)
--	--	-------------------------------------	--

California Bearing Ratio TEST

Testing Date :	5-1-2023	Code	FROM STA :	520+500	522+000
Location :	K.P (521+500)	CA-Emb-41			
Company Name	Al Kahera				

Test Results :-


Compaction % for Mold	
Mold No.	1
Mold Vol. (cm ³)	2158
Mold WT. (gm)	4890
Mold WT. + Wet WT. (gm)	9850
Wet WT. (gm)	4960
Wet Density (g/cm ³)	2.298
Dry Density (g/cm ³)	2.152
Proctor Density (g/cm ³)	2.160
Compaction %	100

Moisture Ratio After Compacted Mold	
Tare No.	16
Tare WT. (gm)	33.9
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	142.6
Water WT. (gm)	7.4
Dry WT. (gm)	108.7
Moisture Content %	6.8

Swelling	
Mold No.	1
Date	5-1-2023
Initial Height (mm)	6.00
Final Height (mm)	6.10
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.1%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.05	0.10	0.16	0.21	0.25	0.30	0.35	0.39	0.49
Load (KN)	1.5	3.0	4.8	6.3	7.5	9.0	10.5	11.7	14.7



Calculations :-

Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	6.30	13.4	47.2%	100	98	46.4%
5.00	11.70	20.0	58.4%			57.5%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Hassan Sign :
--	--	---



MATERIAL INSPECTION REQUEST						

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K															
Issued by Contractor	Name	Sign	Date	Time															
	Eng/ Abdelrahman Adel		8-1-2023																
Contractor reference	CA-8mb-42																		
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From 521+900 520+800	To 522+000 520+900	Fill -6 -9		
MAR Approval No			Date		
Supplier Name					
Test Requirement	Specification		Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	4-1-2023	
2	Classification	m ³	5000	4-1-2023	
3	Proctor & O.m.c	m ³	5000	4-1-2023	
4	L.L & P.L & PI	m ³	5000	4-1-2023	
5	C.B.R	m ³	5000	8-1-2023	
Comments by:		Comments by:			
A sample has been taken from fill material by K.K office to (El Nuby laboratory) and the results founded meet the specifications and accepted.		Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed	Ahmed mohammed	8/1/2023	A
QA/QC *	Abdallah SAMY	Abdallah	8/1/2023	A
GARB**	Hussien Fouad	Laf	8/1/2023	A
Comments by	Rinkantaty approval with Qs			
Employers Representative	Mohamed Ahmed		8-2-23	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



الهيئة العامة
للتنظيم والرقابة
(GARBLT)



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		8-1-2023	
Contractor Reference	CA-Emb-42			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (521+000) No (2)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.1%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	57.4%	
Comments by:		Comments by:		
		All test under Responsibility Third party.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Ali		8/1/2023	A
Contractor QA/QC *	Hassan		8/1/2023	A
GARB**	Hussien Fouad		8/1/2023	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SYSTRA SHAKER	Electric Express Train - HSR		 الهيئة القومية للإنفاق مصر
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA To MARS MATROUH		
From Station 504+000 To Station 568+177				
Opreating Lab	AL Nuby Central Lab			

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	4-1-2023	Code			
LOCATION	K.P (521+000)	CA-Emb-42	ZONE	520+500	522+000
NAME COMPANY	Al Kahera				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		27066.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	1542.0	1895.0	2550.0	3265.0	3152.0	2895.0	2956.0		A-1-a	
Cumulative Retained (g)	1542.0	3437.0	5987.0	9252.0	12404.0	15299.0	18255.0		PRO	2.17
Cumulative Retained %	5.7	12.7	22.1	34.2	45.8	56.5	67.4		WC	6.80
Cumulative Passing %	94.3	87.3	77.9	65.8	54.2	43.5	32.6		CBR	57.40

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	85.60	218.00	330.00					
Cumulative Retained %	17.12	43.60	66.00					
Cumulative Passing %	82.88	56.40	34.00					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	94.3	87.3	77.9	65.8	54.2	43.5	32.6	27.0	18.4	11.1

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.L	N.P	N.P.I

Contractor

Consultant



Handwritten signature and date: 8/1/2023



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 مصر القطار السريع EGYPT SHAKER	Electric Express Train - HSR		 الهيئة العامة للنقل الميناء مصر الهيئة العامة للنقل مصر الهيئة العامة للنقل مصر
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSALA MATROUH		
From Station 504+000 To Station 568+177				


PROCTOR TEST

TESTING DATE:	4-1-2023	code			
LOCATION	K.P (521+000)		ZONE	520+500	522+000
NAME COMPANY	Al Kahera	CA-Emb-42			

Weight of empty mold :	6190.0	MAX Dry Density	2.17
Mold Volume:	2169.0	Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10752.0	11023.0	11215.0	10960	
WT. WET SOIL	4562.0	4833.0	5025.0	4770.0	
Wt. Density	2.103	2.228	2.317	2.199	

Tare No.	40	16	20	19	22	33	34	45		
Tare wt.	46.4	33.9	60.9	44.4	54.1	73.6	70.2	41.5		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	148.0	147.5	145.0	146.3	145.0	144.0	142.0	143.0		
Wt. Of water	2.0	2.5	5.0	3.7	5.0	6.0	8.0	7.0		
Wt. Of dry soil	101.6	113.6	84.1	101.9	90.9	70.4	71.8	101.5		
Water content %	2.0%	2.2%	5.9%	3.6%	5.5%	8.5%	11.1%	6.9%		
AV. Water content %	2.1%	4.8%	7.0%	9.0%						
Dry Density	2.060	2.126	2.165	2.017						



Lab. Engineer

Name :

Sign :



Consultant Engineer

Name :

Sign :



Electric Express Train - HSR

California Bearing Ratio TEST

Testing Date :	8-1-2023	Code	FROM STA :	520+500	522+000
Location :	K.P (521+000)	CA-6m6-42			
Company Name	Al Kallera				

Test Results :-


Compaction % for Mold	
Mold No.	5
Mold Vol. (cm ³)	2122
Mold WT. (gm)	4803
Mold WT. + Wet WT. (gm)	9701
Wet WT. (gm)	4898
Wet Density (g/cm ³)	2.308
Dry Density (g/cm ³)	2.163
Proctor Density (g/cm ³)	2.170
Compaction %	109

Moisture Ratio After Compacted Mold	
Tare No.	8
Tare WT. (gm)	46.8
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	143.5
Water WT. (gm)	6.5
Dry WT. (gm)	96.7
Moisture Content %	6.7

Swelling	
Mold No.	5
Date	8-1-2023
Initial Height (mm)	4.00
Final Height (mm)	4.10
Difference	0
Sample Height (mm)	120.00
Swelling Ratio %	0.1%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.05	0.09	0.15	0.21	0.27	0.31	0.35	0.39	0.49
Load (KN)	1.5	2.7	4.5	6.3	8.1	9.3	10.5	11.7	14.7




Calculations :-




Penteration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR عند نسبة 98 %
2.50	6.30	13.4	47.2%	100	98	46.4%
5.00	11.70	20.0	58.4%			57.4%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : <i>Hasra</i> Sign :
--	--	---

MATERIAL INSPECTION REQUEST	    					

Contractor Company	Cairo for Roads and construction Company			Designer Company	K.K					
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		8/1/2023							
Contractor reference	CA-Emb-43									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment FILL MATERIAL RESULTS						
Location to be Used	From	To	Fill				
	521+000	521+080	-7.5				
	521+320	521+440	-5.5				
	520+700	520+790	-8.5				
MAR Approval No				Date			
Supplier Name							
Test Requirement				Specification	Clause		
Reference Photos	Yes attached / No			Other			
Item	Description	Unit	Quantity	Arrival Date	Note		
1	Sieve analysis	m ³	5000	4-1-2023			
2	Classification	m ³	5000	4-1-2023			
3	Proctor & O.m.c	m ³	5000	4-1-2023			
4	L.L & P.L & PI	m ³	5000	4-1-2023			
5	C.B.R	m ³	5000	8-1-2023			
Comments by:			Comments by:				
A sample has been taken from fill material by K.K office to (Gomaa bader laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3				
APPROVAL STATUS							
Organisation	Name	Sign	Date	A-AWC-R			
Contractor	Eng / Ahmed mohammed		8-1-2023	A			
QA/QC *	Abdallah SANY		8-1-2023	A			
GARB**	Hussien Fouad		8-1-2023	A			
Comments by	fill quantity approval with G.S		8-1-2023	A			
Employers Representative	Mohamed Ali		8-2-23				

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name ENG/ Abdelrahman Adel	Sign 	Date 8/1/2023	Time
Contractor Reference	CA-Emb-43			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.9%	
4	ASTM D 4318	Atterberg limit	19.6%	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	61%	
Comments by:		Comments by:		
		All test under Responsibility Thir d party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Adel	Abdelrahman	8-1-2023	A
Contractor QA/QC *	Hassan		8-1-2023	A
GARB**	Hussien Fouad		8-1-2023	A
Employers Representative	Mohd Ahs		15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

Testing Date :	4/11/2023	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-43	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		19322.00		gm	table classify
sieve size	2	1 1/2	1	3/4	1/2	3/8	# 4	PASS	soil classify
(g)Mass retained	226.0	3870.0	4809.0	1510.0	1118.0	706.0	1275.0		A-1-a
g)Cumulative Retained	226.0	4096.0	8905.0	10415.0	11533.0	12239.0	13514.0	PRO	2.15
Cumulative Retained %	1.2	21.2	46.1	53.9	59.7	63.3	69.9	WC	6.8%
Cumulative Passing %	98.8	78.8	53.9	46.1	40.3	36.7	30.1	CBR	61%

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
(g)Cumulative Retained	87.38	286.16	302.36					
Cumulative Retained %	17.48	57.23	60.47					
Cumulative Passing %	82.52	42.77	39.53					

C-General gradient										
(in)sieve size	5	4.0	3	1 1/2	3/4	3/8	# 4	# 10	# 40	# 200
(mm)sieve size	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	98.8	78.8	53.9	46.1	40.3	36.7	30.1	24.8	12.9	11.9

ATTERBERG LIMITS	(.L.L)LIQUID LIMIT	(.P.L)PLASTIC LIMIT	(.P.I)PLASTIC INDEX
	24.8%	19.6%	5.2%

Contractor

Operated by

Consultant

Gomaa Bader Lab


 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SVSTA B SHAKER	Electric Express Train - HSR	 الهيئة العامة للنقل م.د. خالد قنديل
---	---	-------------------------------------	---

Plasticity and Liquidity Test -Atterberg Limits

Testing Date :	4/1/2023	Code	ZONE	520+500	522+000
Location :	KP:521+000	CA-Emb-43	Material	fill material layer	
Name Company	cairo company		quantity	5000 m3	

Testing Results :-


Test	Liquid Limit				Plastic Limit	
No. of Ticks	34	29	24	17	-	-
Tare No.	46	23	5	2	G	H
Tare WT. (gm)	27.13	25.17	27.41	27.30	13.35	11.16
Tare WT. + Wet WT. (gm)	52.03	43.52	45.00	46.36	14.03	12.00
Tare WT. + Dry WT. (gm)	47.50	40.05	41.42	42.31	13.92	11.86
Water WT. (gm)	4.53	3.47	3.58	4.05	0.11	0.14
Dry WT. (gm)	20.37	14.88	14.01	15.01	0.57	0.70
Moisture Content %	22.2%	23.3%	25.5%	27.0%	19.3%	20.0%
Average %					19.6%	



LL	P.L	P.I
24.8%	19.6%	5.2%

Lab. Specialist	Lab. Engineer	Consultant Engineer
-----------------	---------------	---------------------

Name : 
 Sign : 

Name :
 Sign : 

Name : 
 Sign : 


PROCTOR TEST

Testing Date :	5/1/2023	Code	ZONE	520+500	522+000
Location :	KP:521+000		Material	fill material layer	
Name Company	cairo company	CA-Emb-43	quantity	5000 m3	

Weight of empty mold :	6430.0	MAX Dry Density	2.150
Mold Volume:	2104.9	Water content %	6.80

trial no :	1	2	3	4		
Wt. Of Mold+ wet soil	10863.0	11064.0	11264.0	11134		
WT. WET SOIL	4433.0	4634.0	4834.0	4704.0		
Wt. Density	2.106	2.202	2.297	2.235		

Tare No.	11	11	46	46	7	7	10	10				
Tare wt.	24.61	24.61	26.64	26.64	27.46	27.46	26.63	26.63				
Wt. Of wet soil & tare	146.3	146.3	134.6	134.6	157.6	157.6	136.6	136.6				
Wt. Of dry soil & tare	143.13	143.13	129.64	129.64	149.31	149.31	127.23	127.23				
Wt. Of water	3.2	3.2	5.0	5.0	8.3	8.3	9.4	9.4				
Wt. Of dry soil	118.5	118.5	103.0	103.0	121.9	121.9	100.6	100.6				
Water content %	2.7%	2.7%	4.9%	4.9%	6.8%	6.8%	9.3%	9.3%				
AV. Water content %	2.7%		4.9%		6.8%		9.3%					
Dry Density	2.051		2.100		2.150		2.044					



Contractor

Consultant

مشروع القطار السريع
القطاع المركزي
معمل المركزي
(رقم 6)

مختبر الطرق والإنشاءات
107405
2023-01-05

المكتب
الاستشاري الهندسي
أ. د. خالد قنديل

Electric Express Train - HSR

California Bearing Ratio TEST

Testing Date :	8/1/2023	Code	ZONE	520+500	522+000
Location :	KP:521+000	Material	fill material layer		
Name Company	cairo company	quantity	5000 m3		

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2177.5
Mold WT. (gm)	16444
Mold WT. + Wet WT. (gm)	21356
Wet WT. (gm)	4912
Wet Density (g/cm ³)	2.256
Dry Density (g/cm ³)	2.125
Proctor Density (g/cm ³)	2.150
Compaction %	99

Moisture Ratio After Compacted Mold	
Tare No.	11
Tare WT. (gm)	24.23
Tare WT. +Wet WT. (gm)	136.64
Tare WT. +Dry WT. (gm)	130.13
Water WT. (gm)	6.5
Dry WT. (gm)	105.9
Moisture Content %	6.1

Swelling	
Mold No.	
Date	8/4/2023
Initial Height (mm)	4.0
Final Height (mm)	4.0
Difference	0.0
Sample Height (mm)	11.9
Swelling Ratio %	0.0%

Loading Reading :

(mm)Penteration	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
(mm)Load Reading	98	189	346	510	645	806	1011	1246	1534
(KN)Load	1.0	1.9	3.4	5.0	6.3	7.9	9.9	12.2	15.0



Calculations :-

Penteration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	100 عند نسبة 100
2.50	5.00	13.4	37.4%	99	100	37.9%
5.00	12.21	20.0	61.0%			61.7%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Consultant Engineer

Name :

Sign :

مشروع القطار السريع
القطاع السابع
معمل المركزي
(رقم 6)

المكتب
الاستشاري الهندسي
أ.د. خالد قنديل

MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		13/1/2023							
Contractor reference	CA-Emb-44									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	From and middle embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	520+790	520+800	-8.5			
	520+620	520+700	-8.5			
	521+440	521+560	-5			
	521+140	521+155	-6			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	9-1-2023		
2	Classification	m ³	5000	4-1-2023		
3	Proctor & O.m.c	m ³	5000	4-1-2023		
4	L.L & P.L & PI	m ³	5000	4-1-2023		
5	C.B.R	m ³	5000	13-1-2023		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		13-1-2023	A		
QA/QC *	Hassan		13-1-2023	A		
GARB**	Hussien Fouad		13-1-2023	A		
Comments by	Final quality approved with Qs			13-1-2023	A	
Employers Representative	Mohamed Ahsa		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company																
Electric express train	Cairo for Roads and construction Company		k.k																
Issued by Contractor	Name	Sign	Date	Time															
	ENG/ Abdelrahman Adel		13/1/2023																
Contractor Reference	C.A-Emb-44																		
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower and middle embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	9.62%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.5%	
6	ASTM D 1557	Modified proctor	2.15	
7	ASTM D 1883	CBR	55.8%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		13-1-2023	
Contractor QA/QC *	Hassan		13-1-2023	
GARB**	Hussien Fouad		13-1-2023	A
Employers Representative	M. H. A. M. A.		15-1-2023	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSA MATROUH
 From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	09/01/2023	code			
LOCATION	K.P 520+000	CA-Emb-49	ZONE	520+500	522+000
NAME COMPANY	cairo company				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		22335.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	0.0	3261.0	3362.0	3261.0	2685.0	2212.0	1822.0		A-1-a	
Cumulative Retained (g)	0.0	3261.0	6623.0	9884.0	12569.0	14781.0	16603.0		PRO	2.15
Cumulative Retained %	0.0	14.6	29.7	44.3	56.3	66.2	74.3		WC	6.50
Cumulative Passing %	100.0	85.4	70.3	55.7	43.7	33.8	25.7		CBR	55.80



B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	89.10	206.20	312.50					
Cumulative Retained %	17.82	41.24	62.50					
Cumulative Passing %	82.18	58.76	37.50					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.40	70.35	55.75	43.73	33.82	25.66	21.09	15.08	9.62

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant




PROCTOR TEST

TESTING DATE:	2023/01/10	code	ZONE	520+500	522+000
LOCATION	K.P 520+500	CA-Emb-yu			
NAME COMPANY	cairo company				

Weight of empty mold :	6190.0
Mold Volume:	2169.0

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10712.0	10967.0	11181.0	10856	
WT. WET SOIL	4522.0	4777.0	4991.0	4666.0	
Wt. Density	2.085	2.202	2.301	2.151	

Tare No.	7	18	35	11	22	16	20	10		
Tare wt.	42.8	77.8	73.9	46.1	54.1	34	60.9	43.7		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.6	148.4	146.8	145.4	143.6	142.4	142.0	141.1		
Wt. Of water	2.4	1.6	3.2	4.6	6.4	7.6	8.0	8.9		
Wt. Of dry soil	104.8	70.6	72.9	99.3	89.5	108.4	81.1	97.4		
Water content %	2.3%	2.3%	4.4%	4.6%	7.2%	7.0%	9.9%	9.1%		
AV. Water content %	2.3%		4.5%		7.1%		9.5%			
Dry Density	2.038		2.107		2.149		1.965			



Consultant

 	Electric Express Train - HSR	
---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	13/1/2023	Code	FROM STA :	520+500	522+000
Location :	K.P 520+500	CA-Emb-44			
Company Name	CAIRO ROADS				

:- Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	6075
Mold WT. + Wet WT. (gm)	10912
Wet WT. (gm)	4837
Wet Density (g/cm ³)	2.279
Dry Density (g/cm ³)	2.146
Proctor Density (g/cm ³)	2.150
Compaction %	99.8

Moisture Ratio After Compacted Mold	
Tare No.	22
Tare WT. (gm)	54.1
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	144.4
Water WT. (gm)	5.6
Dry WT. (gm)	90.3
Moisture Content %	6.2

Swelling	
Mold No.	6
Date	13/1/2023
Initial Height (mm)	2.60
Final Height (mm)	2.60
Difference	0
Sample Height (mm)	119.00
Swelling Ratio %	0%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.08	0.14	0.19	0.24	0.29	0.34	0.38	0.45
Load (KN)	0.9	2.4	4.2	5.7	7.2	8.7	10.2	11.4	13.5



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR (%)
2.50	5.70	13.4	42.7%	100	98	41.9%
5.00	11.40	20.0	56.9%			55.9%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec-7 Naka - Matroah

Consultant Engineer

Name :

Sign :

مهندس
البنية التحتية
د.ع. خالد قنديل

MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		13-1-2023																	
Contractor reference	CA-Emb-45																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower embankment FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+155	521+320	-6		
	521+900	522+000	-5.5		
	520+900	520+930	-8		
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification	Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	9-1-2023	
2	Classification	m ³	5000	9-1-2023	
3	Proctor & O.m.c	m ³	5000	9-1-2023	
4	L.L & P.L & PI	m ³	5000	9-1-2023	
5	C.B.R	m ³	5000	13-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	eng / Ahmed Mohammed		13/1/2023	A	
QA/QC *	Hassan		13/1/2023		
GARB**	Hussien Fouad		13/1/2023		
Comments by	fill quantity approved with Co				
Employers Representative	Mohamed Ahmed		8-2-25		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel		13-1-2023	
Contractor Reference	CA-Emb-45			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.23%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.14	
7	ASTM D 1883	CBR	56.2%	
Comments by:		Comments by:		
		All test under Responsibility Third Party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman	13/1/2023	A
Contractor QA/QC *	Hassan		13/1/2023	A
GARB**	Hussien Fouad		13/1/2023	
Employers Representative	Mohamed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARS MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	09/01/2023	code			
LOCATION	K.P 520+500		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-45			

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		25991.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	3751.0	3576.0	3361.0	2957.0	2616.0	2018.0		A-1-a
Cumulative Retained (g)	0.0	3751.0	7327.0	10688.0	13645.0	16261.0	18279.0	PRO	2.14
Cumulative Retained %	0.0	14.4	28.2	41.1	52.5	62.6	70.3	WC	7.00
Cumulative Passing %	100.0	85.6	71.8	58.9	47.5	37.4	29.7	CBR	56.20



B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	76.80	169.60	277.00					
Cumulative Retained %	15.36	33.92	55.40					
Cumulative Passing %	84.64	66.08	44.60					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.57	71.81	58.88	47.50	37.44	29.67	25.11	19.61	13.23

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant



 	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSА MATROUH From Station 504+000 To Station 568+177		


PROCTOR TEST

TESTING DATE:	2023/01/10	code			
LOCATION	K.P. 520+500		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-45			

Weight of empty mold :	6070.0	MAX Dry Density	2.14
Mold Volume:	2113.0	Water content %	7

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10485.0	10641.0	10919.0	10742	
WT. WET SOIL	4415.0	4571.0	4849.0	4672.0	
Wt. Density	2.089	2.163	2.295	2.211	

Tare No.	25	10	7	8	21	22	16	40		
Tare wt.	75.8	43.7	42.8	46.8	55.2	54.1	34	46.4		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.9	147.5	145.9	145.5	143.5	143.6	140.2	141.1		
Wt. Of water	2.1	2.5	4.1	4.5	6.5	6.4	9.8	8.9		
Wt. Of dry soil	72.1	103.8	103.1	98.7	88.3	89.5	106.2	94.7		
Water content %	2.9%	2.4%	4.0%	4.6%	7.4%	7.2%	9.2%	9.4%		
AV. Water content %	2.7%		4.3%		7.3%		9.3%			
Dry Density	2.035		2.075		2.140		2.023			



Contractor

م.م. خالد قنديل



Consultant

Abd-8AE

California Bearing Ratio TEST

Testing Date :	13/1/2023	Code		FROM STA :	520+500	522+000
Location :	K.P 520+500	CA-Emb-45				
Company Name	cairo company					

Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2158
Mold WT. (gm)	4890
Mold WT. + Wet WT. (gm)	9789
Wet WT. (gm)	4899
Wet Density (g/cm ³)	2.270
Dry Density (g/cm ³)	2.125
Proctor Density (g/cm ³)	2.140
Compaction %	99.3

Moisture Ratio After Compacted Mold	
Tare No.	10
Tare WT. (gm)	43.7
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	143.2
Water WT. (gm)	6.8
Dry WT. (gm)	99.5
Moisture Content %	6.8

Swelling	
Mold No.	4
Date	13/01/2023
Initial Height (mm)	2.60
Final Height (mm)	2.60
Difference	0
Sample Height (mm)	119.00
Swelling Ratio %	0%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.02	0.07	0.13	0.18	0.23	0.29	0.34	0.38	0.45
Load (KN)	0.6	2.1	3.9	5.4	6.9	8.7	10.2	11.4	13.5



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR
2.50	5.40	13.4	40.4%			98 عند نسبة 98
5.00	11.40	20.0	56.9%	99	98	39.9%
						56.2%

Lab. Specialist

Name :

Sign :

المختبر
لتنظيم والإدارة
أ. د. خالد قنديل

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
Sec 7 Fuka - Matrouh


Consultant Engineer

Name :



Sign :

المختبر
لتنظيم والإدارة
أ. د. خالد قنديل

MATERIAL INSPECTION REQUEST	    
	    

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		15-1-2023							
Contractor reference	CA-Emb-46									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower and middle embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	520+930	521+000	-8			
	521+560	521+700	-5			
	521+700	521+745	-5			
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	11-1-2023		
2	Classification	m ³	5000	11-1-2023		
3	Proctor & O.m.c	m ³	5000	11-1-2023		
4	L.L & P.L & PI	m ³	5000	11-1-2023		
5	C.B.R	m ³	5000	15-1-2023		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed Mohammed		15/1/2023	A		
QA/QC *	Abdallah SAEY		15/1/2023	A		
GARB**	Hussien Fouad		15/1/2023	A		
Comments by	Rel quantity approved with QCs					
Employers Representative	Mohamed Ahmed		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company			Designer Company						
Electric express train	Cairo for Roads and construction Company			k.k						
Issued by Contractor	Name	Sign	Date	Time						
	ENG/ Abdelrahman Adel		15-1-2023							
Contractor Reference	CA-Emb-46									
Received by ER		MAR	C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower and middle embankment Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	10.4%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	55.3%	
Comments by:			Comments by:	
			All test under Responsibility Third Party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		15/1/2023	A
Contractor QA/QC *	Hassan		15/1/2023	A
GARB**	Hussien Fouad		15/1/2023	A
Employers Representative	Mohamed Ahmed		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	10-1-2023	code			
LOCATION	K.P 520+440		ZONE	520+500	522+000
NAME COMPANY	cairo-company	CA-EM-6-46			

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		27939.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	3968.0	3859.0	3859.0	3565.0	2972.0	2521.0		A-1-a
Cumulative Retained (g)	0.0	3968.0	7827.0	11686.0	15251.0	18223.0	20744.0		PRO 2.16
Cumulative Retained %	0.0	14.2	28.0	41.8	54.6	65.2	74.2		WC 7.00
Cumulative Passing %	100.0	85.8	72.0	58.2	45.4	34.8	25.8		CBR 55.30


B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	95.50	203.60	298.00					
Cumulative Retained %	19.10	40.72	59.60					
Cumulative Passing %	80.90	59.28	40.40					

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.80	71.99	58.17	45.41	34.78	25.75	20.83	15.27	10.40

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant



	Electric Express Train - HSR		
	From El Ain El Sokhna City To El Alamein - MATROUH		
	Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177			

PROCTOR TEST


TESTING DATE:	2023/01/10	code			
LOCATION	K:P 520+500		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-6mb-46			

Weight of empty mold :	6190.0
Mold Volume:	2169.0

MAX Dry Density	2.16
Water content %	7

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10589.0	10814.0	11199.0	10911	
WT. WET SOIL	4399.0	4624.0	5009.0	4721.0	
Wt. Density	2.028	2.132	2.309	2.177	

Tare No.	8	15	26	18	10	35	32	17		
Tare wt.	46.8	31.9	55	77.7	43.7	73.9	74.4	59.5		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.9	147.5	145.9	146.6	143.1	144.9	143.2	142.1		
Wt. Of water	2.1	2.5	4.1	3.4	6.9	5.1	6.8	7.9		
Wt. Of dry soil	101.1	115.6	90.9	68.9	99.4	71.0	68.8	82.6		
Water content %	2.1%	2.2%	4.5%	4.9%	6.9%	7.2%	9.9%	9.6%		
AV. Water content %	2.1%		4.7%		7.1%		9.7%			
Dry Density	1.986		2.036		2.157		1.984			



Contractor

مكتب استشارات الهندسة
أ.م.م. محمد قنديل

Electric Express Train
Central Lab Number 4
Sec 7 Foka - Matrouh

Consultant

مكتب استشارات الهندسة
أ.م.م. محمد قنديل

 	Electric Express Train - HSR	 
---	-------------------------------------	---

California Bearing Ratio TEST


Testing Date :	14/1/2023	Code	FROM STA :	520+500	522+000
Location :	K.P.520+440	CA-Emb-46			
Company Name	cairo company				

- : Test Results

Compaction % for Mold		Moisture Ratio After Compacted Mold		Swelling	
Mold No.	5	Tare No.	11	Mold No.	5
Mold Vol. (cm ³)	2168	Tare WT. (gm)	46.1	Date	14/01/2023
Mold WT. (gm)	5075	Tare WT. +Wet WT. (gm)	150	Initial Height (mm)	7.40
Mold WT. + Wet WT. (gm)	9993	Tare WT. +Dry WT. (gm)	143.3	Final Height (mm)	7.40
Wet WT. (gm)	4918	Water WT. (gm)	6.7	Difference	0
Wet Density (g/cm ³)	2.268	Dry WT. (gm)	97.2	Sample Height (mm)	119.00
Dry Density (g/cm ³)	2.122	Moisture Content %	6.9	Swelling Ratio %	0%
Proctor Density (g/cm ³)	2.160				
Compaction %	98.2				

Loading Reading :

Penetration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.03	0.14	0.18	0.23	0.28	0.33	0.37	0.42
Load (KN)	0.9	2.4	4.2	5.4	6.9	8.4	9.9	11.1	12.6




Calculations :-

Penetration	Load	Standard Load	CBR	Mold - Compaction	Compaction	CBR
(mm)	(Kn)	(lb)	(%)	(%)	(%)	% عند نسبة 98
2.50	5.40	13.4	40.4%	98	98	40.3%
5.00	11.10	20.0	55.4%			55.3%

Lab. Specialist Name : Sign :	Lab. Engineer Name : Sign :	Consultant Engineer Name : Sign :
--	--	--



MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		15-1-2023																	
Contractor reference	CA-Emb-47																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Lower and middle emb. FILL MATERIAL RESULTS				
Location to be Used	From	To	Fill		
	521+745	521+800	-5		
	521+140	521+320	-5.5		
	520+700	520+800	-8		
	521+800	521+840	-5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	11-1-2023	
2	Classification	m ³	5000	11-1-2023	
3	Proctor & O.m.c	m ³	5000	11-1-2023	
4	L.L & P.L & PI	m ³	5000	11-1-2023	
5	C.B.R	m ³	5000	15-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed	Ahmed mohammed	15/1/2023	A
QA/QC *	Abdullah SAMY	Abdullah	15/1/2023	A
GARB**	Hussien Fouad		15/1/2023	A
Comments by	Final quality approval with Qs			
Employers Representative	Mohamed Ahmed		8-2-23	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Ade		15-1-2023	
Contractor Reference	CA-Emb-47			
Received by ER		MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Lower and middle embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	9.05%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	7.5%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	54.7%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Ade		15/1/2023	A
Contractor QA/QC *	Hassan		15/1/2023	A
GARB**	Hussien Fouad		15/1/2023	A
Employers Representative	Mohamed Awa		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARS MATROUH
 From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11-1-2023	code			
LOCATION	K.P 521+500	CA-Emb-U7	ZONE	520+500	522+000
NAME COMPANY	cairo company				

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		29981.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	4112.0	4261.0	4020.0	3861.0	3561.0	2951.0		A-1-a
Cumulative Retained (g)	0.0	4112.0	8373.0	12393.0	16254.0	19815.0	22766.0	PRO	2.17
Cumulative Retained %	0.0	13.7	27.9	41.3	54.2	66.1	75.9	WC	7.50
Cumulative Passing %	100.0	86.3	72.1	58.7	45.8	33.9	24.1	CBR	54.70



B-soft material gradation				WT.OF sample		500.00	gm
sieve size	10	40	200				
Cumulative Retained (g)	89.50	211.00	312.00				
Cumulative Retained %	17.90	42.20	62.40				
Cumulative Passing %	82.10	57.80	37.60				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	86.28	72.07	58.66	45.79	33.91	24.07	19.76	13.91	9.05

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant



 	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		


PROCTOR TEST

TESTING DATE:	2023/01/12	code			
LOCATION	521+500	CA-EMB-47	ZONE	520+500	522+000
NAME COMPANY	cairo company				


Weight of empty mold :	6070.0	MAX Dry Density	2.17
Mold Volume:	2113.0	Water content %	6.5

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10589.0	10781.0	10965.0	10911	
WT. WET SOIL	4519.0	4711.0	4895.0	4841.0	
Wt. Density	2.139	2.230	2.317	2.291	

Tare No.	20	11	90	45	8	4	16	26		
Tare wt.	60.1	46.1	62.5	41.5	46.8	60.1	33.9	55		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	148.1	148.0	146.6	145.2	143.5	144.2	141.1	142.5		
Wt. Of water	1.9	2.0	3.4	4.8	6.5	5.8	8.9	7.5		
Wt. Of dry soil	88.0	101.9	84.1	103.7	96.7	84.1	107.2	87.5		
Water content %	2.2%	2.0%	4.0%	4.6%	6.7%	6.9%	8.3%	8.6%		
AV. Water content %	2.1%		4.3%		6.8%		8.4%			
Dry Density	2.095		2.137		2.169		2.113			




Contractor




 Electric Express Train
 Central Lab Number 4
 Sec7 Foka - Matrouh

Consultant



California Bearing Ratio TEST

Testing Date :	15/1/2023	Code		FROM STA :	520+500	522+000
Location :	521+500		CA-Emb-47			
Company Name	cairo company					

Test Results


Compaction % for Mold	
Mold No.	4
Mold Vol. (cm ³)	2140
Mold WT. (gm)	4900
Mold WT. + Wet WT. (gm)	9804
Wet WT. (gm)	4904
Wet Density (g/cm ³)	2.292
Dry Density (g/cm ³)	2.146
Proctor Density (g/cm ³)	2.160
Compaction %	99.3

Mositure Ratio After Compacted Mold	
Tare No.	16
Tare WT. (gm)	33.9
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	142.6
Water WT. (gm)	7.4
Dry WT. (gm)	108.7
Moisture Content %	6.8

Swelling	
Mold No.	4
Date	15/01/2023
Initial Height (mm)	6.40
Final Height (mm)	6.40
Difference	0
Sample Height (mm)	119.00
Swelling Ratio %	0%

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.02	0.09	0.14	0.19	0.23	0.28	0.33	0.37	0.44
Load (KN)	0.6	2.7	4.2	5.7	6.9	8.4	9.9	11.1	13.2




Calculations :-

Penteration (mm)	Load (KN)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	5.70	13.4	42.7%			42.1%
5.00	11.10	20.0	55.4%	99	98	54.7%

Lab. Specialist

Name :

Sign :



Lab. Engineer

Name :

Sign :




Consultant Engineer

Name :

Sign :



MATERIAL INSPECTION REQUEST



Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K																
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ Abdelrahman Adel		15-1-2023																	
Contractor reference	CA-Emb-45																			
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	lower and middle embankment FILL MATERIAL RESULTS				
Location to be Used	From 521+840 520+560 521+320 521+700	To 521+900 520+620 521+440 521+740	Fill -5 -10.5 -5 -4.5		
MAR Approval No				Date	
Supplier Name					
Test Requirement	Specification			Clause	
Reference Photos	Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sieve analysis	m ³	5000	11-1-2023	
2	Classification	m ³	5000	11-1-2023	
3	Proctor & O.m.c	m ³	5000	11-1-2023	
4	L.L & P.L & PI	m ³	5000	11-1-2023	
5	C.B.R	m ³	5000	15-1-2023	
Comments by:			Comments by:		
A sample has been taken from fill material by K.K office to (EL Tawakol laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	Eng / Ahmed mohammed		15/1/2023		
QA/QC *	Hassa		15/1/2023		
GARB**	Hussien Fouad		15/1/2023		
Comments by	with es				
Employers Representative	Mohamed Ahmed		8-2-23		

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



Location Name	Contractor Company		Designer Company	
Electric express train	Cairo for Roads and construction Company		k.k	
Issued by Contractor	Name	Sign	Date	Time
	ENG/ Abdelrahman Adel	<i>[Signature]</i>	15-1-2023	
Contractor Reference	CA-Emb-48			
Received by ER	<i>[Signature]</i>	MAR	C1	C2
			C3	DD
			MM	YY
			HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower and middle embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.26%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.16	
7	ASTM D 1883	CBR	63.1%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdelrahman Bel A	<i>[Signature]</i>	15/1/2023	A
Contractor QA/QC *	Hassan	<i>[Signature]</i>	15/1/2023	A
GARB**	Hussien Fouad	<i>[Signature]</i>	15/1/2023	A
Employers Representative	Mohamed Ahmed	<i>[Signature]</i>	15-1-25	A

* Designer

** Alignment/Bridges: Culvert only



Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein - MATROUH
Section - 7 From FOKA To MARSALA MATROUH
From Station 504+000 To Station 568+177



PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	11-1-2023	code			
LOCATION	K.P 521+500	CA-Emb-48	ZONE	520+500	522+000
NAME COMPANY	Cairo company				

1-visual inspection test

2-Gradient test



A-gradation of bulk materials				SAMPLE WEIGHT [g]		27096.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	3851.0	3961.0	3632.0	2581.0	2961.0	2081.0		A-1-a
Cumulative Retained (g)	0.0	3851.0	7812.0	11444.0	14025.0	16986.0	19067.0		PRO 2.16
Cumulative Retained %	0.0	14.2	28.8	42.2	51.8	62.7	70.4		WC 6.80
Cumulative Passing %	100.0	85.8	71.2	57.8	48.2	37.3	29.6		CBR 63.10

B-soft material gradation				WT.OF sample		500.00		gm
sieve size	10	40	200					
Cumulative Retained (g)	69.40	196.00	310.00					
Cumulative Retained %	13.88	39.20	62.00					
Cumulative Passing %	86.12	60.80	38.00					


C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.79	71.17	57.76	48.24	37.31	29.63	25.52	18.02	11.26

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor



Consultant



 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ. د. خالد أحمد عبد الجبار	 SYSTRA	Electric Express Train - HSR		 الهيئة العامة للإستشارة المواصلات والبنية التحتية (ARBIT)
		From El Ain El Sokhna City To El Alamein - MATROUH		
		Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177				


PROCTOR TEST

TESTING DATE:	2023/01/12	code			
LOCATION	K.P 521+500		ZONE	520+500	522+000
NAME COMPANY	Cairo company	CA-Emb-48			


Weight of empty mold :	6190.0	MAX Dry Density	2.16
Mold Volume:	2169.0	Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10685.0	10864.0	11195.0	10911	
WT. WET SOIL	4495.0	4674.0	5005.0	4721.0	
Wt. Density	2.072	2.155	2.308	2.177	

Tare No.	25	45	40	16	18	10	11	32		
Tare wt.	75.8	41.5	46.4	33.9	77.7	43.7	46.1	74.4		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	148.5	147.4	145.4	145.1	145.4	143.1	141.1	142.5		
Wt. Of water	1.5	2.6	4.6	4.9	4.6	6.9	8.9	7.5		
Wt. Of dry soil	72.7	105.9	99.0	111.2	97.2	99.4	95.0	68.1		
Water content %	2.1%	2.5%	4.6%	4.4%	6.8%	6.9%	9.4%	11.0%		
AV. Water content %	2.3%		4.5%		6.9%		10.2%			
Dry Density	2.027		2.062		2.159		1.975			



Contractor



Consultant

15/1/2023

المكتب الاستشاري الهندسي
أ. د. خالد أحمد عبد الجبار

California Bearing Ratio TEST

Testing Date :	15/1/2023	Code		FROM STA :	520+500	522+000
Location :	K.P 5214-500					
Company Name	Cairo company	CA-Emb-46				

- : Test Results


Compaction % for Mold	
Mold No.	6
Mold Vol. (cm ³)	2122
Mold WT. (gm)	5075
Mold WT. + Wet WT. (gm)	9970
Wet WT. (gm)	4895
Wet Density (g/cm ³)	2.307
Dry Density (g/cm ³)	2.160
Proctor Density (g/cm ³)	2.160
Compaction %	100.0

Moisture Ratio After Compacted Mold	
Tare No.	22
Tare WT. (gm)	54.1
Tare WT. + Wet WT. (gm)	150
Tare WT. + Dry WT. (gm)	143.9
Water WT. (gm)	6.1
Dry WT. (gm)	89.8
Moisture Content %	6.8

Swelling	
Mold No.	6
Date	15/01/2023
Initial Height (mm)	6.40
Final Height (mm)	6.40
Difference	0
Sample Height (mm)	119.00
Swelling Ratio %	0%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.03	0.11	0.17	0.23	0.28	0.33	0.38	0.43	0.52
Load (KN)	0.9	3.3	5.1	6.9	8.4	9.9	11.4	12.9	15.6




Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (lb)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	6.90	13.4	51.7%			50.7%
5.00	12.90	20.0	64.4%	100	98	63.1%

Lab. Specialist

Name :

Sign :



Lab. Engineer

Name :


Sign :



Consultant Engineer

Name :

Sign :



MATERIAL INSPECTION REQUEST					

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		20-1-2023							
Contractor reference	CA-Emb-49									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower and middle embankment FILL MATERIAL RESULTS					
Location to be Used	From	To	Fill			
	521+740	521+800	-4.5			
	520+560	520+620	-10			
520+620	520+700	-8				
MAR Approval No				Date		
Supplier Name						
Test Requirement				Specification	Clause	
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	16-1-2023		
2	Classification	m ³	5000	16-1-2023		
3	Proctor & O.m.c	m ³	5000	16-1-2023		
4	L.L & P.L & PI	m ³	5000	16-1-2023		
5	C.B.R	m ³	5000	20-1-2023		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	Eng / Ahmed mohammed		20/1/2023			
QA/QC *	Hassan		20/1/2023			
GARB**	Hussien Fouad		20/1/2023			
Comments by	Rid quantity approved with @s					
Employers Representative	Mohamed Ahmed		8-2-25			

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



الهيئة القومية للإتفاق
(GARBT)



Location Name	Contractor Company			Designer Company							
Electric express train	Cairo for Roads and construction Company			k.k							
Issued by Contractor	Name	Sign	Date	Time							
	ENG/ Abdelrahman Adel		20-1-2023								
Contractor Reference	CA - Emb-49										
Received by ER		MAR		C1	C2	C3	DD	MM	YY	HH	MM

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	lower and middle embankment Soil (A-1-a)			
Location of stock	K.p (521+500) No (1)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	11.3%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.17	
7	ASTM D 1883	CBR	64.7%	
Comments by:			Comments by:	
			All test under Responsibility Third party	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel		20/1/2023	A
Contractor QA/QC *	Hassan		20/1/2023	A
GARB**	Hussien Fouad		20/1/2023	A
Employers Representative	Mohd Ahd		15-1-25	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد قنديل	 SYSTRA & SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	 الهيئة القومية للإنفاق سلطة قناة السويس (S.A.S.C.)
--	--	--	---

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	17-1-2023	code		ZONE	520+500	522+000
LOCATION	K.P 521+500	CA-Emb-4g				
NAME COMPANY	cairo company					

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		31809.00		gm	table classify	
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify	
Mass retained (g)	0.0	4661.0	4231.0	3938.0	3401.0	3861.0	2951.0		A-1-a	
Cumulative Retained (g)	0.0	4661.0	8892.0	12830.0	16231.0	20092.0	23043.0		PRO	2.17
Cumulative Retained %	0.0	14.7	28.0	40.3	51.0	63.2	72.4		WC	6.80
Cumulative Passing %	100.0	85.3	72.0	59.7	49.0	36.8	27.6		CBR	64.70

B-soft material gradation			WT.OF sample		500.00		gm
sieve size	10	40	200				
Cumulative Retained (g)	66.60	171.00	295.00				
Cumulative Retained %	13.32	34.20	59.00				
Cumulative Passing %	86.68	65.80	41.00				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	85.35	72.05	59.67	48.97	36.84	27.56	23.89	18.13	11.30

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant


 Electric Express Train
 Central Lab Number 4
 Sec-7 Foka - Matrouh


 20/1
 2023
 الاستشاري الهندسي
 أ.د. خالد قنديل

 	Electric Express Train - HSR		
	From El Ain El Sokhna City To El Alamein - MATROUH		
	Section - 7 From FOKA TO MARSA MATROUH		
From Station 504+000 To Station 568+177			


PROCTOR TEST

TESTING DATE:	2023/01/18	code			
LOCATION	K.P 521+500		ZONE	520+500	522+000
NAME COMPANY	Al Kahera	CA-Emb-yg			


Weight of empty mold :	6070.0	MAX Dry Density	2.17
Mold Volume:	2113.0	Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10482.0	10687.0	10969.0	10741	
WT. WET SOIL	4412.0	4617.0	4899.0	4671.0	
Wt. Density	2.088	2.185	2.319	2.211	


Tare No.	16	21	17	26	33	18	90	73		
Tare wt.	34	55.2	59.5	55	73.6	77.8	62.5	42.9		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	146.9	147.8	145.9	145.6	145.4	145.1	141.1	142.5		
Wt. Of water	3.1	2.2	4.1	4.4	4.6	4.9	8.9	7.5		
Wt. Of dry soil	112.9	92.6	86.4	90.6	71.8	67.3	78.6	99.6		
Water content %	2.7%	2.4%	4.7%	4.9%	6.4%	7.3%	11.3%	7.5%		
AV. Water content %	2.6%		4.8%		6.8%		9.4%			
Dry Density	2.036		2.085		2.170		2.020			



Contractor


 Electric Express Train
 Central Lab Number 4
 Sec 7 Foka - Matrouh

Consultant

20/1/2023



 الإشراف الهندسي
 خالد قنديل
 د. أ.

 	Electric Express Train - HSR	 
---	-------------------------------------	---

California Bearing Ratio TEST


Testing Date :	20/1/2023	Code		FROM STA :	520+500	522+000
Location :	K.P. 521+500					
Company Name	Al-Kahera	CA-6m6-4g				

-: Test Results

Compaction % for Mold		Moisture Ratio After Compacted Mold		Swelling	
Mold No.	2	Tare No.	15	Mold No.	2
Mold Vol. (cm ³)	2168	Tare WT. (gm)	31.9	Date	20/01/2023
Mold WT. (gm)	5089	Tare WT. +Wet WT. (gm)	150	Initial Height (mm)	6.40
Mold WT. + Wet WT. (gm)	10080	Tare WT. +Dry WT. (gm)	143.1	Final Height (mm)	6.40
Wet WT. (gm)	4991	Water WT. (gm)	6.9	Difference	0
Wet Density (g/cm ³)	2.302	Dry WT. (gm)	111.2	Sample Height (mm)	119.00
Dry Density (g/cm ³)	2.168	Moisture Content %	6.2	Swelling Ratio %	0%
Proctor Density (g/cm ³)	2.170				
Compaction %	99.9				

Loading Reading :

Penteration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.04	0.09	0.16	0.21	0.26	0.33	0.38	0.44	0.53
Load (KN)	1.2	2.7	4.8	6.3	7.8	9.9	11.4	13.2	15.9



Calculations :-



Penteration (mm)	Load (Kn)	Standard Load (Ib)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	6.30	13.4	47.2%			46.3%
5.00	13.20	20.0	65.9%	100	98	64.7%

Lab. Specialist
Name :
Sign :

Lab. Engineer
Name :
Sign :
Electric Express Train
Central Lab Number 4
Sec-7 Fuka - Matruh





Consultant Engineer
Name :
Sign :
20/1/2023
المهندس
الإستشاري الهندسي
د.أ. خالد قنديل

MATERIAL INSPECTION REQUEST	    				

Contractor Company	Cairo for Roads and construction Company		Designer Company	K.K						
Issued by Contractor	Name	Sign	Date	Time						
	Eng/ Abdelrahman Adel		20-1-2023							
Contractor reference	CA-Emb-50									
Received by ER		MIR	C1	C2	C3	DD	MM	YY	HH	MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	lower embankment			FILL MATERIAL RESULTS		
Location to be Used	From 520+800	To 520+900	Fill -8.5			
	520+800	520+895	-8			
MAR Approval No				Date		
Supplier Name						
Test Requirement	Specification			Clause		
Reference Photos	Yes attached / No			Other		
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Sieve analysis	m ³	5000	16-1-2023		
2	Classification	m ³	5000	16-1-2023		
3	Proctor & O.m.c	m ³	5000	16-1-2023		
4	L.L & P.L & PI	m ³	5000	16-1-2023		
5	C.B.R	m ³	5000	20-1-2023		
Comments by:			Comments by:			
A sample has been taken from fill material by K.K office to (EL Nuby laboratory) and the results founded meet the specifications and accepted.			Test result for estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng / Ahmed mohammed		20/1/2023	A
QA/QC *	Hassan		20/1/2023	
GARB**	Hussien Fouad		20/1/2023	
Comments by	with approval			
Employers Representative	Mohamed Ali		8-2-25	

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST



الهيئة العامة
للطرق والكباري والمنشآت
(GARBLT)



Location Name	Contractor Company		Designer Company																	
Electric express train	Cairo for Roads and construction Company		k.k																	
Issued by Contractor	Name	Sign	Date	Time																
	ENG/ Abdelrahman Adel		20-1-2023																	
Contractor Reference	CA-Emb-50																			
Received by ER		MAR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

NB:Package 1 only (Package 2 via Content)				
The following test result are attached for review				
Description of Materials	Soil (A-1-a)			
Location of stock	K.p (520+500) No (3)			
Item	Specification	Test requirement	Test result attachment	Remarks
1	ASTM D 75	Aggregate Sampling	According to specifications	
2	ASTM C 136	Sieve Analysis	According to specifications	
3	ASTM D 1440	Passing Sieve, No 200	13.33%	
4	ASTM D 4318	Atterberg limit	N.P	
5	ASTM D 2974	Moisture content	6.8%	
6	ASTM D 1557	Modified proctor	2.17.	
7	ASTM D 1883	CBR	52.9%	
Comments by:		Comments by:		
		All test under Responsibility Third party		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Abdel Rahman Adel	Abdel Rahman Adel	20/1/2023	A
Contractor QA/QC *	Hassan		20/1/2023	A
GARB**	Hussien Fouad	Hussien Fouad	20/1/2023	A
Employers Representative	Mohy Ahs		15-1-23	A

* Designer

** Alignment/Bridges: Culvert only

 ENGINEERING CONSULTING OFFICE المكتب الاستشاري الهندسي أ.د. خالد فتحي	 SYSTRA & SHAKER	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA To MARS MATROUH From Station 504+000 To Station 568+177	 الهيئة العامة للنقل وزارة النقل (M.T.A.)
---	--	--	---

PARTICLE SIZE DISTRIBUTION OF SOIL

TESTING DATE:	17-1-2023	code			
LOCATION	K.P 520+500			ZONE	520+500
NAME COMPANY	cairo company	CA-Emb-50			522+000

1-visual inspection test

2-Gradient test

A-gradation of bulk materials				SAMPLE WEIGHT [g]		24549.00		gm	table classify
sieve size	2	1.5	1	4/3	2/1	8/3	# 4	PASS	soil classify
Mass retained (g)	0.0	3841.0	3251.0	3332.0	2203.0	2141.0	2031.0		A-1-a
Cumulative Retained (g)	0.0	3841.0	7092.0	10424.0	12627.0	14768.0	16799.0		PRO 2.17
Cumulative Retained %	0.0	15.6	28.9	42.5	51.4	60.2	68.4		WC 6.80
Cumulative Passing %	100.0	84.4	71.1	57.5	48.6	39.8	31.6		CBR 52.90

B-soft material gradation			WT.OF sample		500.00		gm
sieve size	10	40	200				
Cumulative Retained (g)	73.50	174.80	288.80				
Cumulative Retained %	14.70	34.96	57.76				
Cumulative Passing %	85.30	65.04	42.24				

C-General gradient										
sieve size(in)	2	1.5	1	3/4	1/2	3/8	# 4	# 10	# 40	# 200
sieve size(mm)	50.0	37.5	25.0	19.0	12.5	9.5	4.75	2.00	0.425	0.075
Cumulative Passing %	100.00	84.35	71.11	57.54	48.56	39.84	31.57	26.93	20.53	13.33

ATTERBERG LIMITS	LIQUID LIMIT (L.L.)	PLASTIC LIMIT (P.L.)	PLASTIC INDEX (P.I.)
	N.P	N.P	N.P

Contractor

Consultant



Handwritten signature and date 20/1/2023



	Electric Express Train - HSR From El Ain El Sokhna City To El Alamein - MATROUH Section - 7 From FOKA TO MARSA MATROUH From Station 504+000 To Station 568+177		


PROCTOR TEST

TESTING DATE:	2023/01/18	code			
LOCATION	K.P 520+000		ZONE	520+500	522+000
NAME COMPANY	cairo company	CA-Emb-50			

Weight of empty mold :	6070.0	MAX Dry Density	2.17
Mold Volume:	2113.0	Water content %	6.8

trial no :	1	2	3	4	
Wt. Of Mold+ wet soil	10482.0	10687.0	10948.0	10741	
WT. WET SOIL	4412.0	4617.0	4878.0	4671.0	
Wt. Density	2.088	2.185	2.309	2.211	

Tare No.	25	16	17	11	15	20	8	26		
Tare wt.	59.6	34	59.6	46.5	31.4	59.9	46.8	55		
Wt. Of wet soil & tare	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0		
Wt. Of dry soil & tare	147.6	146.9	146.1	145.8	142.7	144.1	141.2	142.0		
Wt. Of water	2.4	3.1	3.9	4.2	7.3	5.9	8.8	8.0		
Wt. Of dry soil	88.0	112.9	86.5	99.3	111.3	84.2	94.4	87.0		
Water content %	2.7%	2.7%	4.5%	4.2%	6.6%	7.0%	9.3%	9.2%		
AV. Water content %	2.7%		4.4%		6.8%		9.3%			
Dry Density	2.032		2.094		2.162		2.023			



Contractor


 Electric Express Train
 Central Lab Number 4
 Sec-7 Foka - Matrouh

Consultant

20/1/2023
 Hassan

 	Electric Express Train - HSR	 
---	-------------------------------------	---

California Bearing Ratio TEST

Testing Date :	20/1/2023	Code		FROM STA :	520+500	522+000
Location :	521+500					
Company Name	cairo company	CA-Emb-50				

Test Results


Compaction % for Mold	
Mold No.	2
Mold Vol. (cm ³)	2168
Mold WT. (gm)	5089
Mold WT. + Wet WT. (gm)	10110
Wet WT. (gm)	5021
Wet Density (g/cm ³)	2.316
Dry Density (g/cm ³)	2.169
Proctor Density (g/cm ³)	2.170
Compaction %	99.9

Moisture Ratio After Compacted Mold	
Tare No.	22
Tare WT. (gm)	54.1
Tare WT. +Wet WT. (gm)	150
Tare WT. +Dry WT. (gm)	143.9
Water WT. (gm)	6.1
Dry WT. (gm)	89.8
Moisture Content %	6.8

Swelling	
Mold No.	2
Date	20/01/2023
Initial Height (mm)	7.00
Final Height (mm)	7.10
Difference	0
Sample Height (mm)	119.00
Swelling Ratio %	0.1%

Loading Reading :

Pentration (mm)	0.64	1.27	1.91	2.54	3.18	3.80	4.45	5.00	6.40
Load Reading (mm)	0.06	0.09	0.14	0.17	0.23	0.28	0.32	0.36	0.49
Load (KN)	1.8	2.7	4.2	5.1	6.9	8.4	9.6	10.8	14.7



Calculations :-

Pentration (mm)	Load (Kn)	Standard Load (Ib)	CBR (%)	Mold - Compaction (%)	Compaction (%)	CBR % عند نسبة 98
2.50	5.10	13.4	38.2%	100	98	37.5%
5.00	10.80	20.0	52.9%			52.9%

Lab. Specialist

Name :

Sign :

Lab. Engineer

Name :

Sign :

Electric Express Train
Central Lab Number 4
See Naka - Matrouh

Consultant Engineer

Name :

Sign :

المكتب
الاستشاري الهندسي
د. أحمد قنديل