

السيد المهندس / رئيس قطاع التنفيذ والمناطق

تحية طيبة.. وبعد،،

بالإحالة إلى مشروع القطار الكهربائي السريع قطاع (وادي النطرون - برج العرب - اسكندرية)
نتشرف بأن نرفق لسيادتكم المقياسة المعدلة لبنود أعمال الجسر الترابي للخط الاول من مشروع
القطار الكهربائي السريع
(العين السخنة - العاصمة الادارية - العلمين - مطروح) (قطاع وادي النطرون / برج العرب)
المسافة من الكم 312+800 الي الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الي الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس
(مسافات متفرقة). (بالأمر المباشر) طبقاً للمفاوضه الخاصة بشركة منصور علي بتاريخ 2-

2025

عقد: (2025 / 2024 / 964)

تنفيذ :- شركة منصور علي حسن

برجاء من سيادتكم التفضل بالأحاطه والتوجيه بالازم

وتفضلوا بقبول فائق الاحترام والتقدير،،،

رئيس الإدارة المركزية

المنطقة الخامسة- غرب الدلتا

عميد مهندس/

"هاني محمد محمود طه"



المقايضة المعدلة لأعمال الجسر الترابي للخط الاول من مشروع القطر الكهربائي السريع
(العين السخنة - العاصمة الادارية - العلمين - مطروح) (القطاع الرابع)
المسافة من الكم 312+800 الى الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الى الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس (مسافات متفرقة)
تنفيذ : شركة منصور علي حسن
عقد رقم (2025/2024/964)


رقم البند	بيان الأعمال	الوحدة	الكمية	الفئة	الاجمالي
1	اعمال الردم				
1-1	بالمتر المكعب اعمال تحميل وتوريد ونقل اترية وذلك لاستكمال مسافات متفرقة بالقطاع مطابقة للمواصفات وتشغيلها باستخدام الات التسوية بسمك لا يزيد عن 50 سم حتي منسوب -2 متر اسفل منسوب الفرمة وبسمك لا يزيد عن 25 سم اعلي من منسوب -2 من منسوب الفرمة لاستكمال المنسوب التصميمي لتشكيل الجسر والاكتاف (نسبة تحمل كالفورنيا لا تقل عن 15%) ورشها بالمياة الاصلوية للوصول الي نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الي اقصى كثافة جافة (95% من الكثافة الجافة القصوي) ويتم التنفيذ طبقاً للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقاً لاصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندس المشرف. - مسافة النقل حتي 2 كم - يتم احتساب علاوة 2.5 جنية لكل 1 كم وذلك حتي مسافة نقل 100 كم و 2.15 جنية لكل 1 كم زيادة عن مسافة نقل 100 كم - السعر يشمل عمل تشوينات وتخليط واختبارات ونقل لموقع العمل حتي مسافة 2 كم - البند يشمل قيمة المادة المحجيرة	م3	20600	183	3660000
	علاوة مسافة النقل 150 كم $374=2.15*60+2.5*98$		16000	374.00	5984000
	علاوة مسافة النقل 158 كم $369.7=2.15*58+2.5*98$		4000	369.70	1478800
	علاوة تحصيل رسوم الكارثة والموازين طبقاً للانحة الشركة الوطنية		20000	13.00	260000
2	طبقات الاساس				
2-1	بالمتر المكعب اعمال توريد وفرش طبقة تأسيس (Prepared subgrade) من الاحجار الصلبة المتدرجة ناتج تكسير الكسارات وذلك لاستكمال مسافات أماكن متفرقة والمطابقة للمواصفات واقصى حجم للحبيبات 100 مم والا تزيد نسبة المار من منخل 200 عن 12% والتدرج الوارد بالاشتراطات الخاصة بالمشروع لا تقل نسبة تحمل كالفورنيا عن 25% والا تزيد نسبة الفاقد بجهاز لوس انجلوس عن 30% والا يزيد الامتصاص عن 15% والا يقل معامل المرونة (Ev2) من تجريه لوح التحميل عن 80 ميجاباسكال ويتم فردها علي طبقتين باستخدام الات التسوية الحديثة علي ان لا يزيد سمك الطبقة بعد تمام الدمك عن 25 سم ورشها بالمياة الاصلوية للوصول الي نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الي اقصى كثافة جافة قصوي (لا تقل عن 95% من الكثافة المعملية) والفنه تشمل اجراء التجارب المعملية والحقلية ويتم التنفيذ طبقاً لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقاً للمواصفات الفنية للمشروع وتقرير الاستشاري وتعليمات المهندس المشرف. - مسافه النقل لا تقل عن 20 كم - يتم احتساب علاوة نقل 2.50 جنية لكل 1 كم زيادة حتي 100 كم و 2.15 لكل 1 كم زيادة عن مسافة نقل 100 كم. - السعر لا يشمل قيمة المواد المحجيرة	م3	3000	195	585000
	علاوة المادة المحجيرة		3000	212.94	638820
	علاوة مسافة النقل 150 كم		3000	307.50	922500
	علاوة تحصيل رسوم الكارثة والموازين طبقاً للانحة الشركة الوطنية		3000	25.00	75000

الهيئة العامة للطرق والكباري
مدير عام المشروعات
م/ محمد حسني فياض

الهيئة العامة للطرق والكباري
مدير المشروع
م/ أحمد جلال عبد السلام

المكتب الاستشاري الهندسي أ.د. خالد
قنديل
مدير المشروع
م/ هشام محمد صبري

الشركة المنفذة
مدير المشروع
م/ محمود ايوب





المقاييس المعدلة لأعمال الجسر الترابي للخط الأول من مشروع القطار الكهربائي السريع
(العين السخنة - العاصمة الإدارية - العلمين - مطروح) (القطاع الرابع)
المسافة من الكم 312+800 الى الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الى الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس (مسافات متفرقة)
تنفيذ : شركة منصور علي حسن
عقد رقم (2025/2024/964)

رقم البند	بيان الاعمال	الوحدة	الكمية	الفئة	الاجمالي
2-2	بالمتر المكعب أعمال توريد وفرش طبقة أساس من الاحجار الصلبة المتدرجة ناتج تكسير الكسارات وذلك لاكمال مسافات متفرقة والمطابقة للمواصفات وأقصى حجم للحبيبات ما بين 31.5 مم الي 40 مم و يزيد نسبة المار من منخل 200 عن 5% والتدرج الوارد بالاشتراطات الخاصة بالمشروع لا تقل نسبة تحميل كاليفورنيا عن 80 % والا يقل معامل المرونة (Ev2) من تجربة لوح التحميل عن 120 ميجاباسكال والا يزيد نسبة الفاقد بجهاز لوس انجلوس عن 30 % والا يزيد الامتصاص عن 15 % ويتم فردها علي طبقتين باستخدام الات التسوية الحديثة علي ان لا يزيد سمك الطبقة بعد تمام الدك عن 20سم و رشها بالمياة الاصلوية للوصول الي نسبة الرطوبة المطلوبة والدك الجيد بالهراسات للوصول الي أقصى كثافة جافة قصوي (لا يقل عن 100%) من الكثافة المعملية و الفئة تشمل اجراء التجارب المعملية والحقلية ويتم تنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتعلاته طبقا للمواصفات الفنية للمشروع وتقرير الاستشاري وتعليمات المهندس المشرف . - مسافه النقل لا تقل عن 20 كم . - يتم احتساب علاوة نقل 2.50 جنية لكل 1 كم زيادة حتي 100كم و 2.15 لكل 1كم زيادة عن مسافة نقل 100كم. - السعر لا يشمل قيمة المواد المحجرية	3م	2000	190	380000
	علاوة المادة المحجرية		2000	235.76	471520
	علاوة مسافة النقل 150 كم		2000	307.50	615000
	علاوة تحصيل رسوم الكارثة والموازين طبقا للائحة الشركة الوطنية		2000	25.00	50000
	الاجمالي				15,120,640.00
خمسة عشر مليوناً ومائة وعشرون ألفاً وستمئة وأربعون جنيهاً فقط لا غير					
* يرجى العلم بان الفئات المذكورة طبقا للمفاوضة الخاصة بشركة منصور علي بتاريخ 2-2025.					

الهيئة العامة للطرق والكباري
مدير عام المشروعات
م/ محمد حسني فياض

الهيئة العامة للطرق والكباري
مدير المشروع
م/ أحمد جلال عبد السلام



المكتب الاستشاري الهندسي أ.د. خالد
قنديل
مدير المشروع
م/ هشام محمد صبري

الشركة المنفذة
مدير المشروع
م/ محمود أبو بوب

رئيس الادارة المركزية
منطقة غرب الدلتا

الاسكندرية - مرسى مطروح
عميد مهندس/

هاني محمد محمود طه



"ہائی محمد محمود طہ"

قائمة الكميات الواردة بالمستخلص جاري (1)

أعمال الجسر الترابي للخط الاول من مشروع القطار الكهربائي السريع
(العين السخنة - العاصمة الادارية - العلمين - مطروح) (قطاع وادي النطرون / برج العرب)
المسافة من الكم 312+800 الي الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الي الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس (مسافات متفرقة) بالأمر المباشر

رقم البند و بيانه : (1-1) بالمتر المكعب اعمال تحميل وتوريد ونقل اتربة وذلك لاستكمال مسافات متفرقة
بالقطاع مطابقة للمواصفات وتشغيلها باستخدام الات التسوية بسمك لا يزيد عن 50 سم حتي منسوب 2- متر
اسفل منسوب الفرمة وبسمك لا يزيد عن 25 سم أعلي من منسوب 2- من منسوب الفرمة لاستكمال المنسوب
التصميمي لتشكيل الجسر والاكتاف (نسبة تحمل كاليفرونيا لا تقل عن 15%) ورشها بالمياة الأصولية للوصول الي
نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الي اقصي كثافة جافة (95% من الكثافة الجافة القصوي
(ويتم التنفيذ طبقاً للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند
بجميع مشتملاته طبقاً لاصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندس المشرف.

عقد رقم (964-2024-2025)

تنفيذ : شركة منصور علي حسن منصور

مقدار العمل السابق :		0.00	3م
مسلسل	الموقع الكيلومتری	الكم	
		من الكم	الي الكم
1		312+920	313+140
19912.00	220		
19912.00	اجمالي الكميه الهندسي (3م)		
19912.00	الاجمالي الكلي (3م)		

مهندس الهيئه

م/ أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري

مكتب ا.ه. / خالد قنديل
م/ هشام محمد صبري

مهندس الاستشاري

مكتب XYZ
م/ محمد خليل

مهندس الشركة

م/ محمود ايوب
م/ حسن منصور

2

قائمة الكميات الواردة بالمستخلص جاري (1)

أعمال الجسر الترابي للخط الاول من مشروع القطار الكهربائي السريع
(العين السخنة - العاصمة الادارية - العلمين - مطروح) (قطاع وادي النطرون / برج العرب)
المسافة من الكم 312+800 الي الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الي الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس (مسافات متفرقة) بالأمر
المباشر

علاوة بند (1-1) علاوة مسافة النقل 158 كم .

عقد رقم (2025-2024-964)

تنفيذ : شركة منصور علي حسن منصور

مقدار العمل السابق :		0.00	3م
مسلسل	الموقع الكيلومري	الطول (متر)	
		الى الكم	من الكم
1		313+140	312+920
3982.40		220	
3982.40	اجمالي الكميه الهندسي (م3)		
3982.40	الاجمالي الكلي (م3)		

مهندس الهيئه

م/ أحمد جلال عبد السلام

م/ أحمد جلال

مهندس الاستشاري

مكتب ا.د / خالد قنديل

م/ هشام محمد صبري



مهندس الاستشاري

مكتب XYZ

م/ محمد خليل

مهندس الشركة

م/ محمود ايوب



قائمة الكميات الواردة بالمستخلص جاري (1)

أعمال الجسر الترابي للخط الاول من مشروع القطار الكهربائي السريع
(العين السخنة - العاصمة الادارية - العلمين - مطروح) (قطاع وادي النطرون / برج العرب)
المسافة من الكم 312+800 الي الكم 313+200 بطول 0.400 كم اعمال الردم (مسافات متفرقة)
والمسافة من الكم 311+000 الي الكم 313+200 بطول 2.200 كم اعمال طبقات الاساس (مسافات متفرقة) بالأمر المباشر

علاوة بند (1-1) علاوة تحصيل رسوم الكارثة والموازن طبقا للائحة الشركة الوطنية.

عقد رقم (2025-2024-964)

تنفيذ : شركة منصور علي حسن منصور

		3م	0.00	مقدار العمل السابق :
الكمية (م3)	الطول (متر)	الموقع الكيلومتری		مسلسل
		الى الكم	من الكم	
19912.00	220	313+140	312+920	1
19912.00	اجمالي الكمية الهندسي (م3)			
19912.00	الاجمالي الكلي (م3)			

مهندس الهيئة

م/ أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري

مكتب ا.د. / خالد قنديل

م/ هشام محمد صبري



مهندس الاستشاري

مكتب XYZ

م/ محمد خليل



مهندس الشركة

م/ محمود ايوب

م/ حسن منصور





محضر مسافة نقل

التاريخ : ١٩ / ٥ / ٢٠٢٠

اسم المشروع : القطار الكهربائي السريع (قطاع وادي النطرون / برج العرب / الاسكندرية)
قام استشاري الهيئة العامة للطرق و الكباري بقياس مسافة النقل من المحجر الي الموقع والعكس لشركة منصور علي حسن

وبحضور كلاً من :-

- 1- م / مجدي صلاح عن سيسترا (الإستشاري العام)
- 2- م / هشام محمد صبري عن مكتب د/ خالد قنديل (إستشاري الهيئة)
- 3- م / محمود أيوب عن شركة منصور علي حسن

وكانت الاحداثيات كالتالي :-

اسم المحجر	الشرق	الشمال	المسافة
محجر سويكر (رمل)	29 ° 51 ' 5 . 8 "	30 ° 31 ' 44 . 5 "	158
محجر السيوي (35033) تربة	29 ° 48 ' 16 . 1 "	30 ° 32 ' 19 . 6 "	160

ملاحظات :-

في حالة تغيير المصدر يتم قياس و اعتماد مسافة النقل الجديدة.

مدير المشروع (الهيئة)
م / أحمد جلال عبدالسلام
أحمد جلال

الاستشاري العام
(سيسترا)

م / مجدي صلاح

استشاري الهيئة مكتب
م / خالد قنديل
م / هشام محمد صبري

مدير المشروع الشركة
م / محمود أيوب

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

I. Introduction

- 1- Project : ELERICAL EXPRESS TRAIN
 2- General consultant : SYSTRA
 3- Owner : الهيئة العامة للطرق والكباري
 4- Contractor : شركة منصور علي حسن للمقاولات
 5- Date : 02/05/2025
 6- Station : St(313+300) مشون الشركة
 7- R-Code : 522-3

II. Sample description:

Gravel And Sand

III. Required tests and Results:**Table (1): Physical properties of soil**

1-Grain size analysis and classification and Percentage of Materials finer than No. 200 (75 μ m)	Grain size analysis	As showed in appendix
	Classification	A-1-a
	Pass No.200	12.4%
2- Modified compaction (Proctor test)	MDD	2.115
	OMC	6.0%
3- Liquid limit, plastic limit and plasticity index	LL	20
	PL	15.4
	PI	4.6
4- California bearing ratio (CBR)	CBR ratio	32%

IV. Notes:

- Samples were bought by: Contractor.
- Samples are responsible from the person who brought it.
- The results are applying only for the present report.

Geotechnical consultant

Dr. M. Badry

Dr. Mohamed Mostafa Badry



S.N. 5222

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

APPENDIX



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة


دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

**PARTICLE SIZE DISTRIBUTION
ANALYSIS
ASTM C-136 / AASHTO T27**

	WEIGHT RETAINED (gm)	CUMULATIVE WEIGHT RETAINED (gm)	CUMULATIVE PERCENTAGE RETAINED (%)	CUMULATIVE PERCENTAGE PASSING (%)	STANDARD SPECIFICATION LIMITS
2	0.00	0.00	0.00	100.0	
1 1/2	234.00	234.00	2.34	97.7	
1	654.00	888.00	8.88	91.1	
3/4	248.00	1136.00	11.36	88.6	
1/2	1287.00	2423.00	24.23	75.8	
3/8	1034.00	3457.00	34.57	65.4	
No.4	1987.00	5444.00	54.44	45.6	
No.10	92.00	92.00	18.40	37.2	
No.40	214.00	214.00	42.80	26.1	
No.200	364.00	364.00	72.80	12.4	

Total sample weight = 10000.00 pass No.4= 4556.0 Total fine aggregates weight = 500 gm
% 45.6

**Soil classification: A - 1 - a**

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

**Modified Proctor Test Report
ASTM - D 1557**

Mould Number :-

2

Volume of mould =

2140 cm³

Weight of mould =

6220 g


G.S =

2.55 g/cm³**A- Density Calculations :-**

	1	2	3	4	5
Weight.of wet soil+mould (g)	10652	10871	11034	10931	10764
Weight.of mould (g)	6220	6220	6220	6220	6220
Weight.of wet soil (g)	4432	4651	4814	4711	4544
Volume of mould (cm ³)	2140	2140	2140	2140	2140
Wet density (g/cm ³)	2.071	2.173	2.250	2.201	2.123
Dry density (g/cm ³)	2.028	2.085	2.114	2.022	1.902
Zero-air Void curve			2.192	2.080	1.966

B- Moisture Calculations :-

Weight.of wet soil+container (g)	250.0	250.0	250.0	250.0	250.0
Weight.of dry soil+container (g)	245.7	241.7	237.6	233.3	228.6
Weight.of container (g)	45.0	45.0	44.0	45.0	45.0
moisture content(%)	2.1	4.2	6.4	8.9	11.7

C - Dry density-Moisture relationship:-

M.D.D=

2.115 gm/cm³

O.M.C=

6.00 %



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**


الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Liquid and Plastic Limits Test**ASTM - D 4318**

Test No	1	2	3	4	5	6
Type of test	Liquid Limit				Plastic Limit	
NO of B.	35	27	23	16		
Container No	a	b	c	d	F	J
Mass of wet soil +container	63.10	65.10	61.40	58.20	39.50	40.20
Mass of dry soil +container	61.20	62.30	58.60	55.30	37.90	38.80
Mass of container	45.30	46.20	45.20	45.00	29.20	27.60
Mass of moisture	1.90	2.80	2.80	2.90	1.60	1.40
Mass of dry soil	15.90	16.10	13.40	10.30	8.70	11.20
Moisture content	11.95	17.39	20.90	28.16	18.39	12.50

**Results:**

Liquid Limit (L.L.) : 20 %.

Plastic Limit (P.L.) : 15.4 %.

Plasticity Index (P.I.): 4.6 %.



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**


الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

Report Of CBR Test - ASTM - D 1883

NO OF BLOWS	56					
MOULD NO	1					
WT OF MOULD+SOIL	9809					
WT OF MOULD	4956					
WT OF SOIL	4853					
VOLUME OF MOULD	2176					
WET DENSITY	2.230					
	MC before soaking			Weight of Rammer	4.54Kg	
TIN NO	1			MDD	Kg/m3	2.115
WT OF WET SOIL+TIN	250.00					
WT OF DRY SOIL+TIN	239.2			OMC	%	6.0
WT OF WATER	10.80					
WT OF TIN	45					
WT OF DRY SOIL	194.2					
MOISTURE CONTENT	5.6					
DRY DENSITY	2.113					
Pen	Reading (Div)		Bearing (KN)		CBR	
mm	56		56		standar	56
0.00	0		0.0		0.0	
0.64	67		0.7		4.5	
1.27	102		1.0		8.5	
1.91	147		1.4		12.0	
2.54	206		2.0		14.5	15
3.17	278		2.7		16.3	
3.81	382		3.7		18.0	
4.45	517		5.1		19.3	
5.08	659		6.5		20.5	32
5.71	817		8.0		21.9	
6.35	989		9.7		23.3	



MATERIAL APPROVAL REQUEST



الهيئة العامة
للطرق والجسور
(GARB)



الهيئة القومية للإسكان
والخدمات العمرانية



Contractor Company	MANSOUR ALI HASSAN		Designer Company	(kk)Engineering consulting office							
Issued by Contractor	Name	Sign	Date/Serial Number	Time							
	Eng: MAHMOUD AYOUB		13-05-2025 (MNS- M.A-09)	11:00 AM							
Received by ER	Eng: Gaber Ibrahim		MAR	C1	C2	C3	DD	MM	YY	HH	MM
				313	EW	CS	13	05	25	11	00

CODE-1	51 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	STOCK PILE FOR SOIL (FILL LAYER)		
Location to be Used	STATION 313+300		
Sample only	Yes	Materials Type	FILL layer
Supplier Name	ELSEWY-SWEKAR	Data Sheet provided	Yes attached
Reference in BoQ		Specification	- EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.
Prequalification reference		Test Samples Results	Approved
Reference Photos	No	Other	
Comments by: Eng ahmed galal (GARB)		Comments by: Eng. (ER)	
1- تم إجراء الاختبارات المعملية بمعمل البدري وتم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.		1- All tests were carried-out by ALBADRY Lab, Depended on samples submitted by material engineer for both contractor , GARB engineer. 2- Results report attached and acceptable with the project specifications. 3- Final approval is subject to above mentioned comments.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mahmoud Ayoub			A
GARB** QA/QC*	Eng. Mostafa Khaled			A
GARB**	Eng: Ahmed galal			A
Employers Representative	Eng: Gaber Ibrahim			A.WC

* Designer

** Alignment/Bridges: Culvert only

13-05-2025

ALBADRY CONSULTING

Geology Engineering and Quality Control
Dr. MOHAMED MOSTAFA BADRY
Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات
الجيولوجية والهندسية وضبط الجودة
دكتور استشاري/محمد مصطفى بدرى
ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

TECHNICAL REPORT

Contractor : شركة منصور علي حسن للمقاولات
Date of report : 18/05/2025
R-Code : 598



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

I. Introduction

- 1- Project : ELERICAL EXPRESS TRAIN
 2- General consultant : SYSTRA
 3- Owner : الهيئة العامة للطرق والكباري
 4- Contractor : شركة منصور علي حسن للمقاولات
 5- Date : 13/5/2025
 6- Station : ST/ 311+000 to 313+200
 7- R-Code : 598

II. Sample description:

Gravel And Sand

III. Required tests and Results:*Table (1): Physical properties of soil*

1-Grain size analysis and classification and Percentage of Materials finer than No. 200 (75 μ m)	Grain size analysis	As showed in appendix
	Classification	A-1-a
	Pass No.200	11.7%
2- Modified compaction (Proctor test)	MDD	2.130
	OMC	6.5%
3- Liquid limit, plastic limit and plasticity index	LL	19.5
	PL	15.4
	PI	4.1
4- California bearing ratio (CBR)	CBR ratio	35%

IV. Notes:

- Samples were bought by: Contractor.
- Samples are responsible from the person who brought it.
- The results are applying only for the present report.

Geotechnical consultant

Dr. Mohamed Mostafa Badry



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

APPENDIX



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة


دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

**PARTICLE SIZE DISTRIBUTION
ANALYSIS
ASTM C-136 / AASHTO T27**

	WEIGHT RETAINED (gm)	CUMULATIVE WEIGHT RETAINED (gm)	CUMULATIVE PERCENTAGE RETAINED (%)	CUMULATIVE PERCENTAGE PASSING (%)	STANDARD SPECIFICATION LIMITS
2	240.00	240.00	2.40	97.6	
1 1/2	70.00	310.00	3.10	96.9	
1	1335.00	1645.00	16.45	83.6	
3/4	1095.00	2740.00	27.40	72.6	
1/2	1960.00	4700.00	47.00	53.0	
3/8	930.00	5630.00	56.30	43.7	
No.4	1200.00	6830.00	68.30	31.7	
No.10	66.00	66.00	13.20	27.5	
No.40	207.00	174.00	34.80	20.7	
No.200	348.00	316.00	63.20	11.7	

Total sample weight = 10000.00 pass No.4 = 3170.0 Total fine aggregates weight = 500 gm
% 31.7

**Soil classification: A - 1 - a**

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Modified Proctor Test Report ASTM - D 1557

Mould Number :- 2
Volume of mould = 2140 cm³
Weight of mould = 6220 g
G.S = 2.56 g/cm³


A- Density Calculations :-

	1	2	3	4	5
Weight of wet soil+mould (g)	10798	10953	11095	10988	10861
Weight of mould (g)	6220	6220	6220	6220	6220
Weight of wet soil (g)	4578	4733	4875	4768	4641
Volume of mould (cm ³)	2140	2140	2140	2140	2140
Wet density (g/cm ³)	2.139	2.212	2.278	2.228	2.169
Dry density (g/cm ³)	2.081	2.113	2.127	2.031	1.935
Zero-air Void curve			2.166	2.051	1.955

B- Moisture Calculations :-

Weight of wet soil+container (g)	250.0	250.0	250.0	250.0	250.0
Weight of dry soil+container (g)	244.4	240.8	236.2	231.8	227.9
Weight of container (g)	45.0	43.0	42.0	44.0	45.0
moisture content (%)	2.8	4.7	7.1	9.7	12.1

C - Dry density-Moisture relationship:-



M.D.D= 2.130 gm/cm³
O.M.C= 6.50 %



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات


الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Liquid and Plastic Limits Test
ASTM - D 4318

Test No	1	2	3	4	5	6
Type of test	Liquid Limit				Plastic Limit	
NO of B.	36	26	21	16		
Container No	a	b	c	d	F	J
Mass of wet soil + container	57.20	63.10	60.80	65.80	41.20	37.90
Mass of dry soil + container	55.80	60.20	58.20	61.50	39.40	36.50
Mass of container	43.80	44.80	45.80	45.30	28.70	26.50
Mass of moisture	1.40	2.90	2.60	4.30	1.80	1.40
Mass of dry soil	12.00	15.40	12.40	16.20	10.70	10.00
Moisture content	11.67	18.83	20.97	26.54	16.82	14.00

**Results:**

Liquid Limit (L.L) : 19.5 %.
Plastic Limit (P.L) : 15.4 %.
Plasticity Index (P.I): 4.1 %.



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

St(312+655)
600 mm Plate diameter
Point No.2

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.04
2	14.14	0.050	0.10
3	21.21	0.075	0.25
4	28.28	0.100	0.40
5	35.35	0.125	0.64
6	42.42	0.150	0.85
7	49.49	0.175	1.00
8	56.56	0.200	1.02
9	63.63	0.225	1.30
10	70.7	0.250	1.45
11	56.56	0.200	1.44
12	49.49	0.175	1.22
13	35.35	0.125	1.01
14	21.21	0.075	0.76
15	1.414	0.005	0.55

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.55
16	7.07	0.025	0.58
17	14.14	0.050	0.65
18	21.21	0.075	0.78
19	28.28	0.100	0.95
20	35.35	0.125	1.05
21	42.42	0.150	1.16
22	49.49	0.175	1.29
23	56.56	0.200	1.40
24	63.63	0.225	1.48

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0,MAX})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.168	0.005
a_1 (mm/(MN/m ²))	6.018	4.157
a_2 (mm/(MN ² /m ⁴))	1.880	1.235
$Ev = 1.5 r / (a_1 + a_2 \cdot \sigma_{0,MAX})$	69.36	98.23
$Ev2/Ev1$	1.42	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

● Measurement points from the first loading cycle

▲ Measurement points from the unloading cycle

■ Measurement points from the second loading cycle

S Settlement in mm

 σ_0 Normal stress MN/m²**Conclusions:**

The present test results which obtained from the plate loading tests on Crushed Aggregate Filter layer of the electric express train project at location St(312+655) in accordance to the German standard, DIN 18134 are illustrated in table 4.

Table 4 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
2-St(312+655)	69.36	98.23	1.42

Geotechnical Consultant

Dr. Mohamed Mostafa Badry

Dr / Mohamed Mostafa Badry



MATERIAL INSPECTION REQUEST



Contractor Company	MANSOUR ALI HASSAN		Designer Company	(KK)Engineering consulting office						
Issued by Contractor	Name	Sign	Date/ Serial Number	Time						
	Eng: MAHMOUD AYOUB		19-03-2025 (MNS- M.I.01)	12:00 PM						
Received by ER	Eng. Gaber Ibrahim	MIR	C1	C2	C3	DD	MM	YY	HH	MM
			313	EW	CS	19	03	25	12	00

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILTER Layer		
Location to be Used	From St (312+960) To st (313+120)		
MAR Approval No	(MNS- M.A-01)	Date	04-03-2025
Supplier Name	ELOROBA		
Test Requirement	PLT DIN (18134)	Specification	- EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.
Reference Photos	No	Other	

Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate Load Test	NUMBER	01	19-03-2025	
2					
3					
4					

Comments by : Ahmed Galal (GARB) 1- تم استلام القطاع Plate Load Test بواسطة معمل البديري 2- تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.	Comments by: Eng Gaber Ibrahim 1-P.L.T was carried- out by ALBADRY Lab attendance of material engineer for both contractor, GARB . 2-Results report attached and acceptable with project specifications. 3-Final approval is subject to above mentioned comments.
--	---

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mahmoud Ayoub			A
GARB** QA/QC*	Eng. Mostafa Khaled			A
GARB**	Eng. Ahmed Galal			A
Employers Representative	Eng. Gaber Ibrahim			A.W.C

* Designer

** Alignment / Bridges: Culvert Only

19-03-2025

ALBADRY CONSULTING

Geology Engineering and Quality Control
Dr. MOHAMED MOSTAFA BADRY
Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Technical report of Plate Loading Test (DIN 18134)

Project	:	ELECTRIC EXPRESS TRAIN
General Consultant	:	SYSTRA
Supervisor	:	الهيئة العامة للطرق والكباري
Contractor	:	شركة منصور علي حسن للمقاولات
Sample	:	Crushed Aggregate Filter
Station	:	St(313+040)
Date of Test	:	19/03/2025
R-Code	:	468



ALBADRY CONSULTING

Geology Engineering and Quality Control
Dr. MOHAMED MOSTAFA BADRY
Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

Introduction:

The Plate Load test is designed to determine the vertical deformation and strength characteristics of soil by assessing the force and amount of penetration with time when a rigid plate is made to penetrate the soil.

The test to be carried out on the native soil according to German specifications DIN 18134.

Test methods :

- 1- The German standard DIN 18134 was applied to define the apparatus used, the loading system, test conditions, and procedure for plate load test.
- 2- Loading plates with a diameter of 600 mm have a thickness of 25mm and are provided with equally spaced stiffeners with even upper faces parallel to the plate bottom face to allow 300 mm plate to be placed on top of it.
- 3- The loading system consisted of a hydraulic pump connected to a hydraulic jack of 700 bar capacity, which is capable of applying and releasing the load stages.
- 4- The dial gauge used to measure the plate settlement has a resolution of 0.01mm and the lever ratio was equal to 1.
- 5- The temperature at the time of the test was 25°.
- 6- The plate was carried out on a native soil (sand-gravel). The test surface area was levelled and the plate was bedded on this surface.
- 7- The hydraulic jack was placed on the middle of, and at normal to, the loading plate beneath the reaction loading system and secured against tilting.
- 8- The reaction loading system was a heavy multi-purpose excavator (more than 20 ton).

Description of experiment:

- 1- Loading, unloading and reloading regims were applied according to DIN 18134 for the plate load test to estimate the resilient modulus
- 2- Prior to the test, the force transducer and dial gauge were set to zero, after which a load was applied corresponding to a stress of 0.01 MN/m².
- 3- In the first loading cycle, the load was increased until a normal stress of 0.25 MN/m² was reached, and the loading increment was 0.025 MN/m². The load was released in four stages.
- 4- Following unloading, a further second loading cycle was carried out, in which, the load was increased only to the penultimate stage of the first cycle.



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

St(313+040)

600

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.08
2	14.14	0.050	0.17
3	21.21	0.075	0.31
4	28.28	0.100	0.50
5	35.35	0.125	0.73
6	42.42	0.150	0.87
7	49.49	0.175	1.02
8	56.56	0.200	1.21
9	63.63	0.225	1.40
10	70.7	0.250	1.54
11	56.56	0.200	1.53
12	49.49	0.175	1.52
13	35.35	0.125	1.47
14	21.21	0.075	1.33
15	1.414	0.005	0.72

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.72
16	7.07	0.025	0.81
17	14.14	0.050	0.88
18	21.21	0.075	0.98
19	28.28	0.100	1.11
20	35.35	0.125	1.19
21	42.42	0.150	1.27
22	49.49	0.175	1.38
23	56.56	0.200	1.44
24	63.63	0.225	1.56

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, \max})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.112	0.698
a_1 (mm/(MN/m ²))	6.065	4.034
a_2 (mm/(MN ² /m ⁴))	2.587	-1.128
$Ev = 1.5 r / (a_1 + a_2 \cdot \sigma_{0, \max})$	67.05	119.95
$Ev2/Ev1$	1.79	



ALBADRY CONSULTING

Geology Engineering and Quality Control
 Dr. MOHAMED MOSTAFA BADRY
 Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة
 دكتور استشاري/محمد مصطفى بدرى
 ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²

Conclusions:

The present test results which obtained from the plate loading tests on Crushed Aggregate Filter layer of the electric express train project at location St(313+040) in accordance to the German standard, DIN 18134 are illustrated in table 4.

Table 4 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
St(313+040)	67.05	119.95	1.79

Geotechnical Consultant
 Dr. MB
 Dr / Mohamed Mostafa Badry



MATERIAL INSPECTION REQUEST



Contractor Company	MANSOUR ALI HASSAN		Designer Company	(KK)Engineering consulting office						
Issued by Contractor	Name	Sign	Date/ Serial Number	Time						
	Eng: MAHMOUD AYOUB		21-04-2025 (MNS- M.I.09)	12:00 PM						
Received by ER	Eng. Gaber Ibrahim	MIR	C1	C2	C3	DD	MM	YY	HH	MM
			313	EW	CS	21	04	25	12	00

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL Layer		
Location to be Used	From St (312+930) To st (313+140) -1.5 FROM FERMA		
MAR Approval No	(MNS- M.A-04)	Date	13-04-2025
Supplier Name	Sewey FLORIBA SW & KER		
Test Requirement	PLT DIN (18134)	Specification	- EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.
Reference Photos	No	Other	

Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate Load Test	NUMBER	02	21-04-2025	
2					
3					
4					

Comments by : Ahmed Galal (GARB) 1- تم استلام القطاع Plate Load Test بواسطة معمل البدرى 2- تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.	Comments by: Eng Gaber Ibrahim 1-P.L.T was carried- out by ALBADRY Lab attendance of material engineer for both contractor, GARB . 2-Results report attached and acceptable with project specifications. 3-Final approval is subject to above mentioned comments.
---	---

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mahmoud Ayoub			A
GARB** QA/QC*	Eng. Mostafa Khaled			A
GARB**	Eng. Ahmed Galal			A
Employers Representative	Eng. Gaber Ibrahim			A.W.C

* Designer

** Alignment / Bridges: Culvert Only

21-04-2025

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Introduction:

The Plate Load test is designed to determine the vertical deformation and strength characteristics of soil by assessing the force and amount of penetration with time when a rigid plate is made to penetrate the soil.

The test to be carried out on the native soil according to German specifications DIN 18134.

Test methods :

- 1- The German standard DIN 18134 was applied to define the apparatus used, the loading system, test conditions, and procedure for plate load test.
- 2- Loading plates with a diameter of 600 mm have a thickness of 25mm and are provided with equally spaced stiffeners with even upper faces parallel to the plate bottom face to allow 300 mm plate to be placed on top of it.
- 3- The loading system consisted of a hydraulic pump connected to a hydraulic jack of 700 bar capacity, which is capable of applying and releasing the load stages.
- 4- The dial gauge used to measure the plate settlement has a resolution of 0.01mm and the lever ratio was equal to 1.
- 5- The temperature at the time of the test was 25°.
- 6- The plate was carried out on a native soil (sand-gravel). The test surface area was levelled and the plate was bedded on this surface.
- 7- The hydraulic jack was placed on the middle of, and at normal to, the loading plate beneath the reaction loading system and secured against tilting.
- 8- The reaction loading system was a heavy multi-purpose excavator (more than 20 ton).

Description of experiment:

- 1- Loading, unloading and reloading regims were applied according to DIN 18134 for the plate load test to estimate the resilient modulus
- 2- Prior to the test, the force transducer and dial gauge were set to zero, after which a load was applied corresponding to a stress of 0.01 MN/m².
- 3- In the first loading cycle, the load was increased until a normal stress of 0.25 MN/m² was reached, and the loading increment was 0.025 MN/m². The load was released in four stages.
- 4- Following unloading, a further second loading cycle was carried out, in which, the load was increased only to the penultimate stage of the first cycle.



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

St(312+970)

600

Point No.1

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.10
2	14.14	0.050	0.17
3	21.21	0.075	0.35
4	28.28	0.100	0.79
5	35.35	0.125	0.71
6	42.42	0.150	0.81
7	49.49	0.175	1.05
8	56.56	0.200	1.17
9	63.63	0.225	1.26
10	70.7	0.250	1.34
11	56.56	0.200	1.33
12	49.49	0.175	1.32
13	35.35	0.125	1.27
14	21.21	0.075	1.10
15	1.414	0.005	1.61

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	1.61
16	7.07	0.025	1.72
17	14.14	0.050	1.81
18	21.21	0.075	2.02
19	28.28	0.100	2.12
20	35.35	0.125	2.28
21	42.42	0.150	2.44
22	49.49	0.175	2.54
23	56.56	0.200	2.63
24	63.63	0.225	2.74

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{n,max}$) MN/m ²	0.250	0.250
n_0 (mm)	-0.152	1.561
a_1 (mm/(MN/m ²))	8.464	6.242
a_2 (mm/(MN ² /m ⁴))	-9.822	-4.195
$E_v = 1.5 \cdot r / (a_1 + a_2 \cdot \sigma_{n,max})$	74.89	86.65
E_v2/E_v1	1.16	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

St(313+070)

600

Point No.2

Table 4: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.13
2	14.14	0.050	0.22
3	21.21	0.075	0.49
4	28.28	0.100	0.73
5	35.35	0.125	1.04
6	42.42	0.150	1.17
7	49.49	0.175	1.94
8	56.56	0.200	1.75
9	63.63	0.225	1.93
10	70.7	0.250	1.99
11	56.56	0.200	1.98
12	49.49	0.175	1.90
13	35.35	0.125	1.76
14	21.21	0.075	1.14
15	1.414	0.005	0.72

Table 5: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.72
16	7.07	0.025	0.76
17	14.14	0.050	0.82
18	21.21	0.075	0.94
19	28.28	0.100	1.18
20	35.35	0.125	1.30
21	42.42	0.150	1.63
22	49.49	0.175	1.81
23	56.56	0.200	1.95
24	63.63	0.225	2.08

Table 6: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, max})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.326	0.634
a_1 (mm/(MN/m ²))	12.838	4.391
a_2 (mm/(MN ² /m ⁴))	-12.530	10.692
$Ev = 1.5 \sigma / (a_1 + a_2 \cdot \sigma_{0, max})$	46.36	63.71
$Ev2/Ev1$	1.37	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 2: Load-settlement curve, fitting curves according to Table 4 and Table 5 for the first and second loading cycles

- Measurment points from the first loading cycle
- Measurment points from the unloading cycle
- ▲ Measurment points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Conclusions:

The present test results which obtained from the plate loading tests of the native soil on Middle Embankment layer of the electric express train project at location St(312+950) to ST(313+140) in accordance to the German standard , DIN 18134 are illustrated in table 7.

Table 7 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
1- St(312+970)	74.89	86.65	1.16
1- St(313+070)	46.36	63.71	1.37

Geotechnical Consultant


 Dr / Mohamed Mostafa Badry


ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Technical report

of Plate Loading Test (DIN 18134)

Project	: ELECTRIC EXPRESS TRAIN
Owner	: الهيئة العامة للاتفاق / الهيئة العامة للطرق والكباري
General Consultant	: SYSTRA
Contractor	: شركة منصور علي حسن
Sample	: Middle Embankment
Station	: St(312+930) to (313 + 140)
Date of Test	: 21/04/2025
R-Code	: 525



MATERIAL INSPECTION REQUEST



Contractor Company	MANSOUR ALI HASSAN		Designer Company	(KK)Engineering consulting office						
Issued by Contractor	Name	Sign	Date/ Serial Number	Time						
	Eng: MAHMOUD AYOUB		19-05-2025 (MNS- M.I.025)	12:00 PM						
Received by ER	Eng. Gaber Ibrahim	MIR	C1	C2	C3	DD	MM	YY	HH	MM
			312	EW	CS	19	05	25	12	00

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Fill Layer				
Location to be Used	From St (312+920) To st (313+140) (Ferma)				
MAR Approval No	(MNS- M.A-09)	Date	13-05-2025		
Supplier Name	EL Sewy--SWEKAR				
Test Requirement	F.D.T(ASTM D 1556) PLT DIN 18134	Specification	- EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.		
Reference Photos	No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Sand Cone Test	NUMBER	129	18-05-2025	
2	Plate load test .	NUMBER	5	18-05-2025	
3					
4					
Comments by : Ahmed Galal (GARB)			Comments by: Eng Gaber Ibrahim		
1. تم استلام القطاع SAND CONE . 2. تم تحقيق نسبة الدمك المطلوبة . 3. تم اجراء اختبار PLT بواسطة معمل البدري . 4. تم تحقيق النتائج المطلوبة طبقا لمواصفات المشروع . توقيع احمال			1-F.D.T and P.L.T was carried- out by ALBADRY Lab AND matrial engineer for both contractor, GARB engineer . 2-Results report attached and acceptable with project specifications. 3-Final approval is subject to above mentioned comments.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mahmoud Ayoub			A
GARB** QA/QC*	Eng. Mostafa Khaled			A
GARB**	Eng. Ahmed Galal			A
Employers Representative	Eng. Gaber Ibrahim			A.W.C

* Designer

** Alignment / Bridges: Culvert Only

19-05-2025

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Technical report

of Plate Loading Test (DIN 18134)

Project : ELECTRIC EXPRESS TRAIN
Owner : الهيئة العامة للاتفاق / الهيئة العامة للطرق والكباري
General Consultant : SYSTRA
Contractor : شركة منصور علي حسن
Sample : Upper Embankment (Ferma)
Station : St(312+920) to (313 + 140)
Date of Test : 19/05/2025
R-Code : 620-2



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Introduction:

The Plate Load test is designed to determine the vertical deformation and strength characteristics of soil by assessing the force and amount of penetration with time when a rigid plate is made to penetrate the soil.
The test to be carried out on the native soil according to German specifications DIN 18134.

Test methods :

- 1- The German standard DIN 18134 was applied to define the apparatus used, the loading system, test conditions, and procedure for plate load test.
- 2- Loading plates with a diameter of 600 mm have a thickness of 25mm and are provided with equally spaced stiffeners with even upper faces parallel to the plate bottom face to allow 300 mm plate to be placed on top of it.
- 3- The loading system consisted of a hydraulic pump connected to a hydraulic jack of 700 bar capacity, which is capable of applying and releasing the load stages.
- 4- The dial gauge used to measure the plate settlement has a resolution of 0.01mm and the lever ratio was equal to 1.
- 5- The temperature at the time of the test was 25°.
- 6- The plate was carried out on a native soil (sand-gravel). The test surface area was levelled and the plate was bedded on this surface.
- 7- The hydraulic jack was placed on the middle of, and at normal to, the loading plate beneath the reaction loading system and secured against tilting.
- 8- The reaction loading system was a heavy multi-purpose excavator (more than 20 ton).

Description of experiment:

- 1- Loading, unloading and reloading regims were applied according to DIN 18134 for the plate load test to estimate the resilient modulus
- 2- Prior to the test, the force transducer and dial gauge were set to zero, after which a load was applied corresponding to a stress of 0.01 MN/m².
- 3- In the first loading cycle, the load was increased until a normal stress of 0.25 MN/m² was reached, and the loading increment was 0.025 MN/m². The load was released in four stages.
- 4- Following unloading, a further second loading cycle was carried out, in which, the load was increased only to the penultimate stage of the first cycle.



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

St(312+930)
600 mm Plate diameter
Point No.1

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.02
2	14.14	0.050	0.06
3	21.21	0.075	0.25
4	28.28	0.100	0.45
5	35.35	0.125	0.55
6	42.42	0.150	0.75
7	49.49	0.175	0.87
8	56.56	0.200	1.00
9	63.63	0.225	1.15
10	70.7	0.250	1.30
11	56.56	0.200	1.19
12	49.49	0.175	1.08
13	35.35	0.125	0.85
14	21.21	0.075	0.70
15	1.414	0.005	0.50

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.50
16	7.07	0.025	0.52
17	14.14	0.050	0.61
18	21.21	0.075	0.85
19	28.28	0.100	0.95
20	35.35	0.125	1.08
21	42.42	0.150	1.19
22	49.49	0.175	1.26
23	56.56	0.200	1.44
24	63.63	0.225	1.59

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{0,max}$) MN/m ²	0.250	0.250
a_0 (mm)	0.178	0.178
a_1 (mm/(MN/m ²))	6.023	6.023
a_2 (mm/(MN ² /m ⁴))	-0.424	-0.424
$E_v = 1.5 \pi / (a_1 + a_2 \cdot \sigma_{0,max})$	76.05	76.05
E_{v2}/E_{v1}		1.16



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

St(312+980)
600 mm Plate diameter
Point No.2

Table 4: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.05
2	14.14	0.050	0.14
3	21.21	0.075	0.40
4	28.28	0.100	0.70
5	35.35	0.125	0.90
6	42.42	0.150	1.15
7	49.49	0.175	1.37
8	56.56	0.200	1.59
9	63.63	0.225	1.80
10	70.7	0.250	2.00
11	56.56	0.200	1.68
12	49.49	0.175	1.55
13	35.35	0.125	1.20
14	21.21	0.075	0.88
15	1.414	0.005	0.50

Table 5: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.50
16	7.07	0.025	0.52
17	14.14	0.050	0.72
18	21.21	0.075	1.05
19	28.28	0.100	1.18
20	35.35	0.125	1.80
21	42.42	0.150	1.48
22	49.49	0.175	1.58
23	56.56	0.200	1.70
24	63.63	0.225	1.78

Table 6: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{0,max}$) MN/m ²	0.250	0.250
a_0 (mm)	-0.254	0.311
a_1 (mm/(MN/m ²))	9.430	12.124
a_2 (mm/(MN ² /m ⁴))	-1.334	-25.264
$E_v = 1.5 \tau / (a_1 + a_2 \cdot \sigma_{0,max})$	49.47	77.40
E_{v2}/E_{v1}	1.56	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 2: Load-settlement curve, fitting curves according to Table 4 and Table 5 for the first and second loading cycles

- Measurment points from the first loading cycle
- Measurment points from the unloading cycle
- Δ Measurment points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

St(313+030)
600 mm Plate diameter
Point No.3

Table 7: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.07
2	14.14	0.050	0.15
3	21.21	0.075	0.38
4	28.28	0.100	0.67
5	35.35	0.125	0.95
6	42.42	0.150	1.25
7	49.49	0.175	1.45
8	56.56	0.200	1.60
9	63.63	0.225	1.70
10	70.7	0.250	1.95
11	56.56	0.200	1.74
12	49.49	0.175	1.56
13	35.35	0.125	1.38
14	21.21	0.075	1.10
15	1.414	0.005	0.88

Table 8: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (s_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.88
16	7.07	0.025	0.90
17	14.14	0.050	1.10
18	21.21	0.075	1.35
19	28.28	0.100	1.50
20	35.35	0.125	1.59
21	42.42	0.150	1.70
22	49.49	0.175	1.85
23	56.56	0.200	1.95
24	63.63	0.225	2.05

Table 9: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, \max})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.310	0.786
a_1 (mm/(MN/m ²))	11.053	7.895
a_2 (mm/(MN ² /m ⁴))	-8.003	-3.627
$E_v = 1.5 \text{ } r / (a_1 + a_2 \cdot \sigma_{0, \max})$	49.71	33.51
E_{v2}/E_{v1}	1.68	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 3: Load-settlement curve, fitting curves according to Table 7 and Table 8 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

St(313+080)
600 mm Plate diameter
Point No.4

Table 10: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.05
2	14.14	0.050	0.14
3	21.21	0.075	0.40
4	28.28	0.100	0.70
5	35.35	0.125	0.90
6	42.42	0.150	1.15
7	49.49	0.175	1.37
8	56.56	0.200	1.16
9	63.63	0.225	1.80
10	70.7	0.250	2.00
11	56.56	0.200	1.57
12	49.49	0.175	1.35
13	35.35	0.125	1.14
14	21.21	0.075	0.75
15	1.414	0.005	0.50

Table 11: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.50
16	7.07	0.025	0.52
17	14.14	0.050	0.75
18	21.21	0.075	1.05
19	28.28	0.100	1.18
20	35.35	0.125	1.30
21	42.42	0.150	1.48
22	49.49	0.175	1.58
23	56.56	0.200	1.70
24	63.63	0.225	1.78

Table 12: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, \max})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.190	0.383
a_1 (mm/(MN/m ²))	8.189	9.049
a_2 (mm/(MN ² /m ⁴))	1.279	-12.746
$Ev = 1.5 \text{ r} / (a_1 + a_2 \cdot \sigma_{0, \max})$	52.88	75.78
$Ev2/Ev1$	1.43	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107

**مكتب البدرى للاستشارات**

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري / محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 4: Load-settlement curve, fitting curves according to Table 10 and Table 11 for the first and second loading cycles

- Measurment points from the first loading cycle
- Measurment points from the unloading cycle
- ▲ Measurment points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

St(313+130)
600 mm Plate diameter
Point No.5

Table 13: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.18
2	14.14	0.050	0.28
3	21.21	0.075	0.44
4	28.28	0.100	0.57
5	35.35	0.125	0.70
6	42.42	0.150	0.85
7	49.49	0.175	0.98
8	56.56	0.200	1.10
9	63.63	0.225	1.19
10	70.7	0.250	1.29
11	56.56	0.200	1.17
12	49.49	0.175	1.00
13	35.35	0.125	0.88
14	21.21	0.075	0.67
15	1.414	0.005	0.18

Table 14: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.17
16	7.07	0.025	0.37
17	14.14	0.050	0.52
18	21.21	0.075	0.78
19	28.28	0.100	0.90
20	35.35	0.125	1.03
21	42.42	0.150	1.10
22	49.49	0.175	1.20
23	56.56	0.200	1.23
24	63.63	0.225	1.30

Table 15: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{0, \max}$) MN/m ²	0.250	0.250
a_0 (mm)	-0.190	0.128
a_1 (mm/(MN/m ²))	8.189	9.677
a_2 (mm/(MN ² /m ⁴))	1.279	-7.26
$E_v = 1.5 \, r / (a_1 + a_2 \cdot \sigma_{0, \max})$	52.88	97.58
E_v2/E_v1	1.85	



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧




Fig. 5: Load-settlement curve, fitting curves according to Table 13 and Table 14 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- △ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Field Density Test

Project : Electric Express Train
 Owner : الهيئة العامة للانفاق / الهيئة العامة للطرق والكباري
 General Consultant : SYSTRA
 Contractor : شركة منصور علي حسن للمقاولات
 Section : St(312+920) to St(313+140)
 Sample : Upper Embankment (Ferma)
 Date of test : 19-05-2025
 R-Code : 621-1

Unit weight of sand: 1.54

Station	St(312+935)	St(312+960)	St(312+985)	St(313+010)	St(313+035)	St(313+060)
Sample No.	1	2	3	4	5	6
Wt. Of Wet Soil	3321	2763	2750	3074	2873	2672
Wt. Of Sand used + Cone	10342	10159	9851	9142	8006	7956
Wt. Of residual sand + Cone	6833	7014	6687	5788	4798	4845
Wt. Of sand to fill cone	1200	1200	1200	1200	1200	1200
Wt. Of sand to fill Hole	2309	1945	1964	2154	2008	1911
Cross Vol Of hole	1499	1263	1275	1399	1304	1241
Wt Unit Of Soil	2.21	2.19	2.16	2.20	2.20	2.15
Dry Unit Wt Of Soil	2.10	2.08	2.06	2.10	2.08	2.05

MOISTURE CONTENT:

Bottle No.	1	2	3	4	5	6
Wt Of wet soil + bottle	250.0	250.0	250.0	250.0	250.0	250.0
Wt Of dry soil + bottle	239.5	240.3	241.1	240.8	238.9	240.5
Wt Of bottle	45.0	45.0	45.0	45.0	45.0	45.0
Wt Of dry soil	194.5	195.3	196.1	195.8	193.9	195.5
Wt Of moisture	10.5	9.7	8.9	9.2	11.1	9.5
Moisture content	5.4	5.0	4.5	4.7	5.7	4.9

COMPACTION TEST:

Max dry density	2.130	2.130	2.130	2.130	2.130	2.130
Optimum MC	6.5	6.5	6.5	6.5	6.5	6.5
% Compaction	98.7	97.8	96.8	98.6	97.8	96.3
required Compaction	95	95	95	95	95	95

Geotechnical Consultant

Dr. Mohamed Mostafa El badry

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧ / ٠١٠٩٠٦٦٥٠٩٧

Field Density Test

Project :Electric Express Train
 Owner : الهيئة العامة للاتفاق / الهيئة العامة للطرق والكباري
 General Consultant :SYSTRA
 Contractor :شركة منصور علي حسن للمقاولات
 Section :St(312+920) to St(313+140)
 Sample :Upper Embankment (Ferma)
 Date of test :19-05-2025
 R-Code :621-2 Unit weight of sand: 1.54

Station	St(313+085)	St(313+110)	St(313+135)
Sample No.	7	8	9
Wt.Of Wet Soil	3015	2648	2847
Wt.Of Sand used + Cone	7910	7718	10573
Wt.Of residual sand + Cone	4618	4678	7388
Wt.Of sand to fill cone	1200	1200	1200
Wt.Of sand to fill Hole	2092	1840	1985
Cross Vol Of hole	1358	1195	1289
Wt Unit Of Soil	2.22	2.22	2.21
Dry Unit Wt Of Soil	2.09	2.10	2.08

MOISTURE CONTENT:

Bottle No.	7	1	2
Wt Of wet soil + bottle	250.0	250.0	250.0
Wt Of dry soil + bottle	238.1	239.4	237.8
Wt Of bottle	45.0	45.0	45.0
Wt Of dry soil	193.1	194.4	192.8
Wt Of moisture	11.9	10.6	12.2
Moisture content	6.2	5.5	6.3

COMPACTION TEST:

Max dry density	2.130	2.130	2.130
Optimum MC	6.5	6.5	6.5
% Compaction	98.2	98.7	97.5
required Compaction	95	95	95



Geotechnical Consultant

Dr. Mohamed Mostafa El badry

ALBADRY CONSULTING

Geology Engineering and Quality Control

Dr. MOHAMED MOSTAFA BADRY

Phone.tel: 01090665097/01100214107



مكتب البدرى للاستشارات

الجيولوجية والهندسية وضبط الجودة

دكتور استشاري/محمد مصطفى بدرى

ت: ٠١١٠٠٢١٤١٠٧/٠١٠٩٠٦٦٥٠٩٧

Conclusions:

The present test results which obtained from the plate loading tests on Upper Embankment layer of the electric express train project at location St(312+920) to (313 + 140) in accordance to the German standard , DIN 18134 are illustrated in table 16.

Table 16 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
1- St(312+930)	76.05	88.42	1.16
2- St(312+980)	49.47	77.40	1.56
3- St(313+030)	49.71	83.51	1.68
4- St(313+080)	52.88	75.78	1.43
5- St(313+130)	52.88	97.58	1.85

Geotechnical Consultant

Dr / Mohamed Mostafa Badry

