

القطار الكهربائي السريع

المنطقة الخامسة - غرب الدلتا

(الاسكندرية - مرسى مطروح)

السيد المهندس / رئيس قطاع التنفيذ و المناطق

تحية طيبة وبعد ،،،

بالإحالة إلي مشروع القطار الكهربائي السريع القطاع الرابع (قطاع وادي النطرون/برج العرب/الاسكندرية).

نتشرف بأن نرسل لسيادتكم المقايضة المعدلة لبنود أعمال الجسر الترابي للخط الأول لمشروع القطار الكهربائي السريع (العين السخنة - العاصمة الإدارية - العلمين - مطروح) قطاع (وادي النطرون / برج العرب) أعمال الردم لتنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر).

تنفيذ : "شركة أورانج للاستيراد والتصدير" .

وذلك طبقاً للأسعار بعد المفاوضة.

برجاء من سيادتكم التفضل بالموافقة والتوجيه بالازم.

و تفضلوا بقبول فائق الاحترام ،،،

أصه

رئيس الإدارة المركزية

منطقة غرب الدلتا

الاسكندرية - مرسى مطروح

عبد مهندس /

"هاني محمد محمود طه"

المقايمة المعدلة لبنود الاعمال لعملية
استلاد اعمال الجسر الثرابي للقط الاول لمشروع القطر الكهربائي السريع (العين المنقطة - العاصمة الإدارية - العلمين - مطروح)
قطاع (وادي النطرون / برج العرب) اعمال الرمد لتنفيذ المسئلة من الكم ٣٠٩,٨٠٠ الى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر)
عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)
تنفيذ "شركة أورانج للاستيراد والتصدير"

رقم البند	بيان الأعمال	الوحدة	الكمية	القيمة	الاجملى
١	اعمال الرمد				
١-١	بالمتر المكعب اعمال تحميل وتوريد ونقل اترية مطابقة للمواصفات وتشغيلها باستخدام الات التسوية بسمك لا يزيد عن ٥٠ سم حتى منسوب ٢- متر وبسمك لا يزيد عن ٢٥ سم لاستكمال المنسوب التصميمي لتشكل الجسر والاكتاف (نسبه تحمل كاليفورنيا لا تقل عن ١٥%) ورشها بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى أقصى كثافة جافة (٩٥%) من الكثافة الجافة القصوى) ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقا لأصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندسين المشرفين. - في حالة طلب جهاز الاشراف زيادة نسبة الدمك عن ٩٥% بحسب زيادة ١ جنيه على زيادة نسبة الدمك لكل ١%. - مسافة النقل حتى ٢ كم ويتم حساب علاوة ١,٤ جنيه لكل ١ كم بالزيادة او النقصان. - السعر يشمل عدل تشوينات وتخليط واختبارات ونقل لموقع العمل حتى مسافة ٢ كم. - السعر يشمل قيمة المادة المحجرية				
	السعر خلال شهر مايو طبقاً للمفاوضة بتاريخ ٢٠٢٣-١٢-١٨	م	٣٣١٠٠٠٠	١١٧,٥٠	٣,٨٨٩,٢٥٠
	علاوة مسافة النقل ١٤١ كم	م	٢٦٤٨٠٠٠	١٩٤,٦٠	٥,١٥٣,٠٠٨
	علاوة مسافة النقل ١٣٩ كم	م	٥٨٤٥٠٠	١٩١,٨٠	١,١٢١,٠٧١
	علاوة مسافة النقل ١٠٦ كم	م	٧٧٥٠٠	١٤٥,٦٠	١١٢,٨٤٠
	علاوة تحصيل رسوم الكارثة والموازين طبقاً للاتحة الشركة الوطنية	م	٣٣١٠٠٠٠	١٣,٠٠	٤٣٠,٣٠٠
	الاجملى				١٠,٧٠٦,٤٦٩
	عشرة ملايين وسبعمائة وستة ألفاً وأربعمائة وتسعة وستون جنيهاً فقط لا غير.				
	* يرجى العلم بان الفئات المذكورة طبقاً للمفاوضة الخاصة بالقطاع الرابع بتاريخ ٢٠٢٣-١٢-١٨				

الهيئة العامة للطرق والكباري
مدير عام المشروعات
م/ محمد حسني فياض

الهيئة العامة للطرق والكباري
مدير المشروع
م/ أحمد جلال عبد السلام
أحمد جلال

المكتب الاستشاري الهندسي ا.د خالد قنديل
مدير المشروع
م/ هشام محمد صبري

الشركة المنفذة
مدير المشروع
م/ محمد فتحي القوي

رئيس الإدارة المركزية
منطقة غرب الدلتا
الاسكندرية - مرسى مطروح
عصيدة مهندس /
هاني محمد محمود طه



محضر استلام موقع عملية

العملية:

اسناد أعمال الجسر الترابي للخط الأول لمشروع القطار الكهربائي السريع (العين السخنة - العاصمة الإدارية - العلمين - مطروح) قطاع (وادي النطرون / برج العرب) أعمال الردم لتنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر).

تنفيذ: شركة "أورانج للاستيراد والتصدير"

استشاري المشروع: المكتب الاستشاري الهندسي (أ.د/خالد قنديل)

إشراف: المنطقة الخامسة - منطقة غرب الدلتا

طبقاً للعقد رقم (١٧١٩-٢٠٢٣-٢٠٢٤) بتاريخ (٢٦/٠٦/٢٠٢٤)

أنه في يوم السبت الموافق ٢٠٢٤/٠٧/٢٠ اجتمع كل من:

- | | |
|---|---|
| ١- السيد المهندس / محمد حسني فياض | مدير عام المشروعات - الهيئة العامة للطرق والكباري |
| ٢- السيد المهندس / أحمد جلال عبد السلام | مهندس العملية - الهيئة العامة للطرق والكباري |
| ٣- السيد المهندس / هشام محمد صبري | استشاري المشروع (أ.د خالد قنديل) |
| ٤- السيد المهندس / محمد فتحي الغول | مدير مشروع - شركة أورانج للاستيراد والتصدير |

وذلك للمرور على مسار العملية المذكورة عالية لاستلام الموقع.

وقد تبين أن الموقع خالي من العوائق الظاهرية ويسمح بالبدء في التنفيذ وبناء عليه يعتبر تاريخ ٢٠٢٤/٠٧/٢٠ هو تاريخ استلام الموقع وبدء أعمال الإشراف بالعملية.

واقفل المحضر علي ذلك ووقع الحضور.

التوقيعات:

رئيس الإدارة المركزية
منطقة غرب الدلتا
الاسكندرية - مرسى مطروح
صيد مهندس /
"هاني محمد محمود طه"

٤-
٣-
٢-
١-

قائمة الكميات الواردة بالمستخلص جاري (١)

اسناد أعمال الجسر الترابي للخط الأول لمشروع القطر الكهربائي السريع
(العين السفلى - العاصمة الإدارية - العامين - مطروح)
قطاع (وادي النطرون / برج العرب) أعمال الردم
لتنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر)

بند (١-١):

بالمتر المكعب أعمال تحميل وتوريد ونقل اترية مطابقة للمواصفات وتشغيلها باستخدام الات التسوية بسمك لا يزيد عن ٥٠ سم حتى منسوب -٢ متر ويسمك لا يزيد عن ٢٥ سم لاستكمال المنسوب التصميمي لتشكيل الجسر والاكتاف (نسبه تحمل كاليفورنيا لا تقل عن ١٥%) ورشها بالمياه الاصولية للوصول إلى نسبة الرطوبة المطلوبة والدمك الجيد بالهراست للوصول إلى أقصى كثافة جافة (95% من الكثافة الجافة القصوى) ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقا لأصول الصناعة ومواصفات الهيئة العامة للمطرق والكباري وتعليمات المهندس المشرف.

- في حالة طلب جهاز الاشراف زيادة نسبة الدمك عن ٩٥% بحسب زيادة ١ جنيه على زيادة نسبة الدمك لكل ١%.

- مسافة النقل حتى ٢ كم ويتم حساب علاوة ١,٤ جنيه لكل ١ كم بالزيادة او النقصان.

- السعر يشمل عمل تشوينات وتخليط واختبارات ونقل لموقع العمل حتى مسافة ٢ كم.

- السعر يشمل قيمة المادة المحجيرة.

تنفيذ : "شركة أورانج للاستيراد والتصدير"

عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)

مقدار العمل السابق :		٣م	٠,٠
مستعمل	الموقع الكيلومتری		الكمية (م٣)
	من الكم	إلى الكم	
١	٣٠٩+٨٠٠	٣٠٩+٩٥٠	٨٨٤٣,٧٨
٢	٣١٠+٠١٠	٣١٠+١٨٠	١٣٠٨٧,٢٢
الإجمالي خلال فترة المستخلص الحالية (٣م)			٢١٩٣١,٠٠
الإجمالي الكلي (م٣)			٢١٩٣١,٠٠

مهندس الهيئة
م / أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري
مكتب أ.د/ خالد قنديل
م / هشام محمد صبري

مكتب الاستشاري الهندسي
KK
مدير المشروع: م / هشام محمد صبري
مشروع: القطر الكهربائي السريع
القطاع الرابع (الإسكندرية)

مهندس الاستشاري
مكتب XYZ
م / هبة خليل

مشروع القطر الكهربائي السريع
القطاع الرابع (الإسكندرية)

مهندس الشركة
م / محمد فهد فغول

أورانج للإستيراد والتصدير
ORANGE CO
EXPORT & IMPORT
٢٠٢٤/٢٠٢٣/١٧١٩

قائمة الكميات الواردة بالمستخلص جاري (١)

اسناد اصال الجسر الترابي للخط الأول لمشروع القطار الكهربائي السريع
(العين المسقنة - العاصمة الإدارية - العطين - مطروح)
قطاع (وادي النطرون / برج العرب) أعمال الردم
لتنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر)


علاوة بند (١-١) علاوة مسافة النقل ١٤١ كم .

تنفيذ : "شركة أورانج للاستيراد والتصدير"
عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)

مقدار العمل السابق :		٠,٠	٣م
مسلسل	الموقع الكيلومتری		الكمية (م٣)
	من الكم	إلى الكم	
١	٣٠٩+٨٠٠	٣٠٩+٩٥٠	٧٠٧٥,٠٢
٢	٣١٠+٠١٠	٣١٠+١٨٠	١٠٤٦٩,٧٨
الإجمالي خلال فترة المستخلص الحالية (م٣)			١٧٥٤٤,٨٠
الإجمالي الكلي (م٣)			١٧٥٤٤,٨٠

مهندس الهيئة
م / أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري
مكتب أ.د/ خالد فتدیل
م / هشام محمد صبري



مهندس الشركة
م / محمد فتحي فتوح



قائمة الكميات الواردة بالمستخلص جاري (١)

إسناد أعمال الجسر الترابي للخط الأول لمشروع القطر الكهربائي السريع
(العين السفينة - العاصمة الإدارية - العلمين - مطروح)
قطاع (ولاي التطرون / برج العرب) أعمال الردم
تنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر)

علاوة بند (١-١) علاوة مسافة النقل ١٠٦ كم .

تنفيذ : "شركة أورانج للاستيراد والتصدير"
عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)

مقدار العمل السابق :		٠,٠	٣م
مسلم	الموقع الكيلومتری		الكمية (م٣)
	من الكم	إلى الكم	
١	٣١٠+٠١٠	٣١٠+١٨٠	٧٧٠,٨٢
الاجمالي خلال فترة المستخلص الحالية (م٣)			٧٧٠,٨٢
الاجمالي الكلي (م٣)			٧٧٠,٨٢

مهندس الهيئة
م / أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري
مكتب أ.د/ خالد قنديل
م / هشام محمد صبري

مهندس الاستشاري
مكتب XYZ
م / أحمد خليل
م / هشام محمد صبري

مهندس الشركة
م / محمد فتحي الطويل
م / هشام محمد صبري

مهندس الشركة
م / محمد فتحي الطويل
م / هشام محمد صبري

قائمة الكميات الواردة بالمستخلص جاري (١)

استناد أعمال الجسر الترابي للخط الأول لمشروع القطار الكهربائي السريع
(العين السخنة - العاصمة الإدارية - الطعين - مطروح)
قطاع (وادي التطرون / برج العرب) أعمال الردم
لتنفيذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٤٢٠ كم (بالأمر المباشر)

علاوة بند (١-١) علاوة مسافة النقل ١٣٩ كم .

تنفيذ : "شركة أورانج للاستيراد والتصدير"
عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)

مقدار العمل السابق :		٠,٠	٣م
متسلسل	الموقع الكيلومتری		الكمية (م٣)
	من الكم	إلى الكم	
١	٣٠٩+٨٠٠	٣٠٩+٩٥٠	١٧٦٨,٧٦
٢	٣١٠+٠١٠	٣١٠+٦٧٠	١٨٤٦,٦٢
الاجمالي خلال فترة المستخلص الحالية (م٣)			٣٦١٥,٣٨
الاجمالي الكلي (م٣)			٣٦١٥,٣٨

مهندس الهيئة
م / أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري
مكتب أ/د/ خالد فتدیل
م / هشام محمد صبري

مهندس الاستشاري
مكتب XYZ
م / أحمد خليل
أحمد خليل

مهندس الشركة
م / محمد فتحي الغول
محمد فتحي الغول

أورانج للاستيراد والتصدير
ORANGE CO
EXPORT & IMPORT
٢٠٢٣/١١/٢٢

قائمة الكميات الواردة بالمستخلص جاري (١)

اسناد أعمال الجسر الترابي للخط الأول لمشروع القطار الكهربائي السريع
(العين السفينة - العاصمة الإدارية - العلمين - مطروح)
قطاع (وادي التطرون / برج العرب) أعمال الردم
لتفليذ المسافة من الكم ٣٠٩,٨٠٠ إلى الكم ٣١٠,٢٢٠ بطول ٠,٤٢٠ كم (بالأمر المباشر)

علاوة بند (١-١) علاوة تحصيل رسوم الكارثة والموازن طبقا للاحقة الشركة الوطنية.

تفليذ : "شركة أورانج للاستيراد والتصدير"
عقد رقم (٢٠٢٤/٢٠٢٣/١٧١٩)

مقدار العمل السابق :		٠,٠	٣م
مبلس	الموقع الكيلومتری		الكمية (م٣)
	من الكم	إلى الكم	
١	٣٠٩+٨٠٠	٣٠٩+٩٥٠	٨٨٤٣,٧٨
٢	٣١٠+٠١٠	٣١٠+١٨٠	١٣٠٨٧,٢٢
الإجمالي خلال فترة المستخلص الحالية (م٣)			٢١٩٣١,٠٠
الإجمالي الكلي (م٣)			٢١٩٣١,٠٠

مهندس الهيئة
م / أحمد جلال عبد السلام
أحمد جلال

مهندس الاستشاري
مكتب أ.د/ خالد قنديل
م / هشام محمد صيري

مهندس الاستشاري
مكتب XYZ
م / أحمد خليل

مهندس الشركة
م / محمد فتحى القبول

أورانج للاستيراد والتصدير
ORANGE
EXPORT&IMPORT
٢٠٢٤/٢٠٢٣/١٧١٩



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypton General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egypton Accreditation council (EGAC) under No. 031706/1A

SOIL REPORTS FOR ELECTRIC EXPRESS TRAIN PROJECT

Contractor : شركة أورنج للإستيراد والتصدير والمقاولات العامة
Date : 25/09/2023
QC : 1987-2

Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email : civdept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egypt Accreditation council (EGAC) under No. 031706/1A

I- Introduction

General Consultant : SYSTRA
Consultant : DR/Khaled Kandil
Contractor : شركة أورنج للإستيراد والتصدير والمقاولات العامة
Sample : FERMA
Station : St(308+700)
Date of Test : 19/09/2023
QC : 1987-2

II- Sample description:

Gravel and sand

III- Required tests and Results

Required Tests		Results
1- Grain size analysis and classification	Grain size analysis	As showed in appendix
	Classification	A-1-a
2- Modified compaction (Proctor test)	MDD	2.049
	OMC	9.5%
3- Liquid limit, plastic limit and plasticity index	LL	NP
	PL	NP
	PI	NP
4- California bearing ratio (CBR)	CBR ratio	47%

IV- Notes

- 1- Samples were brought by : Consultant.
- 2- Samples are responsible from the Person who brought it.
- 3- The results are applying only for the present report.

LAB DIRECTOR

Eng / Eman kandil



Geotechnical consultant

Dr. Mohamed Mostafa Badry

Kilo 23 Alexandria - Cairo Desert Road - Merghem

Tel: 002 03 4704595 - 002 034701191

Email : civdept@comibassal.com

WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt

Tel: 002 033920176 - 002 033931482

Fax : 002 033900476

Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egyptian Accreditation council (EGAC) under No. 031706/1A

APPENDIX

Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email : ciddept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector


Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egypt Accreditation council (EGAC) under No. 031706/1A

PARTICLE SIZE DISTRIBUTION ANALYSIS ASTM C-136 / AASHTO T27

	WEIGHT RETAINED (gm)	CUMULATIVE WEIGHT RETAINED (gm)	CUMULATIVE PERCENTAGE RETAINED (%)	CUMULATIVE PERCENTAGE PASSING (%)	STANDARD SPECIFICATION LIMITS
2	0.00	0.00	0.00	100.0	
1 1/2	108.00	108.00	2.16	97.8	
1	235.00	343.00	6.87	93.1	
3/4	165.00	508.00	10.17	89.8	
1/2	475.00	983.00	19.68	80.3	
3/8	467.00	1450.00	29.03	71.0	
No.4	984.00	2434.00	48.74	51.3	
No.10	141.00	141.00	14.10	44.0	
No.40	410.00	410.00	41.00	30.2	
No.200	761.00	761.00	76.10	12.3	

Total sample weight = 4994.00 pass No.4 = 2560.0 Total fine aggregates weight = 1000 gm
% 51.3

Size analysis distribution curve



Soil classification: A - 1 - a Sample is non plastic



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email: civdept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egyptian Accreditation council (EGAC) under No. 031706/1A

Modified Proctor Test Report

ASTM - D 1557

Mould Number :- 2
Volume of mould = 2180 cm³
Weight of mould = 5895 g
G.S = 2.65 g/cm³


A- Density Calculations :-

	1	2	3	4	5
Weight of wet soil+mould (g)	10266	10730	10787	10635	10530
Weight of mould (g)	5895	5895	5895	5895	5895
Weight of wet soil (g)	4371	4835	4892	4740	4635
Volume of mould (cm ³)	2180	2180	2180	2180	2180
Wet density (g/cm ³)	2.005	2.218	2.244	2.174	2.126
Dry density (g/cm ³)	1.898	2.041	2.020	1.906	1.824
Zero-air Void curve			2.065	1.946	1.856

B- Moisture Calculations :-

Weight of wet soil+container (g)	250.0	250.0	250.0	250.0	250.0
Weight of dry soil+container (g)	240.0	235.0	228.0	223.0	219.0
Weight of container (g)	63.0	62.0	30.0	31.0	32.0
moisture content(%)	5.6	8.7	11.1	14.1	16.6

C - Dry density-Moisture relationship:-



MOISTURE CONTENT(%)

M.D.D= 2.049 gm/cm³
O.M.C= 9.5 %



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email: civdept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax :002 033900476
Email : internal-inspection@comibassal.com




COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egypt Accreditation council (EGAC) under No. 031706/1A

Report Of CBR Test - ASTM - D 1883

NO OF BLOWS	56				
MOULD NO	2				
WT OF MOULD+SOIL	10101				
WT OF MOULD	5207				
WT OF SOIL	4894				
VOLUME OF MOULD	2180				
WET DENSITY	2.245				
MC before soaking		Weight of Rammer		4.54Kg	
TIN NO	1			MDD	Kg/m3 2.049
WT OF WET SOIL+TIN	227.70			OMC	% 9.500
WT OF DRY SOIL+TIN	210				
WT OF WATER	17.70				
WT OF TIN	23				
WT OF DRY SOIL	187				
MOISTURE CONTENT	9.5				
DRY DENSITY	2.051			Capacity (KN)	50
Pen	Reading (Div)		Bearing (KN)		CBR
mm	56		56		standar 56
0.00	0		0.0		0.0
0.64	53		0.5		4.5
1.27	210		2.1		8.5
1.91	295		2.9		12.0
2.54	440		4.3		14.5 33
3.17	590		5.8		16.3
3.81	695		6.8		18.0
4.45	820		8.0		19.3
5.08	960		9.4		20.5 47
5.71	1090		10.7		21.9
6.35	1230		12.1		23.3



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email: civdept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax :002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011
Accredited by : Egypt Accreditation council (EGAC) under No. 031706/1A

Report :	738 - 2 - Center
Date :	25/09/2023

CHEMICAL ANALYSIS

General Consultant :	SYSTRA
Consultant :	DR/ Khaled Kandil
Contractor :	شركة اورانج للاستيراد والتصدير والمقاولات العامة
Project :	Electric express train
Sample :	FERMA
Station :	ST (308 + 700)
Date of Test :	19/09/2023
Temperature : 28 °C	Humidity : 45%

ANALYSIS	RESULTS	METHOD REFERENCE
ORGANIG MATTER	NEGATIVE	ASTM D 2974



LAB DIRECTOR
CH/ Mostafa Asker

Per Amany Amin

Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email : civdept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com

Contractor Company	Orange for Import & Export and General Contracting Company			Designer Company	(KK) Engineering Consulting Office			
Issued by Contractor	Name	Sign		Date/Serial Number		Time		
	Eng: Mohamed Fathy			03-01-2024 (OR-M.A 080)		09:00 AM		
Received by ER	Eng: Gaber Ibrahim		MAR	C1	C2	C3	D0	MM
				306	EW	C3	03	01
								YY
								HH
								MM

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	Stockpile For Soil (Fill Layer).		
Location to be Used	Station 306+000		
Sample only	Yes	Materials Type	Fill layers
Supplier Name	EL-Sewy - EL-Wafa (Eslam)	Data Sheet provided	Yes attached
Reference in BoQ		Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CNECON GROUP
Prequalification reference		Test Samples Results	Approved
Reference Photos	No	Other	
Comments by: Eng. Hesham Sabry (KK)		Comments by: Eng. Gaber Ibrahim (ER)	
1. تم إجراء الاختبارات المعملية بمكتب معامل الإستشارات الهندسية (CEL). 2. وتم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.		1- All tests were carried-out by by (Consulting Engineer Bureau & Laboratories), Depended on samples submitted by material engineer for both contractor and and GARB consultant. 2-Results report attached and acceptable with the project specifications. 3-Final approval is subject to above mentioned comments.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		10-01-2024	A
QA/QC *	Eng: Hesham Sabry			
GARB**	Eng: Ahmed Galal			
Employers Representative	Eng: Gaber Ibrahim			

* Designer
 ** Alignment/Bridges: Culvert only

80

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

Dear Gentleman,

Attached here with the Soil Embankment delivered on 03/01/2024

Materials test

1. Sieve analysis according to ASTM D-422.
2. Material finer than sieve No. 200 according to ASTM D-1140.
3. Liquid limits and plasticity index of soil according to ASTM D-4318.
4. Soil classification according to Project Specs.
5. Proctor Test according to ASTM D-1557
6. CBR according to ASTM D-1883
7. Organic Content ASTM D-2974

Note: The sample was brought by the client to our laboratory and the laboratory is not responsible for the way it is taken

Signature  

3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093



3 ش الملك الأفطل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

RESULTS OF SIEVE ANALYSIS According to ASTM D-422.

Sieve Size (mm)	Passing %
50	100
37.5	97.8
25	92.7
19	86.3
12.50	75.2
9.50	65.9
4.75	56.4
2.36	48.6
2.00	39.6
1.18	34.1
0.600	26.8
0.425	23.7
0.300	19.6
0.150	16.7

Signature /  02

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

**Materials finer than 75 μ m (no.200) sieve
by washing ASTM D-1140.**

Test	Results (%)
Percentage of material finer than Sieve Size 75 μ m (No.200)	12.7

CEL
مكتب معامل الإستشارات الهندسية
الساحل الشمالي
Signature: ...
البرق الرئيسي - شبراخيت - القناة - بورسعيد - مصر

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

**Results of liquid limit and plasticity index
of soils according to ASTM D-4318**

Test	Results (%)
Liquid Limit	24.3
Plastic Limit	19.5
Plasticity Index	4.8

CEL
مكتب معامل الاستشارات الهندسية
الساحل الشمالي
شارع النور - شقة ٢٠٠ - طابق الأرض - الزمالة - القاهرة

Signature /

4

3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093



٣ ش الملك الأفصل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

Soil Classification According to Project Specs (Embankment)

TEST	Results (%)	Limits according Projects Specs	
• Group Classification	(A-1-a)	(A-1-a)	(A-1-b)
2.00 mm (No.10).	39.6	Max 50 %	-----
0.425 mm (No. 40).	23.7	Max 30 %	Max 50 %
0.075 mm (No. 200).	12.7	Max 15 %	Max 15 %
Characteristics of fraction passing 0.425 mm (No.40)			
Liquid Limit	24.3	-----	-----
Plasticity index	4.8	Max 6 %	Max 6 %

The test results are (☒ Comply - ☐ Not Comply) with specifications limits


 مکتب معامل الاستشارات الهندسية
 المهندس 02
 التوقيع:
 Signature

5


3 El Malek El Afdal Street
Zamalek, Cairo.
Tel.& Fax : 27367231 - 27363093



٣ ش الملك الأفضل
 الزمالك - القاهرة
 تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

Moisture – Density relation of soil
Test result (Modified proctor test)
ASTM D-1557



- Max dry density (gm/cm³) : 2.143
- Optimum moisture content % : 7.7

CEL
مكتب معامل الاستشارات الهندسية
المنطقة الشمالية 02
شارع النيل - القاهرة - الجيزة

Signature /

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

Test Results of California Bearing Ratio on Base Materials
ASTM D 1883

Penetration		Stress on piston (MPa)
mm	Inch	
0.64	0.025	0.99
1.27	0.050	1.34
1.91	0.075	1.68
2.54	0.100	2.08
3.18	0.125	2.41
3.81	0.150	2.81
4.45	0.175	3.16
5.08	0.200	3.55
5.71	0.225	3.83
6.35	0.250	4.03

CBR Result	Stress (Mpa)		CBR %
At 0.1 inch (2.54 mm) penetration	St. Value	Sample results	30.2
	6.90	2.08	

Notes :

- 1- Attached graph shows penetration resistance versus penetration magnitude.
- 2- The sample was compacted to dry density of 2.143 (gm /cm³) at 7.7% optimum water content.
- 3- Surcharge load = 50 Kg

Signature

3 El Malek El Afdal Street
Zamalek, Cairo.
Tel.& Fax : 27367231 - 27363093




٣ ش الملك الأفصل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Company
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. 306+000
Type of sample : Soil Embankment
Delivery Date : 03-01-2024
Reporting Date : 10-01-2024
Reporting No. : 009
Sample No. : 03

Load Penetration Curve of CBR Test

ASTM D-1883



Signature: 
CEL
مكتب معامل الاستشارات الهندسية
المعامل الشمالي 02
الدكتور المهندس: محمد عبد الله محمد - القاهرة

Contractor Company	Orange for Import & Export and General Contracting Company			Designer Company		(KK) Engineering Consulting Office					
Issued by Contractor	Name	Sign		Date/Serial Number		Time					
	Eng: Mohamed Fathy			10-01-2024 (OR-M.A 081)		09:00 AM					
Received by ER	Eng: Gaber Ibrahim		MAR	C1	C2	C3	DD	MM	YY	HH	MM
				306	EW	C5	10	01	24	09	00

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	Stockpile For Soil (Fill Layer).		
Location to be Used	Station 306+500		
Sample only	Yes	Materials Type	Fill layers
Supplier Name	EL-Sewy – EL-Moassa	Data Sheet provided	Yes attached
Reference in BoQ		Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP
Prequalification reference		Test Samples Results	Approved
Reference Photos	No	Other	
Comments by: Eng. Hesham Sabry (KK)		Comments by: Eng. Gaber Ibrahim (ER)	
1. تم إجراء الاختبارات المعملية 2. وتم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.		1- All tests were carried-out by material engineer for both contractor and GARB Consultant. 2- Results report attached and acceptable with the project specifications. 3- Final approval is subject to above mentioned comments.	

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		15-01-2024	A
QA/QC *	Eng: Hesham Sabry		15/1/2024	A
GARB**	Eng: Ahmed Galal			
Employers Representative	Eng: Gaber Ibrahim			

* Designer

** Alignment/Bridges: Culvert only

Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein
Section - 4 From Wadi El Nnatroun To Borg Elarab "
From Station 305+500 To Station 311+000

Sieve Analysis of Fine and Coarse Aggregates (ASHTO T-27)

Date :	10-Jan-2024	Station:	306+500
From / To :		Sample type :	عينة أتربة من المشون

Classification	A-1-b
----------------	-------

Sieve size	Return	Passing	%
2"	0	10527	100.0
1.5"	716	9811	93.2
1"	934	8877	84.3
3/4"	522	8355	79.4
1/2"	1059	7296	69.3
3/8"	658	6638	63.1
NO. 4	1834	4804	45.6
Passing	4804		
Total	10527		

500 gm			
NO.10	38.4	461.6	42.1
NO.40	160	340	31.0
NO.200	380	120	11.0

المهندس الاستشاري
س. ا. محمد سعيد

مهندس المواد (الشركة)
محمد ابو شنب

Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein
Section - 4 From Wadi El Nnatroun To Borg El Arab "

(Determining the Plastic Limit & Plasticity Index of soil (AASHTO (T-90
(Determining the Liquid Limit of soil (AASHTO (T-89

Date :	10-Jan-2024
From / To :	


Station:	306+500
Sample type :	عينة التربة من المشون

LIQUID LIMIT

Container No	B	C	f
Number of Blows	20	32	38
Mass of Wet Soil + Can	76.00	80.90	76.80
Mass of Dry Soil + Can	67.60	72.20	68.70
Mass of Water	8.40	8.70	8.10
Mass of Can	33.1	34.8	32.5
Mass of Dry Soil	34.5	37.4	36.2
Moisture Content	24.35	23.26	22.38

PLASTIC LIMIT

Container No	E	A
Mass of Wet Soil + Can	38.10	40.40
Mass of Dry Soil + Can	34.8	36.40
Mass of Water	3.30	4.00
Mass of Can	18.80	16.90
Mass of Dry Soil	16.0	19.5
Moisture Content	20.63	20.51



RESULTS

PASSING No. 10	42.1
PASSING No. 40	29.1
PASSING No. 200	11.0
LIQUID LIMIT	23.8
PLASTIC LIMIT	20.57
PLASTICITY INDEX	3.23

المهندس الاستشاري
سرا محمد طافوري

مهندس المواد (الخرق)
عمور ابوشنب


Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein
Section - 4 From Wadi El Natroun To Borg El Arab *
From Station 305+500 To Station 311+000

The Moisture - Density Relations of Soils using (ASTM D1557)

Date :	10-Jan-2024
From / To	

Station:	306+500
Sample type :	عينة تربة من المشون

	1	2	3	4	5
Mold + Wet Sample Weight	9980	10194	10370	10264	
Mold Weight	5630	5630	5630	5630	
Wet Sample Weight	4350	4564	4740	4634	
Mold Volume	2122	2122	2122	2122	
Wet Density	2.05	2.15	2.23	2.18	
Container NO.	2	5	4	1	
Mass of Can	33.2	34.2	33.1	33.4	
Wet soil Weight + Mass of Can	239	487.8	537.3	400.5	
Dry soil Weight + Mass of Can	235	466.8	502.7	370	
Dry soil Weight	201.8	432.6	469.6	336.6	
Water Weight	4	21	34.6	30.5	
Percentage of Moisture	1.98	4.85	7.37	9.06	
Dry Density	2.010	2.051	2.080	2.002	



Max. Dry Density	2.082
Optimum Water Content	7.00%

مهندس الاستشاري
م. احمد محمد الفهد

مهندس البحوث (التراب)
محمود ابو شنب

Electric Express Train - HSR
From El Ain El Sokhna City To El Alamein
Section - 4 From Wadi El Nnatroun To Borg Elarab
From Station 305+500 To Station 311+000

CALIFORNIA BEARING RATIO (ASTM D1883)

Date :	15-Jan-2024
From / To :	

Station:	305+500
Sample type :	عينة التربة من المشون

Mold No	6
Mold g	5073
Volume of Mold cm ³	2140
Sample + Mold g	9812
Sample g	4739
Wet unit weight g/cc	2.21
Dry unit weight g/cc	2.07
Compaction %	99.4%

Maximum Dry Density g/cc	2.082
Optimum Moisture Content	7.00
Can No	3
MASS WET SOIL + CAN	226.0
MASS DRY SOIL + CAN	212.0
Mass of Moisture g	14.0
Mass of Can g	12.5
Mass DRY SOIL g	199.5
Moisture	7.02%


Initial Reading	0.0
Final Reading	0.22

Date Molded	10-Jan-2024
Swell %	0.19

Penetration mm.	0.635	1.27	1.95	2.54	3.81	5.08	7.62
Penetration in"	0.025	0.05	0.075	0.1	0.15	0.2	0.3
Loading Ring Reading							
Load kN	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Load kg	60	148	250	360	561	710	1012

CBR % at 0.1" =	26.5%
CBR % at 0.2" =	34.8%


C.B.R	35%
-------	-----



المهندس الاستشاري
أ. د. خالد قنديل

مهندس المواد (الشركة)
محمد البوشنب

MATERIAL INSPECTION REQUEST



Contractor Company	Orange for Import & Export and General Contracting Company		Designer Company	(KK) Engineering Consulting Office			
Issued by Contractor	Name	Sign	Date/ Serial Number	Time			
	Eng: Mohamed Fathy			10:00 AM			
Received by ER	Eng. Gaber Ibrahim	MIR					
			C1	C2	C3	DD	MM
			310	EW	CS	17	01
						24	10
						00	

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL LAYER				
Location to be Used	From St. (310+010) To St. (310+170) (-1.50m From Ferma).				
MAR Approval No	(OR-M.A 077)			Date	07-01-2024
Supplier Name	EL-SEWY – ELWAFA (ESLAM)				
Test Requirement	P.L.T (DIN 18134)		Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.	
Reference Photos	No		Other		
Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate Loading Test	NUMBER	2	17-01-2024	
2					
3					
4					
Comments by : Eng. Hesham Sabry (KK)			Comments by: Eng. Gaber Ibrahim (ER)		
1- تم اختبار القطاع (Plate Loading Test) من قبل مكتب معامل الاستشارات الهندسية (CEL). 2- تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.			1- P.L.T was carried- out by (Consulting Engineer Bureau & Laboratories), attendance of material engineer for both contractor and GARB Consultant. 2- Results report attached and acceptable with project specifications 3- Final approval is subject to above-mentioned comments.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		18-01-2024	A
QA/QC *	Eng. Hesham Sabry			
GARB**	Eng. Ahmed Galal			
Employers Representative	Eng. Gaber Ibrahim			

* Designer

** Alignment / Bridges: Culvert Only

Company : Orange Construction.

Project : Electric Express Train, Al Ain Sokhna to Marsa Matrouh Priority Sector (4)
- Wadi El Natroun to Borg Al Arab.

Subject : Determine the deformation and strength characteristics of soil by the plate loading test according specifications DIN 18134:2012-04 and project requirements.

Test Location: Station (310+010 to 310+170)

Test Date : 17/01/2024

Repot Date : 18/01/2024

Type of soil : ----

Test level : Middle Embankment (-1.5)

Report No. : 21:22

Dear Gentleman,

According to the above mentioned subject the test performed as follows:-

Apparatus

1. Loading plates consists of two plates with 600 mm and 300 mm diameter
2. The thickness of plates 30 mm
3. Dial gauges with accuracy 0.01 mm to measuring the settlement
4. Steel straightedges with magnetic supports to fixed the dial gauges
5. Hydraulic jack with pump to transfer reactive loads to the loading plates
6. Dial indicator measuring device with scale capacity 700 Bar (Enerbac)
7. Reaction loading system by roller compactor with weight approximately 15 ton.
8. Calibration certificates are attached.

Test Procedure

1. Clean the ground on test area to the required level with undisturbed soil
2. Install loading plates 600 mm and 300 mm diameter, hydraulic jack and 3 dial gauges
3. Prior to starting the test applied preloading about 30 seconds.
4. The strain gauge and the dial gauge shall be set to zero
5. For a 600 mm loading plate, the limit values are 2.5 kg/cm²
6. The load shall be applied in six stages, in approximately equal increments, until the required maximum normal stress is reached.
7. Each change in load (from stage to stage) shall be completed within one minute
8. The load shall be released in 3 stages, to 50 % , 25 % , and approximately 2 % of the maximum load.
9. Following unloading, a further (2nd) loading cycle shall be carried out, in which, however, the load is to be increased only to the penultimate stage of the first cycle (so that the full load is not reached).
10. At each stage the load shall be maintained until the rate of settlement of the plate becomes less than 0.02 mm/min.
11. Remove the loads



Report

1. Evaluation and representation of results
2. Load Settlement curve
3. The test report content the following:-
 - location of test site - Dimension of loading plate
 - Measuring device used - Type of soil
 - Type of Bedding material below the plate -Weathering condition
 - Time and date of measurements - Unusual observation made during test
 - Dial gauge reading and corresponding normal stress - Loading-settlement curve
 - Description of the soil condition below the plate after testing

Report

- Type of Soil : Middle Embankment
- Job Requirement : $E_{v2} > (40 \text{ MPa})$

Item	Descriptions
- Type of bedding material below the plate	Natural Soil
- Weather condition	Partly Sunny
- Plate Diameter (mm)	600
- date of measurement	17/01/2024
- Unusual observation made during test	NO
- Description of the soil conditions below the plate after testing	No deformation

Evaluation and representation of results

Test No.	Station	First Cycle	Second Cycle	E_{v2}/E_{v1} Ratio
		E_{v1} (MPa)	E_{v2} (MPa)	
1	310+100	103	186	1.8
2	310+106	145	187	1.3

Signature / ...



Company Name : Orange Construction.
Project : Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (I) - Wadi El Natroun to Borg El Arab.
Test Date : 17/01/2024
report date : 18/01/2024
Location : Station 310+100
Test No. : 001

Nonrepetitive Static Plate Load Tests of Soils
DIN 18134

Data sheet

Loading Stage (1)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.00	20.00	0.00	20.00	0.00	20.00	0.00	0.00
1	0.42	19.83	0.17	19.80	0.20	19.69	0.31	0.23
2	0.83	19.58	0.32	19.71	0.29	19.50	0.50	0.37
3	1.25	19.57	0.43	19.25	0.75	19.29	0.71	0.63
4	1.67	19.39	0.61	19.21	0.79	19.15	0.85	0.75
5	2.08	19.25	0.75	19.16	0.84	19.04	0.96	0.85
6	2.50	19.14	0.86	19.10	0.90	18.98	1.02	0.93

Unloading Stage (1)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
1	2.50	19.14	0.86	19.10	0.90	18.98	1.02	0.93
2	1.25	19.30	0.70	19.15	0.85	19.03	0.97	0.84
3	0.625	19.41	0.59	19.30	0.70	19.14	0.86	0.72
4	0.01	19.50	0.50	19.41	0.59	19.30	0.70	0.60

Loading Stage (2)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.42	19.41	0.59	19.30	0.70	19.21	0.79	0.69
1	0.83	19.29	0.71	19.21	0.79	19.10	0.90	0.80
2	1.25	19.18	0.82	19.09	0.91	19.02	0.98	0.90
3	1.67	19.06	0.94	19.00	1.00	18.95	1.05	1.00
4	2.08	18.97	1.03	18.91	1.09	18.82	1.18	1.10



3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093




ش.م.ك. الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name
Project
Test Date
Report date
Location
Test No.

: Orange Construction
: Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (4) - Wadi El Natroun to Burg Al Arab
: 17/01/2024
: 18/01/2024
: Station 310+100
: 001

Nonrepetitive Static Plate Load Tests of Soils DIN 10134



Loading (1)	0	1	2	3	4	5	6
Stage(Kg)	0	1186.92	2345.6	3532.5	4718.4	5878.1	7065
Stress (Kg/cm²)	0.00	0.42	0.83	1.25	1.87	2.08	2.50
Settlement (mm)	0.00	0.23	0.37	0.53	0.75	0.85	0.93

Unloading (1)	1	2	3	4
Stage(Kg)	7065	3633	1768	0
Stress (Kg/cm²)	2.50	1.25	0.625	0.01
Settlement (mm)	0.03	0.64	0.72	0.00

D (mm) =	600	S1 (mm) =	0.34	S2 (mm) =	0.77	ΔS =	0.43
Ev1 (MPa) =	(0.75 * D² * ΔS) / ΔS						

Loading (2)	0	1	2	3	4	5
Stage(Kg)	0	1186.92	2345.6	3532.5	4718.4	5878.1
Stress (Kg/cm²)	0.01	0.42	0.83	1.25	1.87	2.08
Settlement (mm)	0.60	0.89	0.80	0.92	1.00	1.10

Ev2/Ev1 =	1.8
-----------	-----

D (mm) =	600	S1 (mm) =	3.78	S2 (mm) =	1.02	ΔS =	0.24
Ev2 (MPa) =	(0.75 * D² * ΔS) / ΔS						

Ev1 = Modulus of deformation during the loading stage.

Ev2 = Modulus of deformation during the releasing stage.

D = Plate diameter (mm)

ΔS = The difference between 0.3 and 0.7 from the maximum loading (mm) (kg/cm²)

ΔS = Difference in settlements corresponding to 0.3 and 0.7 from the maximum loading (mm)



3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 • 27363093



ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Construction.
Project : Electric Express Train, Al Ain Sekhna to Marsa Matrouh Priority Sector (4) - Wadi El Natroun to Borg El Arab.
Test Date : 17/01/2024
report date : 10/01/2024
Location : Station 310+106
Test No. : 002

Nonrepetitive Static Plate Load Tests of Soils
DIN 18134

Data sheet

Loading Stage (1)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.00	20.00	0.00	20.00	0.00	20.00	0.00	0.00
1	0.42	19.79	0.21	19.70	0.30	19.65	0.35	0.29
2	0.83	19.64	0.36	19.59	0.41	19.50	0.50	0.42
3	1.25	19.52	0.48	19.43	0.57	19.39	0.61	0.55
4	1.67	19.40	0.60	19.32	0.68	19.25	0.75	0.68
5	2.08	19.27	0.73	19.20	0.80	19.13	0.87	0.80
6	2.50	19.15	0.85	19.09	0.91	19.01	0.99	0.92

Unloading Stage (1)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
1	2.50	19.15	0.85	19.09	0.91	19.01	0.99	0.92
2	1.25	19.33	0.67	19.18	0.82	19.07	0.93	0.81
3	0.825	19.43	0.57	19.27	0.73	19.14	0.86	0.72
4	0.01	19.55	0.45	19.39	0.61	19.30	0.70	0.59

Loading Stage (2)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.42	19.41	0.59	19.25	0.75	19.19	0.81	0.72
1	0.83	19.29	0.71	19.14	0.86	19.08	0.92	0.83
2	1.25	19.18	0.82	19.04	0.96	18.94	1.06	0.95
3	1.67	19.07	0.93	18.95	1.05	18.89	1.11	1.03
4	2.08	18.98	1.02	18.90	1.10	18.81	1.19	1.10



3 El Malek El Afdal Street
Zamalek, Cairo.
Tel.& Fax : 27367231 - 27363093




٣ ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name
Project
Test Date
Report Date
Location
Test No.

: Orange Construction
: Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (4) - Wadi El Matroun to Borg El Arab.
: 17/01/2024
: 18/01/2024
: Station 310+106
: 002

Nonrepitive Static Plate Load Tests of Soils DIN 18134



Loading (t)	0	1	2	3	4	5	6
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1	7065
Stress (Kg/cm²)	0.00	0.42	0.83	1.25	1.67	2.08	2.50
Settlement (mm)	0.00	0.29	0.42	0.55	0.68	0.80	0.92

Unloading (t)	1	2	3	4
Stage(Kg)	7065	3533	1768	0
Stress (Kg/cm²)	2.50	1.25	0.625	0.01
Settlement (mm)	0.92	0.81	0.72	0.59

D (mm) = 600	S1 (mm) = 0.42	S2 (mm) = 0.79	ΔS = 0.50
Ev1 (MPa) = $(0.75 \cdot D^2 \cdot \Delta S) / \Delta S$	145		

Ev2/Ev1 = 1.3

Loading (2)	0	1	2	3	4	5
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1
Stress (Kg/cm²)	0.01	0.42	0.83	1.25	1.67	2.08
Settlement (mm)	0.59	0.72	0.83	0.95	1.03	1.10

D (mm) = 600	S1 (mm) = 3.81	S2 (mm) = 1.04	ΔS = 0.24
Ev2 (MPa) = $(0.75 \cdot D^2 \cdot \Delta S) / \Delta S$	187		

Ev1 = Modulus of deformation during the loading stage.

Ev2 = Modulus of deformation during the reloading stage.

D = Plate diameter (mm)

ΔS = The difference between 0.3 and 0.7 from the maximum loading stage.

ΔS = Difference in settlements corresponding to 0.3 and 0.7 from the maximum loading stage.



3 El Malek El Afdal Street

Zamalek, Cairo.

Tel. & Fax : 27367231 - 27363093



ش الملك الأفضل

الزمالك - القاهرة

تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣

www.cel-egypt.com

MATERIAL INSPECTION REQUEST



الهيئة العامة
للتنظيم والرقابة
(GARB)



Contractor Company	Orange for Import & Export and General Contracting Company		Designer Company	(KK) Engineering Consulting Office							
Issued by Contractor	Name	Sign	Date/ Serial Number	Time							
	Eng: Mohamed Fathy		17-01-2024 OR-M.I.216	10:00 AM							
Received by ER	Eng. Gaber Ibrahim		MIR	C1 309	C2 EW	C3 CS	DD 17	MM 01	YY 24	HH 10	MM 00

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL LAYER				
Location to be Used	From St. (309+810) To St. (309+950) (-1.50m From Ferma).				
MAR Approval No	(OR-M.A 077)	Date	07-01-2024		
Supplier Name	EL-SEWY – ELWAFI (ESLAM)				
Test Requirement	P.L.T (DIN 18134)	Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.		
Reference Photos	No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate Loading Test	NUMBER	2	17-01-2024	
2					
3					
4					
Comments by : Eng. Hesham Sabry (KK)			Comments by: Eng. Gaber Ibrahim (ER)		
1- تم اختبار القطاع (Plate Loading Test) من قبل مكتب معامل الاستشارات الهندسية (CEL). 2- تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.			1- P.L.T was carried- out by (Consulting Engineer Bureau & Laboratories), attendance of material engineer for both contractor and GARB Consultant. 2- Results report attached and acceptable with project specifications 3- Final approval is subject to above-mentioned comments.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		18-01-2024	A
QA/QC *	Eng. Hesham Sabry			
GARB**	Eng. Ahmed Galal			
Employers Representative	Eng. Gaber Ibrahim			

* Designer

** Alignment / Bridges: Culvert Only

Company : Orange Construction.

Project : Electric Express Train, Al Ain Sokhna to Marsa Matrouh Priority Sector (4)
– Wadi El Natroun to Borg Al Arab.

Subject : Determine the deformation and strength characteristics of soil by the plate loading test according specifications DIN 18134:2012-04 and project requirements.

Test Location: Station (309+810 to 309+950)

Test Date : 17/01/2024

Report Date : 18/01/2024

Type of soil : ----

Test level : Middle Embankment (-1.5)

Report No. : 17:18

Dear Gentleman,

According to the above mentioned subject the test performed as follows:-

Apparatus

1. Loading plates consists of two plates with 600 mm and 300 mm diameter
2. The thickness of plates 30 mm
3. Dial gauges with accuracy 0.01 mm to measuring the settlement
4. Steel straightedges with magnetic supports to fixed the dial gauges
5. Hydraulic jack with pump to transfer reactive loads to the loading plates
6. Dial indicator measuring device with scale capacity 700 Bar (Enerbac)
7. Reaction loading system by roller compactor with weight approximately 15 ton.
8. Calibration certificates are attached.

Test Procedure

1. Clean the ground on test area to the required level with undisturbed soil
2. Install loading plates 600 mm and 300 mm diameter, hydraulic jack and 3 dial gauges
3. Prior to starting the test applied preloading about 30 seconds.
4. The strain gauge and the dial gauge shall be set to zero
5. For a 600 mm loading plate, the limit values are 2.5 kg/cm²
6. The load shall be applied in six stages, in approximately equal increments, until the required maximum normal stress is reached.
7. Each change in load (from stage to stage) shall be completed within one minute
8. The load shall be released in 3 stages, to 50 %, 25 %, and approximately 2 % of the maximum load.
9. Following unloading, a further (2nd) loading cycle shall be carried out, in which, however, the load is to be increased only to the penultimate stage of the first cycle (so that the full load is not reached).
10. At each stage the load shall be maintained until the rate of settlement of the plate becomes less than 0.02 mm/min.
11. Remove the loads

Report

1. Evaluation and representation of results
2. Load Settlement curve
3. The test report content the following:-
 - location of test site - Dimension of loading plate
 - Measuring device used - Type of soil
 - Type of Bedding material below the plate -Weathering condition
 - Time and date of measurements - Unusual observation made during test
 - Dial gauge reading and corresponding normal stress - Loading-settlement curve
 - Description of the soil condition below the plate after testing

Report

- Type of Soil : Middle Embankment
- Job Requirement : $E_{v2} > (40 \text{ MPa})$

Item	Descriptions
- Type of bedding material below the plate	Natural Soil
- Weather condition	Partly Sunny
- Plate Diameter (mm)	600
- date of measurement	17/01/2024
- Unusual observation made during test	NO
- Description of the soil conditions below the plate after testing	No deformation

Evaluation and representation of results

Test No.	Station	First Cycle	Second Cycle	E_{v2}/E_{v1} Ratio
		E_{v1} (MPa)	E_{v2} (MPa)	
1	309+900	133	204	1.5
2	309+940	123	186	1.5

Signature /



Company Name : Orange Construction.
Project : Electric Express Train, Al Ain Sokhna to Marsa Matrouh Priority Sector (4) - Wadi El Natroun to Borg El Arab.
Test Date : 17/01/2024
report date : 18/01/2024
Location : Station 309+900
Test No. : 001

Nonrepetitive Static Plate Load Tests of Soils
DIN 18134

Data sheet

Loading Stage (1)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.00	20.00	0.00	20.00	0.00	20.00	0.00	0.00
1	0.42	19.95	0.05	19.80	0.20	19.75	0.25	0.17
2	0.83	19.81	0.19	19.73	0.27	19.68	0.32	0.26
3	1.25	19.69	0.31	19.60	0.40	19.51	0.49	0.40
4	1.67	19.53	0.47	19.44	0.56	19.38	0.62	0.55
5	2.08	19.40	0.60	19.33	0.67	19.25	0.75	0.67
6	2.50	19.28	0.72	19.21	0.79	19.13	0.87	0.79

Unloading Stage (1)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
1	2.50	19.28	0.72	19.21	0.79	19.13	0.87	0.79
2	1.25	19.36	0.64	19.30	0.70	19.15	0.81	0.72
3	0.625	19.49	0.51	19.41	0.59	19.21	0.79	0.63
4	0.01	19.63	0.37	19.50	0.50	19.35	0.65	0.51

Loading Stage (2)

Loading	Stress Kg/cm2	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.42	19.51	0.49	19.43	0.57	19.21	0.79	0.62
1	0.83	19.39	0.61	19.31	0.69	19.10	0.90	0.73
2	1.25	19.28	0.72	19.20	0.80	19.13	0.87	0.80
3	1.67	19.16	0.84	19.10	0.90	19.04	0.96	0.90
4	2.08	19.03	0.97	18.96	1.04	18.90	1.10	1.04




3 El Malek El Afdal Street
Zamalek, Cairo.
Tel.& Fax : 27367231 - 27363093



ش الملك الأفندي
القاهرة - الزمالك
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Construction.
Project : Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (4) - Wadi El Matroun to Borg El Arab.
Test Date : 17/01/2024
report date : 18/01/2024
Location : Station 309+900
Test No. : 001

Nonrepetitive Static Plate Load Tests of Soils DIN 18134



Loading (1)	0	1	2	3	4	5	6
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1	7065
Stress (Kg/cm²)	0.00	0.42	0.83	1.25	1.67	2.08	2.50
Settlement (mm)	0.00	0.17	0.26	0.40	0.55	0.67	0.79

UnLoading (1)	1	2	3	4
Stage(Kg)	7065	3533	1768	0
Stress (Kg/cm²)	2.50	1.25	0.625	0.01
Settlement (mm)	0.79	0.72	0.63	0.51

D (mm) =	600	S1 (mm) =	0.24	S2(mm) =	0.57	ΔS =	0.33
Ev1 (MPa) =	(0.75*D*Δσ/ΔS)		133				

Loading (2)	0	1	2	3	4	5
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1
Stress (Kg/cm²)	0.01	0.42	0.83	1.25	1.67	2.08
Settlement (mm)	0.51	0.62	0.73	0.80	0.90	1.04

Ev2/Ev1 = 1.5

D (mm) =	600	S1 (mm) =	0.71	S2(mm) =	0.93	ΔS =	0.22
Ev2 (MPa) =	(0.75*D*Δσ/ΔS)		254				

Ev1 = Modulus of deformation during the loading stage.
Ev2 = Modulus of deformation during the reloading stage.
D = Plate diameter (mm)

Δσ = The difference between 0.3 and 0.7 from the maximum loading (mm)(Kg/cm²)
ΔS = Difference in settlements corresponding to 0.3 and 0.7 from the maximum loading (mm)



Company Name : Orange Construction.
Project : Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (4) - Wadi El Natroun to Borg El Arab.
Test Date : 17/01/2024
report date : 18/01/2024
Location : Station 309+940
Test No. : 002

Nonrepetitive Static Plate Load Tests of Soils
DIN 18134

Data sheet

Loading Stage (1)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.00	20.00	0.00	20.00	0.00	20.00	0.00	0.00
1	0.42	19.83	0.17	19.75	0.25	19.70	0.30	0.24
2	0.83	19.71	0.29	19.62	0.38	19.50	0.50	0.39
3	1.25	19.55	0.41	19.51	0.49	19.44	0.56	0.49
4	1.67	19.38	0.62	19.30	0.70	19.24	0.76	0.69
5	2.08	19.25	0.75	19.18	0.82	19.10	0.90	0.82
6	2.50	19.14	0.86	19.07	0.93	19.00	1.00	0.93

Unloading Stage (1)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
1	2.50	19.14	0.86	19.07	0.93	19.00	1.00	0.93
2	1.25	19.30	0.70	19.16	0.84	19.07	0.93	0.82
3	0.83	19.47	0.53	19.32	0.68	19.15	0.85	0.69
4	0.01	19.60	0.40	19.45	0.55	19.34	0.66	0.54

Loading Stage (2)

Loading	Stress Kg/cm ²	Dial 1	Settlement mm	Dial 2	Settlement mm	Dial 3	Settlement mm	Average
0	0.42	19.47	0.53	19.32	0.68	19.22	0.78	0.66
1	0.83	19.35	0.65	19.21	0.79	19.10	0.90	0.78
2	1.25	19.23	0.77	19.09	0.91	19.02	0.98	0.89
3	1.67	19.10	0.90	19.01	0.99	18.95	1.05	0.98
4	2.08	19.04	0.96	18.94	1.06	18.86	1.14	1.05




3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093



ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : Orange Construction.
 Project : Electric Express Train, Al Ain Sokhna to Marsa Matruh Priority Sector (4) - Wadi El Natroun to Borg El Arab.
 Test Date : 17/01/2024
 report date : 18/01/2024
 Location : Station 309+948
 Test No. : 002

Nonrepetitive Static Plate Load Tests of Soils DIN 18134



Loading (1)	0	1	2	3	4	5	6
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1	7063
Stress (Kg/cm ²)	0.00	0.42	0.83	1.25	1.67	2.08	2.59
Settlement (mm)	0.00	0.24	0.38	0.49	0.69	0.82	0.93

UnLoading (1)	1	2	3	4
Stage(Kg)	7063	3533	1768	0
Stress (Kg/cm ²)	2.56	1.25	0.625	0.01
Settlement (mm)	0.93	0.82	0.69	0.54

D (mm) = 600	S1 (mm) = 0.36	S2 (mm) = 0.72	ΔS = 0.36
Ev1 (MPa) = $(0.75 \cdot D^2 \cdot \Delta S) / \Delta S$	123		

Ev2/Ev1 = 1.5

Loading (2)	0	1	2	3	4	5
Stage(Kg)	0	1186.92	2345.6	3532.5	4719.4	5878.1
Stress (Kg/cm ²)	0.01	0.42	0.83	1.25	1.67	2.08
Settlement (mm)	0.54	0.66	0.78	0.89	0.96	1.05

D (mm) = 600	S1 (mm) = 0.76	S2 (mm) = 0.99	ΔS = 0.24
Ev2 (MPa) = $(0.75 \cdot D^2 \cdot \Delta S) / \Delta S$	186		

Ev1 = Modulus of deformation during the loading stage.

Ev2 = Modulus of deformation during the Reloading stage.

D = Plate diameter (mm)

ΔS = The difference between 0.3 and 0.7 from the maximum loading (mm)

ΔS = Difference in settlements corresponding to 0.3 and 0.7 from the maximum loading (mm)



3 El Malek El Afdal Street
 Zamalek, Cairo.
 Tel. & Fax : 27367231 - 27363093



3 ش الملك الأفضل
 الزمالك - القاهرة
 تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

MATERIAL INSPECTION REQUEST



الهيئة العامة
للتنظيم والرقابة
(GARB)



Contractor Company	Orange for Import & Export and General Contracting Company			Designer Company	(KK) Engineering Consulting Office						
Issued by Contractor	Name	Sign		Date/ Serial Number	Time						
	Eng: Mohamed Fathy			01-05-2024 OR-M.I.289	10:30 AM						
Received by ER	Eng. Gaber Ibrahim		MIR	C1	C2	C3	DD	MM	YY	HH	MM
				310	EW	CS	01	05	24	10	30

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For the Kilometer point, only the Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials		Fill Layer			
Location to be Used		From St. (310+020) To St. (310+170) (Ferma).			
MAR Approval No		(OR-M.A 087)		Date	15-04-2024
Supplier Name		EL-Sewy – EL-Moassa			
Test Requirement		P.L.T (DIN 18134)		Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.
Reference Photos		No		Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate load test by Comibassal Lab	NUMBER	3	01-05-2024	
2					
3					
4					
Comments by : Eng. Hesham Sabry			Comments by: Eng. Hesham Sabry		
1. تم اختبار القطاع (Plate Loading Test) من قبل المعمل الهندسي (كوميبسال). 2. تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.			1- P.L.T was carried- out by Comibassal Lab, Attendances of material engineer for both contractor and GARB Consultant. 2- Results report attached and acceptable with project specifications 3- Final approval is subject to above mentioned comments.		

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		01-05-2024	A
QA/QC *	Eng. Hesham Sabry			
GARB**	Eng. Ahmed Galal			
Employers Representative	Eng. Gaber Ibrahim			

* Designer

** Alignment / Bridges: Culvert Only



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34 / 29-11-2011

Technical report

of Plate Loading Test (DIN 18134)

General	:	SYSTRA
Consultant	:	Dr/ Khaled Kandil
Contractor	:	شركة اورنج للإستيراد والتصدير والمقاولات العامة
Project	:	ELECTRIC EXPRESS TRAIN
Sample	:	Upper Embankment
Station	:	ST(310+020) TO ST(310+170)
Date of Test	:	1/5/2024
QC	:	746 -2





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011

Introduction:

The Plate Load test is designed to determine the vertical deformation and strength characteristics of soil by assessing the force and amount of penetration with time when a rigid plate is made to penetrate the soil.


The test to be carried out on the native soil according to German specifications DIN 18134.

Test methods :

- 1- The German standard DIN 18134 was applied to define the apparatus used, the loading system, test conditions, and procedure for plate load test.
- 2- Loading plates with a diameter of 600 mm have a thickness of 25mm and are provided with equally spaced stiffeners with even upper faces parallel to the plate bottom face to allow 300 mm plate to be placed on top of it.
- 3- The loading system consisted of a hydraulic pump connected to a hydraulic jack of 700 bar capacity, which is capable of applying and releasing the load stages.
- 4- The dial gauge used to measure the plate settlement has a resolution of 0.01mm and the lever ratio was equal to 1.
- 5- The temperature at the time of the test was 25°.
- 6- The plate was carried out on a native soil (sand-gravel). The test surface area was levelled and the plate was bedded on this surface.
- 7- The hydraulic jack was placed on the middle of, and at normal to, the loading plate beneath the reaction loading system and secured against tilting.
- 8- The reaction loading system was a heavy multi-purpose excavator (more than 20 ton).

Description of experiment:

- 1- Loading, unloading and reloading regims were applied according to DIN 18134 for the plate load test to estimate the resilient modulus
- 2- Prior to the test, the force transducer and dial gauge were set to zero, after which a load was applied corresponding to a stress of 0.01 MN/m².
- 3- In the first loading cycle, the load was increased until a normal stress of 0.25 MN/m² was reached, and the loading increment was 0.025 MN/m². The load was released in four stages.
- 4- Following unloading, a further second loading cycle was carried out, in which, the load was increased only to the penultimate stage of the first cycle.



Kilo 23 Alexandria - Cairo Desert Road - Merghen
Tel: 002 03 4704595 - 002 034701191
Email : civdept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011

St(310+050)

600

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.17
2	14.14	0.050	0.43
3	21.21	0.075	0.54
4	28.28	0.100	0.70
5	35.35	0.125	0.88
6	42.42	0.150	1.15
7	49.49	0.175	1.33
8	56.56	0.200	1.24
9	63.63	0.225	1.34
10	70.7	0.250	1.77
11	56.56	0.200	1.76
12	49.49	0.175	1.75
13	35.35	0.125	1.70
14	21.21	0.075	1.63
15	1.414	0.005	1.17

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	1.17
16	7.07	0.025	1.29
17	14.14	0.050	1.36
18	21.21	0.075	1.42
19	28.28	0.100	1.48
20	35.35	0.125	1.54
21	42.42	0.150	1.60
22	49.49	0.175	1.66
23	56.56	0.200	1.74
24	63.63	0.225	1.80

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, max})$ MN/m ²	0.250	0.250
s_0 (mm)	0.009	1.187
a_1 (mm/(MN/m ²))	7.704	3.147
a_2 (mm/(MN ² /m ²))	-4.689	-2.110
$Ev = 1.5 \pi / (a_1 + a_2 \cdot \sigma_{0, max})$	68.89	171.76
$Ev2/Ev1$	2.49	



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email : clvdept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax :002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_s Normal stress MN/m²





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011

St(310+100)

600

Table 4: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.10
2	14.14	0.050	0.19
3	21.21	0.075	0.31
4	28.28	0.100	0.45
5	35.35	0.125	0.65
6	42.42	0.150	0.78
7	49.49	0.175	0.91
8	56.56	0.200	1.03
9	63.63	0.225	1.13
10	70.7	0.250	1.24
11	56.56	0.200	1.23
12	49.49	0.175	1.22
13	35.35	0.125	1.17
14	21.21	0.075	1.05
15	1.414	0.005	0.47

Table 5: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.47
16	7.07	0.025	0.63
17	14.14	0.050	0.71
18	21.21	0.075	0.79
19	28.28	0.100	0.89
20	35.35	0.125	0.99
21	42.42	0.150	1.03
22	49.49	0.175	1.10
23	56.56	0.200	1.16
24	63.63	0.225	1.23

Table 6: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0,max})$ MN/m ²	0.250	0.250
a_0 (mm)	-0.098	0.475
a_1 (mm/(MN/m ²))	6.183	4.853
a_2 (mm/(MN ² /m ⁴))	-3.092	-6.964
$E_v = 1.5 \cdot (a_1 + a_2 \cdot \sigma_{0,max})$	83.18	144.57
E_v2/E_v1	1.74	





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypton General Authority for Petroleum under No. 34/20-11-2011




Fig. 2: Load-settlement curve, fitting curves according to Table 4 and Table 5 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email: cindept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax: 002 033900476
Email: internal-inspection@comibassal.com

St(310+150)

600

Table 7: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.09
1	7.07	0.025	0.10
2	14.14	0.050	0.23
3	21.21	0.075	0.39
4	28.28	0.100	0.58
5	35.35	0.125	0.72
6	42.42	0.150	0.86
7	49.49	0.175	0.97
8	56.56	0.200	1.06
9	63.63	0.225	1.15
10	70.7	0.250	1.26
11	56.56	0.200	1.24
12	49.49	0.175	1.24
13	35.35	0.125	1.20
14	21.21	0.075	1.10
15	1.414	0.005	0.58

Table 8: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.58
16	7.07	0.025	0.67
17	14.14	0.050	0.74
18	21.21	0.075	0.83
19	28.28	0.100	0.90
20	35.35	0.125	0.96
21	42.42	0.150	1.03
22	49.49	0.175	1.10
23	56.56	0.200	1.16
24	63.63	0.225	1.23

Table 9: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{0,max}$) MN/m ²	0.250	0.250
s_0 (mm)	-0.110	0.571
a_1 (mm/(MN/m ²))	7.722	3.553
a_2 (mm/(MN ² /m ⁴))	-9.115	-2.964
$E_v = 1.5 \cdot (a_1 + a_2 \cdot \sigma_{0,max})$	82.67	160.00
E_v2/E_v1	1.94	





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011




Fig. 3: Load-settlement curve, fitting curves according to Table 7 and Table 8 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_z Normal stress MN/m²



Kilo 23 Alexandria - Cairo Desert Road - Merghem
 Tel: 002 83 4704595 - 002 034701191
 Email: cindept@comibassal.com
 WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
 Tel: 002 033920176 - 002 033931482
 Fax :002 033900476
 Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011

Conclusions:

The present test results which were obtained via the plate loading tests of the native soil on upper embankment layer of the electric express train project at location from St(310+020) to St(310+170) in accordance to the German standard , DIN 18134 are illustrated in table 10 .

Table 10 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
St(310+050)	68.89	171.76	2.49
St(310+100)	83.18	144.57	1.74
St(310+150)	82.67	160.00	1.94

Lab Director

Eug / Eman Kandil




Geotechnical Consultant

For Dr. H.
Dr / Mohamed Mostafa Badry



MATERIAL INSPECTION REQUEST



Contractor Company	Orange for Import & Export and General Contracting Company				Designer Company				(KK) Engineering Consulting Office				
Issued by Contractor	Name		Sign		Date/ Serial Number				Time				
	Eng: Mohamed Fathy				01-05-2024 OR-M.I.290				10:00 AM				
Received by ER	Eng. Gaber Ibrahim				MIR	C1	C2	C3	DD	MM	YY	HH	MM
						309	EW	CS	01	05	24	10	00

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For the Kilometer point, only the Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	Fill Layer				
Location to be Used	From St. (309+820) To St. (309+950) (Ferma).				
MAR Approval No	(OR-M.A 087)			Date	15-04-2024
Supplier Name	EL-Sewy - EL-Moassa				
Test Requirement	P.L.T (DIN 18134)		Specification	EARTHWORK SPECIFICATIONS & TESTING REPORT (CG21-41.2) VERSION 2 BY CIVECON GROUP.	
Reference Photos	No		Other		
Item	Description	Unit	Quantity	Arrival Date	Note
1	Plate load test by Comibassal Lab	NUMBER	3	01-05-2024	
2					
3					
4					
Comments by : Eng. Hesham Sabry			Comments by: Eng. Hesham Sabry		
1. تم اختبار القطاع (Plate Loading Test) من قبل المعمل الهندسي (كومببسال). 2. تم تحقيق النتائج المطلوبة طبقاً لمواصفات المشروع.			1- P.L.T was carried out by Comibassal Lab, Attendances of material engineer for both contractor and GARB Consultant. 2- Results report attached and acceptable with project specifications 3- Final approval is subject to above mentioned comments.		

APPROVAL STATUS

Organisation	Name	Sign	Date	A-AWC-R
Contractor	Eng: Mohamed Fathy		01-05-2024	A
QA/QC *	Eng. Hesham Sabry			
GARB**	Eng. Ahmed Galal			
Employers Representative	Eng. Gaber Ibrahim			

* Designer

** Alignment / Bridges: Culvert Only



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011

Technical report

of Plate Loading Test (DIN 18134)

General	:	SYSTRA
Consultant	:	Dr/ Khaled Kandil
Contractor	:	مركبة اورنج للإستيراد والتصدير و المقلولات العامة
Project	:	ELECTRIC EXPRESS TRAIN
Sample	:	Upper Embankment
Station	:	ST(309+820) TO ST(309+950)
Date of Test	:	1/5/2024
QC	:	746 -1



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011

Introduction:

The Plate Load test is designed to determine the vertical deformation and strength characteristics of soil by assessing the force and amount of penetration with time when a rigid plate is made to penetrate the soil.

The test to be carried out on the native soil according to German specifications DIN 18134.

Test methods :

- 1- The German standard DIN 18134 was applied to define the apparatus used, the loading system, test conditions, and procedure for plate load test.
- 2- Loading plates with a diameter of 600 mm have a thickness of 25mm and are provided with equally spaced stiffeners with even upper faces parallel to the plate bottom face to allow 300 mm plate to be placed on top of it.
- 3- The loading system consisted of a hydraulic pump connected to a hydraulic jack of 700 bar capacity, which is capable of applying and releasing the load stages.
- 4- The dial gauge used to measure the plate settlement has a resolution of 0.01mm and the lever ratio was equal to 1.
- 5- The temperature at the time of the test was 25°.
- 6- The plate was carried out on a native soil (sand-gravel). The test surface area was levelled and the plate was bedded on this surface.
- 7- The hydraulic jack was placed on the middle of, and at normal to, the loading plate beneath the reaction loading system and secured against tilting.
- 8- The reaction loading system was a heavy multi-purpose excavator (more than 20 ton).

Description of experiment:

- 1- Loading, unloading and reloading regims were applied according to DIN 18134 for the plate load test to estimate the resilient modulus
- 2- Prior to the test, the force transducer and dial gauge were set to zero, after which a load was applied corresponding to a stress of 0.01 MN/m².
- 3- In the first loading cycle, the load was increased until a normal stress of 0.25 MN/m² was reached, and the loading increment was 0.025 MN/m². The load was released in four stages.
- 4- Following unloading, a further second loading cycle was carried out, in which, the load was increased only to the penultimate stage of the first cycle.



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701161
Email : cldept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave- Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : Internal-Inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011

St(309+840)

600

Table 1: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.11
2	14.14	0.050	0.19
3	21.21	0.075	0.34
4	28.28	0.100	0.50
5	35.35	0.125	0.71
6	42.42	0.150	0.83
7	49.49	0.175	0.96
8	56.56	0.200	1.06
9	63.63	0.225	1.17
10	70.7	0.250	1.29
11	56.56	0.200	1.28
12	49.49	0.175	1.27
13	35.35	0.125	1.25
14	21.21	0.075	1.13
15	1.414	0.005	0.75

Table 2: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.75
16	7.07	0.025	0.79
17	14.14	0.050	0.85
18	21.21	0.075	0.94
19	28.28	0.100	1.02
20	35.35	0.125	1.11
21	42.42	0.150	1.17
22	49.49	0.175	1.22
23	56.56	0.200	1.28
24	63.63	0.225	1.33

Table 3: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, max})$ MN/m ²	0.250	0.250
s_0 (mm)	-0.103	0.710
a_1 (mm/(MN/m ²))	6.828	3.399
a_2 (mm/(MN ² /m ⁴))	-4.992	-2.701
$E_v = 1.5 \pi / (a_1 + a_2 \cdot \sigma_{0, max})$	80.64	165.19
E_v2/E_v1	2.05	



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email : civdept@comibassal.com
WebSite : www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : Internal-Inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011




Fig. 1: Load-settlement curve, fitting curves according to Table 1 and Table 2 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_s Normal stress MN/m²





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/28-11-2011

St(309+890)

600

Table 4: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.11
2	14.14	0.050	0.28
3	21.21	0.075	0.45
4	28.28	0.100	0.64
5	35.35	0.125	0.83
6	42.42	0.150	0.98
7	49.49	0.175	1.10
8	56.56	0.200	1.21
9	63.63	0.225	1.31
10	70.7	0.250	1.40
11	56.56	0.200	1.39
12	49.49	0.175	1.38
13	35.35	0.125	1.35
14	21.21	0.075	1.20
15	1.414	0.005	0.70

Table 5: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.70
16	7.07	0.025	0.84
17	14.14	0.050	0.97
18	21.21	0.075	1.04
19	28.28	0.100	1.15
20	35.35	0.125	1.23
21	42.42	0.150	1.30
22	49.49	0.175	1.36
23	56.56	0.200	1.43
24	63.63	0.225	1.48

Table 6: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
$(\sigma_{0, max})$ MN/m ²	0.250	0.250
s_0 (mm)	-0.129	0.697
a_1 (mm/(MN/m ²))	8.990	5.324
a_2 (mm/(MN ² /m ⁴))	-11.439	-8.410
$E_v = 1.5 \pi / (s_1 + s_2 - \sigma_{0, max})$	73.41	139.69
$E_v 2/E_v 1$	1.90	



Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034781191
Email: cidept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011




Fig. 2: Load-settlement curve, fitting curves according to Table 4 and Table 5 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_s Normal stress MN/m²





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011

St(309+940)

600

Table 7: Measured values for first loading cycle and unloading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
0	1.414	0.005	0.00
1	7.07	0.025	0.15
2	14.14	0.050	0.35
3	21.21	0.075	0.51
4	28.28	0.100	0.75
5	35.35	0.125	0.89
6	42.42	0.150	1.02
7	49.49	0.175	1.14
8	56.56	0.200	1.25
9	63.63	0.225	1.35
10	70.7	0.250	1.44
11	56.56	0.200	1.43
12	49.49	0.175	1.42
13	35.35	0.125	1.39
14	21.21	0.075	1.27
15	1.414	0.005	0.75

Table 8: Measured values for second loading cycle

Loading stage no.	Load (F) kN	Normal stress (σ_0) MN/m ²	Settlement of loading plate S (mm)
15	1.414	0.005	0.75
16	7.07	0.025	0.85
17	14.14	0.050	0.97
18	21.21	0.075	1.07
19	28.28	0.100	1.18
20	35.35	0.125	1.25
21	42.42	0.150	1.30
22	49.49	0.175	1.36
23	56.56	0.200	1.40
24	63.63	0.225	1.46

Table 9: Compilation of results

Parameters	1st loading cycle	2nd loading cycle
($\sigma_{0, max}$) MN/m ²	0.250	0.250
s_0 (mm)	-0.082	0.726
s_1 (mm/(MN/m ²))	9.321	5.288
s_2 (mm/(MN ² /m ⁴))	-13.076	-9.270
$E_v = 1.5 \sigma' / (s_1 + s_2 \cdot \sigma_{0, max})$	74.35	151.46
E_v2/E_v1	2.04	

Kilo 23 Alexandria - Cairo Desert Road - Merghem
Tel: 002 03 4704595 - 002 034701191
Email: civdept@comibassal.com
WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
Tel: 002 033920176 - 002 033931482
Fax : 002 033900476
Email : internal-inspection@comibassal.com





COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egypt General Authority for Petroleum under No. 34/29-11-2011




Fig. 3: Load-settlement curve, fitting curves according to Table 7 and Table 8 for the first and second loading cycles

- Measurement points from the first loading cycle
- Measurement points from the unloading cycle
- ▲ Measurement points from the second loading cycle
- S Settlement in mm
- σ_0 Normal stress MN/m²



Kilo 23 Alexandria - Cairo Desert Road - Merghem
 Tel: 002 03 4704595 - 002 034701191
 Email: civdept@comibassal.com
 WebSite: www.comibassal.com



49 El Horria Ave. Alex, Egypt
 Tel: 002 033920176 - 002 033931482
 Fax :002 033900476
 Email : internal-inspection@comibassal.com



COMIBASSAL International Controllers

Internal inspection and laboratories sector

Accredited by : Egyptian General Authority for Petroleum under No. 34/29-11-2011

Conclusions:

The present test results which were obtained via the plate loading tests of the native soil on upper embankment layer of the electric express train project at location from St(309+820) to St(309+950) in accordance to the German standard , DIN 18134 are illustrated in table 10 .

Table 10 :Test results

Location	Ev1(MN/m ²)	Ev2(MN/m ²)	Ev2/Ev1 ratio
St(309+840)	80.64	165.19	2.05
St(309+890)	73.41	139.69	1.90
St(309+940)	74.35	151.46	2.04

Lab Director

Eng / Eman Kandil



Geotechnical Consultant

Dr / Mohamed Mostafa Badry

