



المنطقة الخامسة - (غرب الدلتا)

السيد المهندس / رئيس قطاع التنفيذ والمناطق

تحية طيبة.. وبعد،،

بالإحالة إلى مشروع القطار الكهربائي فائق السرعة قطاع (العلمين - فوكة)
نتشرف بأن نرفق لسيادتكم طيه المقياسة المعدلة بعد اعتماد لجنة المفاوضة للقطاعات
الآتية بتاريخ 2023/12/18 :

مسلسل	إسم الشركة	من المحطة	من المحطة	الاتجاه
1	شركة الحسن للمقاولات المتكاملة	453+600	454+600	رأس الحكمة

برجاء من سيادتكم التفضل بالأحاطه والتوجيه بالازم .

وتفضلوا بقبول فائق الاحترام والتقدير،،

رئيس الإدارة المركزية

المنطقة الخامسة- غرب الدلتا

عميد مهندس //

"هاني محمد محمود طه"



مركز الاستشارات الهندسية
للتفصيل والمطارات والطرق
(خبراء دوليون)
دكتور/ سعد الجبوشي



الهيئة العامة
للمطارات والكباري
(GARB)



مشروع القطار الكهربائي فائق السرعة قطاع (العلمين - فوكة)

أعمال تشكيل الجسر الترابي

المقايضة المعدلة بعد المفاوضة بتاريخ ٢٠٢٣/١٢/١٨ لبنود الاعمال تنفيذ شركة الحسن للمقاولات المتكاملة اتجاة رأس الحكمة

القطاع من المحطة ٤٥٢+٦٠٠ الى ٤٥٤+٦٠٠

رقم البند	بيان الأعمال	الوحدة	الكمية	القيمة	الإجمالي
١	أعمال الحفر				
١-١	بالمتر المكعب أعمال حفر باستخدام المعدات الميكانيكية لجميع أنواع التربة عدا التربة الصخرية و تسوية السطح بالآلات التسوية والرش بالمياه الاصلوية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراست للوصول الى أقصى كثافة جافة (95%) من الكثافة الجافة القصوى (ومحمل على البند تحميل ونقل التربة الزائدة لمسافة ٥٠٠ متر من محور الطريق ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقا لاصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندس المشرف . علاوة ١,١ جنيه / كم لمسافة نقل ناتج الحفر .	م ^٣	١٥٨٥٧,٣٠	٢٦,٥	٤٢٠,٢١٨
٢-١	بالمتر المكعب أعمال الحفر باستخدام المعدات الميكانيكية في التربة المتساكنة عدا التربة الصخرية (باستخدام البلدوزر) وتسوية السطح بالآلات التسوية والرش بالمياه الاصلوية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراست للوصول الى أقصى كثافة جافة (95%) من الكثافة الجافة القصوى (ومحمل على البند تحميل ونقل التربة الزائدة لمسافة ٥٠٠ متر من محور الطريق ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقا لاصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندس المشرف . علاوة ١,١ جنيه / كم لمسافة نقل ناتج الحفر .	م ^٣	١٧,٩٥	٣٠,٥	٥٢١,٣٩٨
٣	أعمال الردم				
١-٣	أعمال تحميل وتوريد ونقل التربة مطابقة للمواصفات وتشغيلها باستخدام آلات التسوية بسمك لا يزيد عن ٥٠ سم حتى منسوب (2.00 متر) وبسمك لا يزيد عن ٢٥ سم لاستكمال المنسوب التصميمي لتشكيل الجسر الترابي والاكثاف (نسبة تحمل كاليفورنيا لا تقل عن ١٥ %) ورشها بالمياه الاصلوية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراست للوصول الى أقصى كثافة جافة (95%) من الكثافة الجافة القصوى (ويتم التنفيذ طبقا للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتلاته طبقا لاصول الصناعة ومواصفات الهيئة العامة للطرق والكباري وتعليمات المهندس المشرف . - في حالة طلب جهاز الإشراف زيادة نسبة الدمك عن ٩٥% بحسب زيادة ١ جنيه على زيادة نسبة الدمك لكل ١ % مسافة النقل حتى ٢ كم ويتم احتساب علاوة ١,٥ جنيه لكل بالزيادة او النقصان السعر يشمل عمل تشوينات وتخليط واختبارات ونقل لموقع العمل حتى مسافة ٢ كم السعر يشمل قيمة المادة المحجرة علاوة مسافة النقل ٢٠٦ كم علاوة تحميل الكارته والموازن طبقا للاحه الشركة الوطنية	م ^٣	١١٣١٨,٧٠٦١	١٠١,٤	١,١٤٧,٧١٧
		م ^٣	١١٣١٨,٧٠٦١	٣٠٦,٠٠	٣,٤٦٣,٥٢٤
		م ^٣	١١٣١٨,٧٠٦١	١٣,٠٠	١٤٧,١٤٣
	الإجمالي				٥,٧٠٠,٠٠٠,٠

(خمس مائة وسبع مائة ألف جنيه فقط لا غير)

مدير عام المشروعات
م / محمد حسني فياض

مدير المشروع والمالك
م / إبراهيم عبد الله الحناوي

مدير المشروع الاستشاري
م / مصطفى محمود نجم

مدير المشروع المقاول
م / محمود دسوقي دسوقي


يعتمد

رئيس الإدارة المركزية
منطقة غرب الدلتا

الاسكندرية - مرسى مطروح

عميد مهندس /

" هاني محمد محمود طه "



قائمة الكميات الواردة بالمستخلص جاري (٢)

مشروع : القطار الكهربائي السريع (العين السخنة -العاصمة الادارية -العلمين -مطروع) قطاع غرب النيل في المسافة من الكم ٤٥٣,٦٠٠ الى الكم ٤٥٤,٦٠٠ بطول ١ كيلو متر اتجاه رأس الحكمة

رقم البند و بيانه : (١-١) بالمتر المكعب أعمال حفر باستخدام المعدات الميكانيكية في التربة المتماسكة عدا التربة الصخرية

تنفيذ : مكتب الحسن للمقاولات المتكاملة

مقدار العمل السابق : ٠,٠ ٣م

الكمية	الابعاد (متر)		الموقع الكيلومتری		بيان الاعمال بالمقايضة
	مساحة المقطع	طول	الى	من	
١٥٨٥٧,٣٠	٢٦٤,٢٨٨	٦٠	٤٥٣+٦٦٠	٤٥٣+٦٠٠	القطاع الأول
١٥٨٥٧,٣٠	اجمالي الكميات خلال فترة المستخلص الحالية (م ^٣)				
١٥٨٥٧,٣٠	الاجمالي الكلي (م ^٣)				

مهندس الاستشاري

مهندس الاستشاري

مهندس الهيئة

مكتب د/سعد الجيوشي

مكتب XYZ

مهندس الشركة

م / إبراهيم عبدالله الحناوى

م/مصطفى محمود نجم

م / محمد شهاب خليل

م/محمود دسوقي دسوقي

قائمة الكميات الواردة بالمستخلص جاري (٢)

مشروع : القطار الكهربائي السريع (العين السخنة -العاصمة الادارية -العلمين -مطروع) قطاع غرب النيل في المسافة من
الكم ٤٥٣,٦٠٠ الى الكم ٤٥٤,٦٠٠ بطول ١ كيلو متر اتجاه رأس الحكمة

رقم البند و بيانه : (٢-١) بالمتر المكعب أعمال حفر باستخدام المعدات الميكانيكية في التربة المتماسكة عدا التربة
الصخرية (باستخدام البلدوزر)

تنفيذ : مكتب الحسن للمقاولات المتكاملة

مقدار العمل السابق : ٠,٠ م ٣

الكمية	الابعاد (متر)		الموقع الكيلومتری		بيان الاعمال بالمقايضة
	مساحة المقطع	طول	الى	من	
١٧٠٩٥	١٧٠,٩٥٠	١٠٠	٤٥٣+٨٢٠	٤٥٣+٧٢٠	القطاع الأول
١٧٠٩٥	اجمالي الكميات خلال فترة المستخلص الحالية (م ^٢)				
١٧٠٩٥	الاجمالي الكلي (م ^٢)				

مهندس الاستشاري

مهندس الاستشاري

مهندس الهيئة
م / إبراهيم عبدالله الحناوى

مكتب د/سعد الجيوشي
م/مصطفى محمود نجم

مكتب XYZ
م / محمد شهاب خليل

مهندس الشركة
م /محمود دسوقي دسوقي



مشروع : القطار الكهربائي السريع (العين السخنة -العاصمة الادارية -العلمين -مطروح) قطاع غرب النيل في المسافة من الكم ٤٥٣,٦٠٠ الى الكم ٤٥٤,٦٠٠ بطول ١ كيلو متر اتجاه رأس الحكمة .

تنفيذ : مكتب الحسن للمقاولات المتكاملة

الكمية	الابعاد (متر)		الموقع الكيلوميتري		بيان الاعمال بالمقايسة
	مساحة المقطع	طول	الى	من	
٢٦١٦,٣٩٩	٥,٢٣٣	٥٠٠	٤٥٤+١٠٠	٤٥٣+٦٠٠	القطاع الأول
٨٧٠٢,٣٠٧	١٧,٤٠٥	٥٠٠	٤٥٤+٦٠٠	٤٥٤+١٠٠	القطاع الثاني
١١٣١٨,٧٠٦١	اجمالي الكميات خلال فترة المستخلص الحالية (٣م)				
١١٣١٨,٧٠٦١	الاجمالي الكلي (٣م)				

مهندس الشركة
م / محمود دسوقي دسوقي
محمود دسوقي

قائمة الكميات الواردة بالمستخلص جاري (٢)

مشروع : القطار الكهربائي السريع (العين السخنة -العاصمة الادارية -العلمين -مطروح) قطاع غرب النيل في المسافة من الكم ٤٥٣,٦٠٠ الى الكم ٤٥٤,٦٠٠ بطول ١ كيلو متر اتجاه رأس الحكمة .

رقم البند و بيانه : (١-٣) أعمال توريد وتشغيل اترية صالحة للردم

تنفيذ : مكتب الحسن للمقاولات المتكاملة

مقدار العمل السابق : ٠,٠ م ٣

الكمية	الابعاد (متر)		الموقع الكيلومتری		بيان الاعمال بالمقايضة
	مساحة المقطع	طول	الى	من	
٢٦١٦,٣٩٩	٥,٢٣٣	٥٠٠	٤٥٤+١٠٠	٤٥٣+٦٠٠	القطاع الأول
٨٧٠٢,٣٠٧	١٧,٤٠٥	٥٠٠	٤٥٤+٦٠٠	٤٥٤+١٠٠	القطاع الثاني
١١٣١٨,٧٠٦١	اجمالي الكميات خلال فترة المستخلص الحالية (م ^٢)				
١١٣١٨,٧٠٦١	الاجمالي الكلي (م ^٢)				

مهندس الاستشاري

مهندس الاستشاري

مهندس الهيئة
م / إبراهيم عبدالله الحناوى

مكتب د/ سعد الجيوشي
م/ مصطفى محمود نجم

مكتب XYZ
م / محمد شهاب خليل

مهندس الشركة
م/ محمود دسوقي دسوقي

قائمة الكميات الواردة بالمستخلص جاري (٢)

مشروع : القطار الكهربائي السريع (العين السخنة -العاصمة الادارية -العلمين -مطروح) قطاع غرب النيل في المسافة من الكم ٤٥٣,٦٠٠ الى الكم ٤٥٤,٦٠٠ بطول ١ كيلو متر اتجاه رأس الحكمة .

رقم البند و بيانه : (١-٣) علاوة مسافة النقل ٢٠.٦ كم

تنفيذ : مكتب الحسن للمقاولات المتكاملة

مقدار العمل السابق : ٣٠٠ م

الكمية	الابعاد (متر)		الموقع الكيلومتری		بيان الاعمال بالمقايضة
	مساحة المقطع	طول	الى	من	
٢٦١٦,٣٩٩	٥,٢٣٣	٥٠٠	٤٥٤+١٠٠	٤٥٣+٦٠٠	القطاع الأول
٨٧٠٢,٣٠٧	١٧,٤٠٥	٥٠٠	٤٥٤+٦٠٠	٤٥٤+١٠٠	القطاع الثاني
١١٣١٨,٧٠٦١	اجمالي الكميات خلال فترة المستخلص الحالية (٣م)				
١١٣١٨,٧٠٦١	الاجمالي الكلي (٣م)				

مهندس الاستشاري

مهندس الاستشاري

مهندس الهيئة

م / إبراهيم عبد الله الحناوى

مكتب د/ سعد الجيوشي

م/مصطفى محمود نجم

مكتب XYZ

م / محمد شهاب خليل

مهندس الشركة

م /محمود دسوقي دسوقي

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+600) : (454+260)
Type of sample : Soil Embankment (Upper Embankment)
Delivery Date : 06/01/2023
Reporting Date : 12/01/2023
Reporting No. : 12
Sample No. : 01

Dear Gentleman,

Attached here with the Soil Embankment delivered on 06/01/2023

Materials test

1. Sieve analysis according to ASTM D-422.
2. Material finer than sieve No. 200 according to ASTM D-1140.
3. Liquid limits and plasticity index of soil according to ASTM D-4318.
4. Soil classification according to Project Specs.
5. Proctor Test according to ASTM D-1557

Note: The sample was brought by the client to our laboratory and the laboratory is not responsible for the way it is taken

Signature /


Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+600) : (454+260)
Type of sample : Soil Embankment (Upper Embankment)
Delivery Date : 06/01/2023
Reporting Date : 12/01/2023
Reporting No. : 12
Sample No. : 01

RESULTS OF SIEVE ANALYSIS According to ASTM D-422.

Sieve Size (mm)	Passing %
50	100
37.5	97.2
25	91.6
19	86.5
12.50	75.1
9.50	64.7
4.75	50.4
2.36	48.8
2.00	47.4
1.18	33.8
0.600	29.6
0.425	27.1
0.300	20.8
0.150	16.9

Signature /

CEL
مكتب معامل الاستشارات الهندسية
المعامل الشمالية
رقم تسجيل مصري 837 - 819 - 091
مركز 31 شارع هادي - القاهرة - 11515

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+600) : (454+260)
Type of sample : Soil Embankment (Upper Embankment)
Delivery Date : 06/01/2023
Reporting Date : 12/01/2023
Reporting No. : 12
Sample No. : 01

Materials finer than 75 μ m (no.200) sieve
by washing ASTM D-1140.

Test	Results (%)
Percentage of material finer than Sieve Size 75 μ M (No.200)	14.5



Signature /.....

CEL

Consulting Engineering Bureau & Laboratories
مكتب معامل الاستشارات الهندسية

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+600) : (454+260)
Type of sample : Soil Embankment (Upper Embankment)
Delivery Date : 06/01/2023
Reporting Date : 12/01/2023
Reporting No. : 12
Sample No. : 01

**Results of liquid limit and plasticity index
of soils according to ASTM D-4318**

Test	Results (%)
Liquid Limit	NP
Plastic Limit	NP
Plasticity Index	NP

Signature /



4

3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093



٣ ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : مكتب الحسن للمقاولات المتكاملة
 Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
 Location : St. (453+600) : (454+260)
 Type of sample : Soil Embankment (Upper Embankment)
 Delivery Date : 06/01/2023
 Reporting Date : 12/01/2023
 Reporting No. : 12
 Sample No. : 01

Soil Classification According to Project Specs (Embankment)

TEST	Results (%)	Limits according Projects Specs	
		(A-1-a)	(A-1-b)
• Group Classification	(A-1-a)	(A-1-a)	(A-1-b)
2.00 mm (No.10).	47.4	Max 50 %	-----
0.425 mm (No. 40).	27.1	Max 30 %	Max 50 %
0.075 mm (No. 200).	14.5	Max 15 %	Max 15 %
Characteristics of fraction passing 0.425 mm (No.40)			
Liquid Limit	NP	-----	-----
Plasticity index	NP	Max 6 %	Max 6 %

The test results are (☒ Comply - ☐ Not Comply) with specifications limits

Signature /


3 El Malek El Afdal Street
 Zamalek, Cairo.
 Tel. & Fax : 27367231 - 27363093



ش الملك الأفضل
 الزمالك - القاهرة
 تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
 www.cel-egypt.com

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+600) : (454+260)
Type of sample : Soil Embankment (Upper Embankment)
Delivery Date : 06/01/2023
Reporting Date : 12/01/2023
Reporting No. : 12
Sample No. : 01

Moisture – Density relation of soil
Test result (Modified proctor test)
ASTM D-1557



- Max dry density (gm/cm³) : 2.10
- Optimum moisture content % : 7.5

Signature

CEL
مكتب معامل الاستشارات الهندسية
المساحل الشمالي
رقم تسجيل المهندس : ١٧٧٢٣١ - ١٧٧٢٣٠٩٣
إدارة الترخيص : ١٧٧٢٣١ - ١٧٧٢٣٠٩٣

3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093

IAS
ACCREDITED
Testing Laboratory

٣ ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ١٧٧٢٣١ - ١٧٧٢٣٠٩٣
www.cel-egypt.com

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Dear Gentleman,

Attached here with the Soil Embankment delivered on 09/01/2023

Materials test

1. Sieve analysis according to ASTM D-422.
2. Material finer than sieve No. 200 according to ASTM D-1140.
3. Liquid limits and plasticity index of soil according to ASTM D-4318.
4. Soil classification according to Project Specs.
5. Proctor Test according to ASTM D-1557
6. CBR according to ASTM D-1883

Note: The sample was brought by the client to our laboratory and the laboratory is not responsible for the way it is taken

Signature /



3 El Malek El Afdal Street
Zamalek, Cairo.
Tel. & Fax : 27367231 - 27363093



ش ٣ الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Tel. & Fax : 27367231 - 27363093

www.cel-egypt.com

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

RESULTS OF SIEVE ANALYSIS According to ASTM D-422.

Sieve Size (mm)	Passing %
50	100
37.5	96.1
25	93.6
19	87.3
12.50	78.2
9.50	63.5
4.75	46.2
2.36	43.8
2.00	40.4
1.18	35.9
0.600	30.2
0.425	28.1
0.300	22.2
0.150	15.9

Signature / ...

CEL
مكتب معامل الاستشارات الهندسية
المنطقة الشمالية
رقم تسجيل تجاري: 537 - 091 - 27363093
شارع النيل 31
المنطقة الشمالية

CELConsulting Engineering Bureau & Laboratories
مكتب معامل الاستشارات الهندسية

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Materials finer than 75 μ m (no.200) sieve
by washing ASTM D-1140.

Test	Results (%)
Percentage of material finer than Sieve Size 75 μ m (No.200)	13.9

Signature /



Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Results of liquid limit and plasticity index
of soils according to ASTM D-4318

Test	Results (%)
Liquid Limit	NP
Plastic Limit	NP
Plasticity Index	NP

Signature / ...

مكتب معامل الاستشارات الهندسية
أنساجل الشمصالي
رقم تسجيل تجاري 210-001-027
مركز شامس : شارع محمد النور - شامس

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Soil Classification According to Project Specs (Embankment)

TEST	Results (%)	Limits according Projects Specs	
• Group Classification	(A-1-a)	(A-1-a)	(A-1-b)
2.00 mm (No.10).	40.4	Max 50 %	-----
0.425 mm (No. 40).	28.1	Max 30 %	Max 50 %
0.075 mm (No. 200).	13.9	Max 15 %	Max 15 %
Characteristics of fraction passing 0.425 mm (No.40)			
Liquid Limit	NP	-----	-----
Plasticity index	NP	Max 6 %	Max 6 %


The test results are (☒ Comply - ☐ Not Comply) with specifications limits

مكتب معامل الاستشارات الهندسية
المصالح الشمالية
بم. تسجيل قطري 319-091-037
3 شارع شوك الأنجل - زمامك - القاهرة
إملاك شامس

Signature /

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Moisture – Density relation of soil
Test result (Modified proctor test)
ASTM D-1557



- Max dry density (gm/cm³) : 2.09
- Optimum moisture content % : 7.1

Signature /



Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Test Results of California Bearing Ratio on Base Materials
ASTM D 1883

penetration		stress on piston (Mpa)
mm	Inch	
0.64	0.025	1.95
1.27	0.050	2.21
1.91	0.075	2.36
2.54	0.100	2.56
3.18	0.125	2.81
3.81	0.150	3.02
4.45	0.175	3.22
5.08	0.200	3.47
5.71	0.225	3.63
6.35	0.250	3.73

CBR Result	Stress (Mpa)		CBR %
At 0.1 inch (2.54 mm) penetration	St. Value	Sample results	37.1
	6.90	2.56	

Notes :

- 1- Attached graph shows penetration resistance versus penetration magnitude.
- 2- The sample was compacted to dry density of 2.09 (gm /cm³) at 7.1 % optimum water content.
- 3- Surcharge load 4.50 Kg

Signature / ...

مكتب معامل الاستشارات الهندسية
الساحل الشمالي
رقم تسجيل قديم : 537 - 991
مركز شاتيس : شارع هبة القوي - الزمالة - القاهرة


3 El Malek El Afdal Street
Zamalek, Cairo.
Tel.& Fax : 27367231 - 27363093



٣ ش الملك الأفضل
الزمالك - القاهرة
تليفون + فاكس : ٢٧٣٦٧٢٣١ - ٢٧٣٦٣٠٩٣
www.cel-egypt.com

Company Name : مكتب الحسن للمقاولات المتكاملة
Project : Electric Express Train, from Al Ain Sokhna to Marsa Matrouh
Location : St. (453+760) : (454+600)
Type of sample : Soil Embankment (Middle Embankment)
Delivery Date : 09/01/2023
Reporting Date : 15/01/2023
Reporting No. : 13
Sample No. : 02

Load Penetration Curve of CBR Test
ASTM D-1883



Signature /



Horema for Soil Investigation & QC.

5 Mostafa Kamel st., Smouha, Alexandria

Tel./Fax : +203 4243784 , +203 4272604

El-Hassan company

GEOTECHNICAL REPORT
FOR ANALYSING OF EIGHT PLATE LOADING TESTS
CARRIED OUT AT ALDABAA
FOR THE PROJECT OF ELECTRIC EXPRESS TRAIN

Station 453+600 to 455+600

Level -1.50 m

Prepared by Prof. Dr Mostafa Abu Kiefa

2023

TABLE OF CONTENTS


	Page
1.0 INTRODUCTION	3
2.0 DESCRIPTION OF EXPERIMENTS	3
3.0 ANALYSIS OF RESULTS	3
4.0 CONCLUSIONS	6
APPENDIX (A)	

1- INTRODUCTION

This report has been prepared upon the request of Al-Hassan Company. The study deals with the area specified to the Electric Express Train at Al-Dabaa. 19 double repetitive static plate loading tests were conducted in accordance with the DIN 18134 slandered specifications. The plate loading tests were conducted by **Horema** (LTD). The purpose of these tests is to obtain the relationship between the loading and soil settlement due to each load, which can be used to determine the soil strain modulus (E_v) and the modulus of sub-grade reaction (k_s).

2- DESCRIPTION OF EXPERIMENTS

The loading experiments were conducted at certain locations at the route of the Electric Express Train at Al-Dabaa. 19 plate load tests were carried out on Silty SAND with Gravel at **wet** conditions using a load disc of 75 cm diameter in locations identified by the Client. The plate loading tests were conducted (at-1.50 m) in accordance with the DIN 18134 slandered specifications. As per code DIN 18134 apply the load to the soil in cumulative equal increments. The conducted stress increment was 0.30 kg/cm^2 (0.03 MN/m^2)(Mpa). A gradual applied loading up to 3 kg/cm^2 (0.30 MN/m^2)(Mpa) and the corresponding soil settlement was measured per load increment. Each test was carried out into two loading cycles. The first loading cycles consisted of loading and reloading, while the second loading cycle consisted of loading only. The results of all tests are shown in appendix (A).



3- ANALYSIS OF RESULTS

The obtained results showed that the loading and settlement curves did not show any shear failure occurred to the **wet** soil during the test. The settlements values corresponding to the final stage of two loading cycles did not exceed 1/10 of the load diameter. The strain modulus (E_v) and the modulus of sub-grade reaction (k_s) for the conducted tests are shown in appendices (A). In order to

evaluated the obtained results of the repetitive plate loading tests, the following target values were considered:

The following table shows a summary of the obtained results:



PL T No .	Station Al-Dabaa level -1.5	E_{v1} (MN/m ²) (Mpa)	E_{v2} (MN/m ²) (Mpa)	E_{v2}/E_{v1}	Sub-Grade Reaction k_s (MN/m ³)
21	454+200 to 454+300	89.1	243.6	2.73	156.8
22	454+100 to 454+200	93	236.1	2.54	156.8
23	454+000 to 454+100	93.9	241.1	2.57	164
24	453+900 to 454+00	87.9	227.4	2.59	154.4
25	453+800 to 453+900	89.5	241.1	2.69	158.4
26	453+700 to 453+800	89.9	232.1	2.58	157.6
27	453+600 to 453+700	92.9	241.1	2.59	156.8
28	454+300 to 454+400	79.3	210.9	2.66	143.2
29	454+400 to 454+500	79	210.9	2.67	144
30	454+500 to 454+600	75.4	188.7	2.5	136.8
31	454+600 to 454+700	80.9	210.9	2.61	144
32	454+800 to 454+900	77.3	198.6	2.57	139.2
33	454+900 to 455+000	75.5	198.6	2.63	135.2
34	455+000 to 455+100	77.3	198.6	2.57	138.4
35	455+100 to 455+200	71.6	187.5	2.62	128
36	455+200 to 455+300	71.5	185.6	2.6	128.8
37	455+300 to 455+400	80.4	201.5	2.51	142.4
38	455+400 to 455+500	90.8	244.1	2.69	159.2
39	455+500 to 455+600	84.3	224.1	2.66	148
Minimum		71.50	185.60	2.50	128.00
Average		83.13	216.97	2.61	146.95

4- CONCLUSIONS


This report deals with the area specified to the Electric Express Train at Al-Dabaa. 19 plate loading tests were conducted in accordance with the DIN 18134 slandered specifications. The plate loading tests were conducted by **Horema** (LTD). The relationship between the loading and soil settlement for each test was obtained and soil strain modulus (E_v) and the modulus of sub-grade reaction (k_s) were determined.

Consulting Engineer

M. Abu Kiefa

Dr. Mostafa Abu Kiefa

Geotechnical Engineering Office,
Prof. of Geotechnical Engineering
Cairo University – Egypt





APPENDIX (A)


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+200) to (454+300) level (-1.5)
PLATE LOAD NO. PLT-21
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 6:00 AM
TIME FINISH: 9:00 AM
DATE 11-Jan-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.40
0.09	0.60
0.12	0.80
0.15	0.98
0.18	1.17
0.21	1.35
0.24	1.54
0.27	1.73
0.30	1.91
0.27	1.82
0.21	1.68
0.15	1.54
0.09	1.40
0.03	1.26
0.00	1.09
0.03	1.18
0.06	1.24
0.09	1.30
0.12	1.37
0.15	1.44
0.18	1.51
0.21	1.58
0.24	1.65
0.27	1.72
0.30	1.79



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.511	2.302
a_2 [mm/(MN ² /m ⁴)]	-0.66	0.024
E_v [MN/m ²][Mpa]	89.1	243.6
E_{v2}/E_{v1}	2.73	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 156.8 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+100) to (454+200) level (-1.5)
PLATE LOAD NO. PLT-22
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 9:00 AM
TIME FINISH: 12:00 PM
DATE 11-Jan-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.28
0.06	0.46
0.09	0.65
0.12	0.84
0.15	1.03
0.18	1.22
0.21	1.36
0.24	1.56
0.27	1.73
0.30	1.92
0.27	1.83
0.21	1.69
0.15	1.55
0.09	1.41
0.03	1.27
0.00	1.11
0.03	1.18
0.06	1.25
0.09	1.32
0.12	1.39
0.15	1.46
0.18	1.53
0.21	1.60
0.24	1.67
0.27	1.74
0.30	1.84



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.16	2.222
a_2 [mm/(MN ² /m ⁴)]	-0.378	0.536
E_v [MN/m ²][Mpa]	93.0	236.1
E_{v2}/E_{v1}	2.54	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 156.8 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+000) to (454+100) level (-1.5)
PLATE LOAD NO. PLT-23
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 12:00 PM
TIME FINISH: 3:00 PM
DATE 11-Jan-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.39
0.09	0.56
0.12	0.71
0.15	0.89
0.18	1.08
0.21	1.28
0.24	1.47
0.27	1.66
0.30	1.83
0.27	1.74
0.21	1.60
0.15	1.46
0.09	1.32
0.03	1.18
0.00	1.04
0.03	1.11
0.06	1.18
0.09	1.25
0.12	1.32
0.15	1.39
0.18	1.46
0.21	1.53
0.24	1.60
0.27	1.67
0.30	1.74



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	5.532	2.333
a_2 [mm/(MN ² /m ⁴)]	1.53	0
E_v [MN/m ²][Mpa]	93.9	241.1
E_{v2}/E_{v1}	2.57	



MODULUS OF SUB-GRADE REACTION, K_s

$$k_s = \Delta\sigma/\Delta s \quad 164.0 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (453+900) to (454+000) level (-1.5)
PLATE LOAD NO. PLT-24
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 3:00 PM
TIME FINISH: 6:00 PM
DATE 11-Jan-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.40
0.09	0.60
0.12	0.79
0.15	0.98
0.18	1.18
0.21	1.37
0.24	1.55
0.27	1.74
0.30	1.94
0.27	1.85
0.21	1.71
0.15	1.57
0.09	1.43
0.03	1.29
0.00	1.09
0.03	1.16
0.06	1.23
0.09	1.30
0.12	1.37
0.15	1.44
0.18	1.51
0.21	1.59
0.24	1.66
0.27	1.73
0.30	1.86



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.483	2.096
a_2 [mm/(MN ² /m ⁴)]	-0.281	1.257
E_v [MN/m ²][Mpa]	87.9	227.4
E_{v2}/E_{v1}	2.59	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 154.4 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (453+800) to (453+900) level (-1.5)
PLATE LOAD NO. PLT-25
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 6:00 AM
TIME FINISH: 9:00 AM
DATE 11-Jan-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.20
0.06	0.39
0.09	0.59
0.12	0.78
0.15	0.97
0.18	1.16
0.21	1.34
0.24	1.52
0.27	1.71
0.30	1.89
0.27	1.80
0.21	1.66
0.15	1.52
0.09	1.38
0.03	1.24
0.00	1.10
0.03	1.17
0.06	1.24
0.09	1.31
0.12	1.38
0.15	1.45
0.18	1.52
0.21	1.59
0.24	1.66
0.27	1.73
0.30	1.80



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.576	2.333
a_2 [mm/(MN ² /m ⁴)]	-0.974	0
E_v [MN/m ²][Mpa]	89.5	241.1
E_{v2}/E_{v1}	2.69	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 158.4 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (453+700) to (453+800) level (-1.5)
PLATE LOAD NO. PLT-26
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 9:00 AM
TIME FINISH: 12:00 PM
DATE 11-Jan-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.22
0.06	0.40
0.09	0.58
0.12	0.76
0.15	0.96
0.18	1.15
0.21	1.34
0.24	1.53
0.27	1.72
0.30	1.91
0.27	1.82
0.21	1.68
0.15	1.54
0.09	1.40
0.03	1.26
0.00	1.08
0.03	1.15
0.06	1.22
0.09	1.29
0.12	1.36
0.15	1.43
0.18	1.50
0.21	1.57
0.24	1.64
0.27	1.73
0.30	1.82



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.07	2.163
a_2 [mm/(MN ² /m ⁴)]	0.627	0.867
E_v [MN/m ²][Mpa]	89.9	232.1
E_{v2}/E_{v1}	2.58	



MODULUS OF SUB-GRADE REACTION, K_s

$$k_s = \Delta\sigma/\Delta s \quad 157.6 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+300)To(454+400) Level (-1.50)
PLATE LOAD NO. PLT-28
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 8:00 AM
TIME FINISH: 10:00 AM
DATE 12-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.18
0.06	0.39
0.09	0.60
0.12	0.81
0.15	1.02
0.18	1.23
0.21	1.45
0.24	1.67
0.27	1.88
0.30	2.10
0.27	1.99
0.21	1.83
0.15	1.67
0.09	1.51
0.03	1.35
0.00	1.19
0.03	1.27
0.06	1.35
0.09	1.43
0.12	1.51
0.15	1.59
0.18	1.67
0.21	1.75
0.24	1.83
0.27	1.91
0.30	1.99



STRAIN MODULUS, Ev

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.911	2.667
a_2 [mm/(MN ² /m ⁴)]	0.61	0
E_v [MN/m ²][Mpa]	79.3	210.9
E_{v2}/E_{v1}	2.66	



MODULUS OF SUB-GRADE REACTION, Ks

$k_s = \Delta\sigma/\Delta s$ 143.2 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+400)To(454+500)Level (-1.50)
PLATE LOAD NO. PLT-29
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 10:00 AM
TIME FINISH: 12:00 PM
DATE 12-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.17
0.06	0.37
0.09	0.58
0.12	0.80
0.15	1.02
0.18	1.22
0.21	1.44
0.24	1.66
0.27	1.88
0.30	2.09
0.27	1.99
0.21	1.83
0.15	1.67
0.09	1.51
0.03	1.35
0.00	1.19
0.03	1.27
0.06	1.35
0.09	1.43
0.12	1.51
0.15	1.59
0.18	1.67
0.21	1.75
0.24	1.83
0.27	1.91
0.30	1.99



STRAIN MODULUS, Ev

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.967	2.667
a_2 [mm/(MN ² /m ⁴)]	0.516	0
E_v [MN/m ²][Mpa]	79.0	210.9
E_{v2}/E_{v1}	2.67	



MODULUS OF SUB-GRADE REACTION, Ks

$k_s = \Delta\sigma/\Delta s$ 144.0 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+500)To(454+600)Level (-1.50)
PLATE LOAD NO. PLT-30
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 12:00 PM
TIME FINISH: 2:00 PM
DATE 12-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.19
0.06	0.40
0.09	0.63
0.12	0.84
0.15	1.07
0.18	1.30
0.21	1.52
0.24	1.76
0.27	1.98
0.30	2.20
0.27	2.10
0.21	1.93
0.15	1.76
0.09	1.59
0.03	1.42
0.00	1.25
0.03	1.33
0.06	1.42
0.09	1.51
0.12	1.60
0.15	1.69
0.18	1.78
0.21	1.87
0.24	1.96
0.27	2.05
0.30	2.14



STRAIN MODULUS, Ev

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	7.229	2.907
a_2 [mm/(MN ² /m ⁴)]	0.755	0.246
E_v [MN/m ²] [Mpa]	75.4	188.7
E_{v2}/E_{v1}	2.50	



MODULUS OF SUB-GRADE REACTION, Ks

$$k_s = \Delta\sigma / \Delta s \quad 136.8 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+600)to(454+700)Level (-1.50)
PLATE LOAD NO. PLT-31
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 2:00 PM
TIME FINISH: 4:00 PM
DATE 12-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.22
0.06	0.42
0.09	0.63
0.12	0.83
0.15	1.05
0.18	1.25
0.21	1.46
0.24	1.67
0.27	1.89
0.30	2.11
0.27	2.01
0.21	1.85
0.15	1.68
0.09	1.52
0.03	1.36
0.00	1.20
0.03	1.28
0.06	1.36
0.09	1.44
0.12	1.52
0.15	1.60
0.18	1.68
0.21	1.76
0.24	1.84
0.27	1.92
0.30	2.00



STRAIN MODULUS, Ev

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.659	2.667
a_2 [mm/(MN ² /m ⁴)]	0.981	0
E_v [MN/m ²] [Mpa]	80.9	210.9
E_{v2}/E_{v1}	2.61	



MODULUS OF SUB-GRADE REACTION, Ks

$$k_s = \Delta\sigma / \Delta s \quad 144.0 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (453+600) to (453+700) level (-1.5)
PLATE LOAD NO. PLT-27
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 12:00 PM
TIME FINISH: 3:00 PM
DATE 11-Jan-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.39
0.09	0.58
0.12	0.75
0.15	0.94
0.18	1.12
0.21	1.30
0.24	1.49
0.27	1.67
0.30	1.84
0.27	1.75
0.21	1.61
0.15	1.47
0.09	1.33
0.03	1.19
0.00	1.05
0.03	1.12
0.06	1.19
0.09	1.26
0.12	1.33
0.15	1.40
0.18	1.47
0.21	1.54
0.24	1.61
0.27	1.68
0.30	1.76



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.134	2.333
a_2 [mm/(MN ² /m ⁴)]	-0.271	0
E_v [MN/m ²][Mpa]	92.9	241.1
E_{v2}/E_{v1}	2.59	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 156.8 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+800) to (454+900) level (-1.50)
PLATE LOAD NO. PLT-32
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 8:00 AM
TIME FINISH: 10:00 AM
DATE 30-Mar-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.18
0.06	0.38
0.09	0.60
0.12	0.81
0.15	1.03
0.18	1.25
0.21	1.47
0.24	1.70
0.27	1.93
0.30	2.15
0.27	2.05
0.21	1.88
0.15	1.71
0.09	1.54
0.03	1.37
0.00	1.20
0.03	1.29
0.06	1.38
0.09	1.47
0.12	1.56
0.15	1.65
0.18	1.73
0.21	1.81
0.24	1.89
0.27	1.97
0.30	2.05



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.823	3.117
a_2 [mm/(MN ² /m ⁴)]	1.501	-0.95
E_v [MN/m ²][Mpa]	77.3	198.6
E_{v2}/E_{v1}	2.57	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 139.2 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (454+900) to (455+000) level (-1.50)
PLATE LOAD NO. PLT-33
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 10:00 AM
TIME FINISH: 12:00 PM
DATE 30-Mar-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.20
0.06	0.41
0.09	0.62
0.12	0.85
0.15	1.07
0.18	1.30
0.21	1.53
0.24	1.76
0.27	1.98
0.30	2.21
0.27	2.11
0.21	1.94
0.15	1.77
0.09	1.60
0.03	1.43
0.00	1.26
0.03	1.35
0.06	1.44
0.09	1.53
0.12	1.62
0.15	1.71
0.18	1.79
0.21	1.87
0.24	1.95
0.27	2.03
0.30	2.11



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	7.133	3.117
a_2 [mm/(MN ² /m ⁴)]	1.061	-0.95
E_v [MN/m ²][Mpa]	75.5	198.6
E_{v2}/E_{v1}	2.63	



MODULUS OF SUB-GRADE REACTION, K_s

$$k_s = \Delta\sigma/\Delta s \quad 135.2 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+000) to (455+100) level (-1.50)
PLATE LOAD NO. PLT-34
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 12:00 PM
TIME FINISH: 2:00 PM
DATE 30-Mar-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.19
0.06	0.39
0.09	0.60
0.12	0.82
0.15	1.05
0.18	1.26
0.21	1.48
0.24	1.71
0.27	1.93
0.30	2.16
0.27	2.06
0.21	1.89
0.15	1.72
0.09	1.55
0.03	1.38
0.00	1.21
0.03	1.30
0.06	1.39
0.09	1.48
0.12	1.57
0.15	1.66
0.18	1.74
0.21	1.82
0.24	1.90
0.27	1.98
0.30	2.06



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.896	3.117
a_2 [mm/(MN ² /m ⁴)]	1.269	-0.95
E_v [MN/m ²][Mpa]	77.3	198.6
E_{v2}/E_{v1}	2.57	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 138.4 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+100) to (455+200) level (-1.50)
PLATE LOAD NO. PLT-35
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 2:00 PM
TIME FINISH: 4:00 PM
DATE 30-Mar-23
TESTED BY : Ashraf Hanafy
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.44
0.09	0.69
0.12	0.94
0.15	1.16
0.18	1.39
0.21	1.63
0.24	1.86
0.27	2.10
0.30	2.33
0.27	2.23
0.21	2.05
0.15	1.87
0.09	1.69
0.03	1.51
0.00	1.33
0.03	1.42
0.06	1.51
0.09	1.60
0.12	1.69
0.15	1.78
0.18	1.87
0.21	1.96
0.24	2.05
0.27	2.14
0.30	2.23



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	8.044	3
a_2 [mm/(MN ² /m ⁴)]	-0.641	0
E_v [MN/m ²][Mpa]	71.6	187.5
E_{v2}/E_{v1}	2.62	



MODULUS OF SUB-GRADE REACTION, K_s

$$k_s = \Delta\sigma/\Delta s \quad 128.0 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+200) to (455+300) level (-1.50)
PLATE LOAD NO. PLT-36
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 8:00 AM
TIME FINISH: 10:00 AM
DATE 30-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.43
0.09	0.66
0.12	0.90
0.15	1.14
0.18	1.38
0.21	1.62
0.24	1.86
0.27	2.09
0.30	2.33
0.27	2.24
0.21	2.06
0.15	1.88
0.09	1.70
0.03	1.52
0.00	1.34
0.03	1.44
0.06	1.54
0.09	1.63
0.12	1.72
0.15	1.81
0.18	1.90
0.21	1.99
0.24	2.08
0.27	2.17
0.30	2.25



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	7.684	3.241
a_2 [mm/(MN ² /m ⁴)]	0.622	-0.702
E_v [MN/m ²][Mpa]	71.5	185.6
E_{v2}/E_{v1}	2.60	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 128.8 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+300) to (455+400) level (-1.50)
PLATE LOAD NO. PLT-37
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 10:00 AM
TIME FINISH: 12:00 PM
DATE 30-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.20
0.06	0.42
0.09	0.63
0.12	0.83
0.15	1.04
0.18	1.25
0.21	1.46
0.24	1.67
0.27	1.88
0.30	2.10
0.27	2.00
0.21	1.83
0.15	1.66
0.09	1.49
0.03	1.32
0.00	1.15
0.03	1.23
0.06	1.31
0.09	1.39
0.12	1.47
0.15	1.55
0.18	1.63
0.21	1.72
0.24	1.81
0.27	1.90
0.30	1.99



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.932	2.531
a_2 [mm/(MN ² /m ⁴)]	0.219	0.868
E_v [MN/m ²][Mpa]	80.4	201.5
E_{v2}/E_{v1}	2.51	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 142.4 MN/m³


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+400) to (455+500) level (-1.50)
PLATE LOAD NO. PLT-38
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 12:00 PM
TIME FINISH: 2:00 PM
DATE 30-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031


**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.20
0.06	0.38
0.09	0.56
0.12	0.75
0.15	0.93
0.18	1.12
0.21	1.30
0.24	1.49
0.27	1.69
0.30	1.89
0.27	1.80
0.21	1.66
0.15	1.52
0.09	1.38
0.03	1.24
0.00	1.10
0.03	1.17
0.06	1.24
0.09	1.31
0.12	1.38
0.15	1.45
0.18	1.52
0.21	1.59
0.24	1.66
0.27	1.72
0.30	1.79



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	5.816	2.381
a_2 [mm/(MN ² /m ⁴)]	1.268	-0.255
E_v [MN/m ²][Mpa]	90.8	244.1
E_{v2}/E_{v1}	2.69	



MODULUS OF SUB-GRADE REACTION, K_s

$$k_s = \Delta\sigma / \Delta s \quad 159.2 \quad \text{MN/m}^3$$


Plate Load Tests of Soils
DIN 18134

CLIENT شركة الحسن
PROJECT Electric Express Train
LOCATION Al-dabaa (455+500) to (455+600) level (-1.50)
PLATE LOAD NO. PLT-39
PLATE DIAMETER (cm) 75.00
TYPE OF SOIL Silty SAND with gravel

TIME START: 2:00 PM
TIME FINISH: 4:00 PM
DATE 30-Mar-23
TESTED BY : Mohamed Issa
LAB. REF. 11031

**** Note : Soil is Wet**

Stress MN/m ²	Settlement mm
0.00	0.00
0.03	0.21
0.06	0.42
0.09	0.61
0.12	0.82
0.15	1.02
0.18	1.21
0.21	1.42
0.24	1.60
0.27	1.81
0.30	2.02
0.27	1.93
0.21	1.77
0.15	1.61
0.09	1.45
0.03	1.29
0.00	1.13
0.03	1.20
0.06	1.27
0.09	1.34
0.12	1.41
0.15	1.48
0.18	1.55
0.21	1.62
0.24	1.71
0.27	1.81
0.30	1.89



STRAIN MODULUS, E_v

	1 st loading	2 st loading
σ_{0max}	0.30	0.30
a_1 [mm/(MN/m ²)]	6.733	2.077
a_2 [mm/(MN ² /m ⁴)]	-0.191	1.442
E_v [MN/m ²][Mpa]	84.3	224.1
E_{v2}/E_{v1}	2.66	



MODULUS OF SUB-GRADE REACTION, K_s

$k_s = \Delta\sigma/\Delta s$ 148.0 MN/m³