

السيد المهندس / رئيس قطاع التنفيذ والمناطق

تحية طيبة وبعد ،،،،

بالاحالة الى مشروع تنفيذ اعمال الجسر الترابى والاعمال الصناعية لمشروع القطر الكهربائى السريع بطول ١ كم

نتشرف بان نرفق لسيادتكم طيه المقاييس المعدلة بعد اعتماد لجنة المفاوضة للقطاعات الاتية :-

م	اسم الشركة	من المحطة	الى المحطة	اتجاه
١	جمعة بدر نوح للمقاولات	٥٦٢,٠٠٠	٥٦٧,٧٥٧,٠٠٠	سيدى برانى

برجاء من سيادتكم التفضل بالاحاطة والتوجيه باللازم

وتفضلوا بقبول فائق الاحترام ،،،،

رئيس الادارة المركزية

منطقة غرب الدلتا

(بالاسكندرية/ مرسى مطروح)

٢٠٢٤
١٢
٨
عميد مهندس / " هانى محمد محمود طه "




مشروع القطار الكهربائي السريع					
المقاييس التقديرية المعدلة طبقاً للمفاوضة لاستكمال تنفيذ الجسر الترابي بمشروع القطار الكهربائي السريع للقطاع السابع (فوكه - مطروح) - شركة جمعه بدر-المسافة من الكم 562+000 إلى الكم 567+757 بطول 5.75 كم - اتجاه سيدي براني					
رقم البند	بيان الأعمال	الوحدة	الكمية	الغلة	الاجمالي
1	أعمال الحفر				
1-2	بالمتر المكعب أعمال حفر باستخدام المعدات الميكانيكية في التربة المتناسكة عدا التربة الصخرية (باستخدام البلدوزر) وتسوية السطح بالآلات الترسوية والرشش بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى أقصى كثافة جافة (95% من الكثافة الجافة القصوى) ومحمل على البند تحميل ونقل التربة الزائدة لمسافة 500 متر من محور الطريق ويتم التنفيذ طبقاً للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقاً لوصول الصناعة ومواصفات الهيئة العامة للطرق والكبارى وتعليمات المهندس المشرف. يتم احتساب علاوة 1 جنيه لكل 1 كم بالزيادة.	م3	12000.00		
1-3	السعر في شهر مايو (2023) طبقاً للمفاوضة	م3	12000.00	30.50	366,000
1-3	و محمل على البند الآتي: 1- تحميل ونقل تاج الحفر لمسافة لا تقل عن 500 متر 2- توريد التربة مطابقة للمواصفات وتشغيلها باستخدام آلات التسوية بسمك لا يزيد عن 25 سم لاستكمال المنسوب التصميمي لتشكل الجسر والاكتاف (نسبة تحمل كاليفورنيا لا تقل عن 10%) ورشها بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى أقصى كثافة جافة (95% من الكثافة الجافة القصوى). ويتم التنفيذ طبقاً للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقاً لوصول الصناعة ومواصفات الهيئة العامة للطرق والكبارى وتعليمات المهندس المشرف.		58701.70		
1-3-1	السعر في شهر يناير (2023) طبقاً للمفاوضة		12111.10	89.50	1,083,943
1-3-2	السعر في شهر مارس (2023) طبقاً للمفاوضة	ذات اتجاه (300-400)	7414.90	99.90	740,749
1-3-3	السعر في شهر مايو (2023) طبقاً للمفاوضة		35132.80	100.70	3,537,873
1-3-9	السعر ابتداء من 22 مارس (2024) حتى شهر نوفمبر (2024) طبقاً للمفاوضة	ذات اتجاه (100-200)	4042.90	71.60	289,472
3	أعمال الردم				
3-1	بالمتر المكعب أعمال توريد وتشغيل اترية صالحة للردم و مطابقة للمواصفات والتشغيل باستخدام آلات التسوية بسمك لا يزيد عن 50 سم حتى منسوب -2 متر و بسمك لا يزيد عن 25 سم لاستكمال المنسوب التصميمي لتشكل الجسر والاكتاف (نسبة تحمل كاليفورنيا لا تقل عن 15%) ورشها بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد بالهراسات للوصول الى أقصى كثافة جافة (95% من الكثافة الجافة القصوى) ويتم التنفيذ طبقاً للمناسيب التصميمية والقطاعات العرضية النموذجية والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقاً لوصول الصناعة ومواصفات الهيئة العامة للطرق والكبارى وتعليمات المهندس المشرف. -في حالة طلب جهاز الإشراف زيادة نسبة الدمك عن 95% وحسب زيادة 1 جنيه على زيادة نسبة الدمك لكل 1% -مسافة النقل 2 كم ويتم احتساب علاوة 1.5 جنيه لكل 1 كم بالزيادة أو النقصان -السعر يشمل عمل تشوينات وتخليط واختبارات ونقل لموقع العمل حتى مسافة 2 كم -السعر يشمل قيمة المادة المحجيرة طبقاً لافادة المنطقة بهذا القطاع (7) من الكم 504 إلى 568 علاوة مسافة النقل 216 كم علاوة تحصيل رسوم الكارثة والموازن طبقاً للائحة الشركة الوطنية	م3	496658.33		
3-1-1	السعر في شهر ابريل (2023) طبقاً للمفاوضة	م3	496658.33	321.00	159,427,322
3-1-2	السعر في شهر مايو (2023) طبقاً للمفاوضة	م3	470663.93	101.40	47,725,322

مدير عام المشروعات
م / محمد حسني فياض

مدير المشروع (الهيئة)
م / إبراهيم عبدالله الحناوي

مهندس موقع الهيئة
م / مؤمن محمد سرور

مدير المشروع المقاول
م / عمرو عبدالوهاب





مشروع القطار الكهربائي السريع

المقاسة التقديرية المعدلة طبقا للمفاوضة لاستكمال تنفيذ الجسر الترابي، بمشروع القطار الكهربائي السريع للقطاع السابع (فوكه - مطروح) - شركة جمعه بدر- المسافة من الكم 562+000 إلى الكم 567+757 بطول 5.75 كم - اتجاه سيدى برانى

رقم البند	بيان الأعمال	الوحدة	الكمية	القيمة	الإجمالي
4	طبقات الأساس				
4-1	بالمتر المكعب أعمال توريد وفرش طبقة تاسيس (prepared Subgrade) من الأحجار الصلبة المترججة ناتج تكسير الكسرات والمطابقة للمواصفات وأقصى حجم للجبيبات 100 مم والا يزيد نسبة المار من منخل 200 عن 12 % و التدرج الوارد بالاشتراطات الخاصة بالمشروع لا تقل نسبة تحمل كاليفورنيا عن 25 % والا يزيد نسبة الغدق بجهاز لوس انجلوس عن 30 % والا يزيد الامتصاص عن 15% والا يقل معامل المرونة (Ev2) من تجربة لوح التحميل 80 ميجاباسكال ويتم فردها على طبقتين باستخدام الات التسوية الحديثة على ان لا يزيد سمك الطبقة بعد تمام الدمك عن 25 سم و رشها بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد للهراسات للوصول الى أقصى كثافة جافة قصوي (لا تقل عن 95 %) من الكثافة العملية والفة تشمل اجراء التجارب المعملية والحقلية ويتم تنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا للمواصفات الفنية للمشروع وتقرير الاستشاري وتعليمات المهندس المشرف -مسافة النقل لا تقل عن 20 كم - يتم احتساب علاوة 1.3 جنيه لكل 1 كم بالزيادة او النقصان	3م	39100.00		
	قيمة المادة المحجيرة بمشتملاتها	3م	39100.00	161.00	6,295,100
	علاوة مسافة النقل 100 كم	3م	39100.00	104.00	4,066,400
	علاوة تحصيل رسوم الكارتة والموازين طبقا للائحة الشركة الوطنية	3م	39100.00	25.00	977,500
4-1-1	السعر في شهر ابريل (2023) طبقا للمفاوضة	3م	3274.70	144.90	474,504
4-1-2	السعر في شهر مايو (2023) طبقا للمفاوضة	3م	35825.30	146.40	5,244,824
4-2	بالمتر المكعب أعمال توريد وفرش طبقة أساس من الاحجار الصلبة المترججة ناتج تكسير الكسرات والمطابقة للمواصفات وأقصى حجم للجبيبات ما بين 31.5 مم الى 40 مم والا يزيد نسبة المار من منخل 200 عن 5% والتدرج الوارد بالاشتراطات الخاصة بالمشروع لا تقل نسبة تحمل كاليفورنيا عن 80 % والا يقل معامل المرونة (Ev2) من تجربة لوح التحميل 120 ميجاباسكال والا يزيد نسبة الغدق بجهاز لوس انجلوس عن 30 % والا يزيد الامتصاص عن 15 % ويتم فردها على طبقتين باستخدام الات التسوية الحديثة على ان لا يزيد سمك الطبقة بعد تمام الدمك عن 20 سم و رشها بالمياه الاصولية للوصول الى نسبة الرطوبة المطلوبة والدمك الجيد للهراسات للوصول الى أقصى كثافة جافة قصوي (لا يقل عن 100%) من الكثافة العملية والفة تشمل اجراء التجارب المعملية والحقلية ويتم تنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا للمواصفات الفنية للمشروع وتقرير الاستشاري وتعليمات المهندس المشرف -مسافة النقل لا تقل عن 20 كم - يتم احتساب علاوة 1.3 جنيه لكل 1 كم بالزيادة او النقصان	3م	48169.00		
	قيمة المادة المحجيرة بمشتملاتها	3م	48169.00	175.00	8,429,575
	علاوة مسافة النقل 270 كم	3م	48169.00	325.00	15,654,925
	علاوة تحصيل رسوم الكارتة والموازين طبقا للائحة الشركة الوطنية	3م	48169.00	25.00	1,204,225
4-2-1	السعر في شهر مايو (2023) طبقا للمفاوضة	3م	48169.00	151.30	7,287,970
5	البلطات الخرسانية				
5-1	بالمتر المصطح أعمال توريد وصب خرسانة عادية سمك 15 سم لحماية الإكثاف والميول الجانبية تتكون من 0.8 م 3م سن دولوميت متدرج + 0.4 م 3م رمل حرش + 280 كجم أسمنت بورتلاندي عادي وإضافة Fiber reinforcement على أن يكون السن نظيف ومغسول والرمل خالي من الشوائب والطفلة والأملاح والمواد الغريبة والبند يشمل تجهيز واستبدال مناسيب التربة الطبيعية أسفل البلاطة للوصول إلى المناسيب التصميمية على أن تحقق الخرسانة إجهاد لا يقل عن 250 كجم / 2م وتنشيط السطح والتنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا للمواصفات الفنية العامة للطرق والكباري وتعليمات المهندس المشرف .	2م	107781.28		
5-1-1	السعر في شهر مايو (2023) طبقا للمفاوضة	2م	107781.28	457.00	49,256,045
5-2	بالمتر المكعب أعمال توريد وصب خرسانة عادية تتكون من 0.8 م 3م سن دولوميت متدرج + 0.4 م 3م رمل حرش + 280 كجم أسمنت بورتلاندي عادي على أن يكون السن نظيف ومغسول والرمل خالي من الشوائب والطفلة والأملاح والمواد الغريبة والبند يشمل تجهيز واستبدال مناسيب التربة الطبيعية أسفل القدمة للوصول إلى المناسيب التصميمية على أن تحقق الخرسانة إجهاد لا يقل عن 250 كجم / 2م وتنشيط السطح والتنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا للمواصفات الفنية العامة للطرق والكباري وتعليمات المهندس المشرف .	3م	15202.80		
5-2-1	السعر في شهر مايو (2023) طبقا للمفاوضة	3م	15202.80	2,665.20	40,518,503
6	أعمال التربة المسلحة				
6-1	بالمتر المصطح توريد وتركيب طبقة من التسيج الصناعي جيوجريد مستورد التداخل لا يقل عن 10% و يتم التنفيذ طبقا لاصول الصناعة والرسومات التفصيلية المعتمدة والبند بجميع مشتملاته طبقا للمواصفات الفنية العامة للطرق والكباري . ذات قوة شد 30 ك . نيوتن في الاتجاهين Biaxial	2م	6496.10	37.00	240,356
	الإجمالي				361,900,000.0000
	(فقط ثلاثمائة وواحد وستون مليوناً وتسعمائة ألف جنيه مصري لا غير)				

مدير عام المشروعات
م / محمد حسني فياض

مدير المشروع (الهيئة)
م / إبراهيم عبدالله الحناوي

مهندس موقع الهيئة
م / مؤمن محمد سرور


مدير المشروع المقاول
م / عمرو عبدالوهاب

رئيس الإدارة المركزية
منطقة غرب الدلتا

الاسكندرية - مرسى مطروح

عميد - مهندس /

" هانى محمد محمود طه "



MATERIAL APPROVAL REQUEST

المشروع
للمسحور والمباني
(GARBIT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ. د. خالد شنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Refrence	GB63-147																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 16/8/2023	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td>16</td> <td>8</td> <td>2023</td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM				16	8	2023			
C1	C2	C3	DD	MM	YY	HH	MM													
			16	8	2023															

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

REPLACEMENT FILL MATERIAL RESULTS						
Description of Materials	564+600 TO 564+680 (-14.5)					
Location to be Used	564+600 TO 565+680 (-14)					
MAR Approval No		Date				
Supplier Name						
Test Requirement		Specification		Clause		
Reference Photos	Yes attached / No	Other				
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M^3	5000	14/8/2023		
2	Atterberg Limits	M^3	5000	14/8/2023		
3	Proctor	M^3	5000	15/8/2023		
6	CBR	M^3	5000	16/8/2023		
Comments by:			Comments by:			
			Test results for Estimated quantities of about 5000 m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>		
QA/QC *	<i>Abdullah SAMY</i>	<i>Abdullah</i>		
GARB**				
Employers Representative				

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

الهيئة العامة
للمطرق والكباري والسبل المائية
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ. د. خالد هادي



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-148	خطة تدقيق نوع للمطروقات المقترحة ودراسة أرصفة الجسر والمخارج المبرولة																		
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 20/8/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

REPLACEMENT FILL MATERIAL RESULTS						
Description of Materials						
Location to be Used		564+600 TO 564+680 (-13.5) 564+600 TO 564+670 (-13)				
MAR Approval No					Date	
Supplier Name						
Test Requirement		Specification			Clause	
Reference Photos		Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M ³	4700	19/7/2024		
2	Atterberg Limits	M ³	4700	19/7/2024		
3	Proctor	M ³	4700	20/8/2024		
4	CBR	M ³	4700	20/8/2024		
Comments by:			Comments by:			
			Test results for Estimated quantities of about 4700 m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A - AWC - R		
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	20-8-2024	A		
QA/QC *	<i>Ahmed Abo Zaid</i>	<i>[Signature]</i>	20-8-2024	A		
GARB**			20-8-2024	A		
Employers Representative						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب الاستشاري والهندسي
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري والهندسي
أ. د. خالد فاضل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-Emb-149																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign Ahmed Fouad	Date 26/8/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	- FILL MATERIAL RESULTS					
Location to be Used	564+600 TO 564+700 (-12.5) 564+670 TO 564+700 (-13) 564+600 TO 564+640 (-12)					
MAR Approval No					Date	
Supplier Name						
Test Requirement		Specification			Clause	
Reference Photos	Yes attached / No	Other				
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M^3	4936	24/7/2024		
2	Atterberg Limits	M^3	4936	24/7/2024		
3	Proctor	M^3	4936	25/8/2024		
4	CBR	M^3	4936	26/8/2024		
Comments by:		Comments by:				
		Test results for Estimated quantities of about 4936m3				
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	ENG/ AHMED FOUAD	Ahmed Fouad				
QA/QC *	Abdullah SAMY	Abdullah				
GARB**			26-8-2024			
Employers Representative						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب العامة
للمواد والكباري والنقل البري
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63 - Emb-150																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 14/9/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS					
Location to be Used	564+600 TO 564+700 (-11.5) 564+640 TO 564+700 (-12)					
MAR Approval No						Date
Supplier Name						
Test Requirement	Specification					Clause
Reference Photos	Yes attached / No		Other			
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M ³	4150	13/9/2024		
2	Atterberg Limits	M ³	4150	13/9/2024		
3	Proctor	M ³	4150	13/9/2024		
4	CBR	M ³	4150	14/9/2024		
Comments by:			Comments by:			
			Test results for Estimated quantities of about 4150m ³			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	14/9/2024	A		
QA/QC *	<i>Abdallah SANY</i>	<i>Abdallah</i>	14/9/2024	A		
GARB **	Eng/hussin Fouad	<i>Hussin</i>	14/9/2024	A		
Employers Representative						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

الهيئة العامة
لنقل و البنية التحتية
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ. د. خالد فايز



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63- Emb-151																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 21/9/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	564+600 TO 564+720 (-11) 564+600 TO 564+670 (-10.5)				
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M ³	5000	21/9/2024	
2	Atterberg Limits	M ³	5000	21/9/2024	
3	Proctor	M ³	5000	21/9/2024	
4	CBR	M ³	5000	21/9/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 5000m3			

APPROVAL STATUS				
Organisation	Name	Sign	Date	A-AWC-R
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	21/9/2024	A
QA/QC *			21/9/2024	A
GARB**	Eng/hussin Fouad	<i>Hussin Fouad</i>	21/9/2024	A
Employers Representative				

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب الاستشاري والهندسي
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري والهندسي
أ.د. خالد شنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																
Contractor Reference	GB63-Emb-152																		
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 22/9/2024	Time															
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM												

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS					
Location to be Used	564+670 TO 564+720 (-10.5) 564+600 TO 564+720 (-10) 564+600 TO 564+630 (-9.5)					
MAR Approval No				Date		
Supplier Name						
Test Requirement		Specification		Clause		
Reference Photos	Yes attached / No	Other				
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M ³	5000	20/9/2024		
2	Atterberg Limits	M ³	5000	20/9/2024		
3	Proctor	M ³	5000	20/9/2024		
4	CBR	M ³	5000	22/9/2024		
Comments by:			Test results for Estimated quantities of about 5000m ³			

APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	22/9/2024	A	
QA/QC *	<i>Abdullah SAMY</i>	<i>Abdullah</i>	22/9/2024	A	
GARB**	Eng/hussin Fouad	<i>Hussin</i>	22/9/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب العامة
للمسحور و الكبارى و الجسور
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشارى الهندسى
أ. د. خالد شاذل



Contractor Company	GOMAA BADER COMPANY		Designer Company	
Contractor Reference	GB63- Emb-53			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 26/9/2024	Time
Received by ER				

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	564+030 TO 564+720 (-9.5) 564+600 TO 564+720 (-9)				
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M^3	5000	25/9/2024	
2	Atterberg Limits	M^3	5000	25/9/2024	
3	Proctor	M^3	5000	25/9/2024	
4	CBR	M^3	5000	26/9/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 5000m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	26/9/2024	A	
QA/QC *	<i>Omar Yousef</i>	<i>Omar Yousef</i>	26/9/2024	A	
GARB**	Eng/hussin Fouad	<i>Hussin Fouad</i>	26/9/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب الاستشاري
للطرق والكباري و
المتن المتري
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ. د. خالد قنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-Emb-54																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 28/9/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM									
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS					
Location to be Used	564+700 TO 564+740 (-9) 564+600 TO 564+740 (-8.5)					
MAR Approval No				Date		
Supplier Name						
Test Requirement		Specification		Clause		
Reference Photos	Yes attached / No	Other				
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M ³	3700	27/9/2024		
2	Atterberg Limits	M ³	3700	27/9/2024		
3	Proctor	M ³	3700	27/9/2024		
4	CBR	M ³	3700	28/9/2024		
Comments by:		Comments by: Test results for Estimated quantities of about 3700m ³				
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	28/9/2024	A		
QA/QC *	<i>omar youssef</i>	<i>omar youssef</i>	28/9/2024	A		
GARB**	Eng/hussin Fouad	<i>Hussin</i>	28/9/2024	A		
Employers Representative						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب العامة
للمسحور و الكبارى و الجسر
(GARBLT)



ENGINEERING CONSULTING OFFICE
المصالح الاستشارى الهندسى
أ. د. خالد شحاته



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Refrence	GB63-155																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 29/9/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	REPLACEMENT FILL MATERIAL RESULTS				
Location to be Used	563+380 TO 563+460 (-1) 563+380 TO 563+460 (-.75)				
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M³	1400	28/9/2024	
2	Atterberg Limits	M³	1400	28/9/2024	
3	Proctor	M³	1400	28/9/2024	
4	CBR	M³	1400	29/9/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 1400m³			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	29/9/2024	A	
QA/QC *	<i>Hassan</i>	<i>Hassan</i>	29/9/2024	A	
GARB**	Eng/hussin Fouad		29/9/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

المكتب الاستشاري
للمسحور والكباري
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-EMB-156																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 2/10/2024	Time																
Received by ER			MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													


CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	563+380 TO 563+460 (-0.5) & 563+380 TO 563+460 (-0.25) 564+380 TO 563+391.4 (0) & 563+391.4 TO 563+438.6 (-.10) 563+438.6 TO 563+460 (0)				
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M ³	1500	1/10/2024	
2	Atterberg Limits	M ³	1500	1/10/2024	
3	Proctor	M ³	1500	1/10/2024	
4	CBR	M ³	1500	2/10/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 1500m ³			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	2/10/2024	A	
QA/QC *	<i>Abdullah SAMY</i>	<i>Abdullah</i>	2/10/2024	A	
GARB**	Eng/hussin Fouad		2/10/2024	A	
Employers Representative					



* Designer

** Alignment / Bridges: Culvert Only



**MATERIAL
INSPECTION
REQUEST**





Contractor Company	GOMAA BADER COMPANY			Designer Company			
Contractor Reference	GB63-EMB-157						
Issued by Contractor	Name	Sign	Date	3/10/2024	Time		
	Eng/ AHMED FOUAD						
Received by ER			MIR	C1	C2	C3	DD

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials		FILL MATERIAL RESULTS				
Location to be Used		564+600 TO 564+760 (-8) 564+600 TO 564+670 (-7.5)				
MAR Approval No					Date	
Supplier Name						
Test Requirement		Specification			Clause	
Reference Photos		Yes attached / No			Other	
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M^3	5000	2/10/2024		
2	Atterberg Limits	M^3	5000	2/10/2024		
3	Proctor	M^3	5000	2/10/2024		
4	CBR	M^3	5000	3/10/2024		
Comments by:			Comments by:			
			Test results for Estimated quantities of about 5000m3			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	ENG/ AHMED FOUAD		3/10/2024	A		
QA/QC *	Abdullah SAMY		3/10/2024	A		
GARB**	Eng/hussin Fouad		3/10/2024	A		
Employers Representative						

* Designer
 ** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST		الهيئة العامة للمطرق والكبارى و (GARBLT)		 ENGINEERING CONSULTING OFFICE المكتب الاستشارى الهندسى أ. د. خالد شادي	 SVSRA SHAKER

Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-EMB-158																			
Issued by Contractor	Name	Sign	Date	Time																
	Eng/ AHMED FOUAD	Ahmed Fouad	4/10/2024																	
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE-2	Work Activity		
CODE-3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	564+670 TO 564+760 (-7.5) 564+600 TO 564+760 (-7)				
MAR Approval No		Date			
Supplier Name					
Test Requirement		Specification	Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M^3	5000	3/10/2024	
2	Atterberg Limits	M^3	5000	3/10/2024	
3	Proctor	M^3	5000	3/10/2024	
4	CBR	M^3	5000	4/10/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 5000m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	Ahmed Fouad	4/10/2024	A	
QA/QC *	Abdallah SAMY	Abdallah	4/10/2024	A	
GARB**	Eng/hussin Fouad		4/10/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

الممسوحة ضوئياً بـ CamScanner

MATERIAL INSPECTION REQUEST

المكتب العامة
للمطرق والكباري والسبل البري
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ. د. خالد شاذلي



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB66-162																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 24/11/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>M</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	M	YY	HH	MM									
C1	C2	C3	DD	M	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2		Work Activity	
CODE - 3		Sub Element of Activity	

Description of Materials	REPLACEMENT FILL MATERIAL RESULTS				
Location to be Used	564+560 & 564+630 (-4) & 564+630 & 564+780 (-4) 564+560 & 564+630 (-3.5)				
MAR Approval No		Date			
Supplier Name					
Test Requirement		Specification	Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M ³	4940	23/11/2024	
2	Atterberg Limits	M ³	4940	23/11/2024	
3	Proctor	M ³	4940	23/11/2024	
4	CBR	M ³	4940	24/11/2024	
Comments by:		Comments by: Test results for Estimated quantities of about 4940 m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>	24/11/2024	A	
QA/QC *		<i>mom en</i>	24/11/2024	A	
GARB**			24/11/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST

المكتب الاستشاري
للطرق والكباري و
المشاة البرية
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد شحيد



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-SG-23																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign	Date 8/10/2024	Time																
Received by ER			MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM								
C1	C2	C3	DD	MM	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	FILL MATERIAL RESULTS				
Location to be Used	563+380 TO 563+391.4 (0.25) & 563+391.4 TO 563+438.6 (0.1) by cement 563+380 TO 563+391.4 (0.5) & 563+391.4 TO 563+438.6 (0.3) by cement 563+438.6 TO 563+460 (0.25) & 563+391.4 TO 563+438.6 (0.5) by cement 563+438.6 TO 563+460 (0.5)				
MAR Approval No			Date		
Supplier Name					
Test Requirement		Specification	Clause		
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M ³	1000	7/10/2024	
2	Atterberg Limits	M ³	1000	7/10/2024	
3	Proctor	M ³	1000	7/10/2024	
4	CBR	M ³	1000	8/10/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 1000m ³			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD		8/10/2024	A	
QA/QC *			8/10/2024	A	
GARB**	ENG / HUSSIN FOUAD		8/10/2024	A	
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST

الهيئة العامة
للمطرق والكباري والجسور
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-SG-22		Date 30/7/2024	Time																
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>																		
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td>30</td> <td>7</td> <td>2024</td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM				30	7	2024			
C1	C2	C3	DD	MM	YY	HH	MM													
			30	7	2024															

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

REPLACEMENT FILL MATERIAL RESULTS						
Description of Materials		562+350 TO 562+440 (0.5+)				
Location to be Used		562+340 TO 562+350 (0.5+)				
		562+340 TO 562+350 (0.25+)				
MAR Approval No						Date
Supplier Name						Clause
Test Requirement						Specification
Reference Photos						Other
Yes attached / No						
Item	Description	Unit	Quantity	Arrival Date	Note	
1	Seive Analysis	M ³	1000	29/7/2024		
2	Atterberg Limits	M ³	1000	29/7/2024		
3	Proctor	M ³	1000	30/8/2024		
4	CBR	M ³	1000	30/8/2024		
Comments by:			Comments by:			
			Test results for Estimated quantities of about 1000m ³			
APPROVAL STATUS						
Organisation	Name	Sign	Date	A-AWC-R		
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>				
QA/QC *	<i>Abdelrahman SAHAY</i>	<i>Abdelrahman</i>				
GARB**						
Employers Representative						

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST

المكتب العامة
للمطرق والكباري و
الأنفاق (GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-SG-21																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date 1/8/2024	Time																
Received by ER		MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>MM</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td>1</td> <td>8</td> <td>2024</td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM				1	8	2024			
C1	C2	C3	DD	MM	YY	HH	MM													
			1	8	2024															

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

REPLACEMENT FILL MATERIAL RESULTS					
Description of Materials	562+350 TO 562+440 (0.25+)				
Location to be Used					
MAR Approval No					Date
Supplier Name					
Test Requirement	Specification				Clause
Reference Photos	Yes attached / No	Other			
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M ³	500	31/7/2024	
2	Atterberg Limits	M ³	500	31/7/2024	
3	Proctor	M ³	500	1/8/2024	
6	CBR	M ³	500	1/8/2024	
Comments by:			Comments by:		
			Test results for Estimated quantities of about 500m ³		
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>			
QA/QC *	<i>Abdallah SAMY</i>	<i>Abdallah</i>			
GARB**					
Employers Representative					

* Designer


** Alignment / Bridges: Culvert Only

MATERIAL INSPECTION REQUEST

الهيئة العامة
للمنشآت والكباري والجسور
(GARBLT)

ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد قنديل

SHAKER
SVSTRA

Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-SB-22																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign <i>Ahmed Fouad</i>	Date : 17/10/2024	Time																
Received by ER			MIR	<table border="1"> <tr> <td>C1</td> <td>C2</td> <td>C3</td> <td>DD</td> <td>M</td> <td>YY</td> <td>HH</td> <td>MM</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	M	YY	HH	MM								
C1	C2	C3	DD	M	YY	HH	MM													

CODE - 1	S1 to S21 Station Reference	D1 to S3 Depot Reference	Kp XXX Note For Kilometer point only Start Km is used
CODE - 2	Work Activity		
CODE - 3	Sub Element of Activity		

Description of Materials	SUBBALLAST				
Location to be Used	563+391.4 TO 563+438.6 (0.7) By Cement 563+391.4 TO 563+438.6 (0.9) By Cement 563+340 TO 563+391.4 (0.7) & 563+320 TO 563+391.4 (0.9) 563+438.6 TO 563+500 (0.7) & 563+438.6 TO 563+500 (0.9)				
MAR Approval No		Date			
Supplier Name		Specification	Clause		
Test Requirement		Other			
Reference Photos	Yes attached / No				
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M^3	1000	16/10/2024	
2	Atterberg Limits	M^3	1000	16/10/2024	
3	Proctor	M^3	1000	16/10/2024	
4	Water Absorption	M^3	1000	17/10/2024	
5	Lo: Angelos	M^3	1000	17/10/2024	
6	CBR	M^3	1000	17/10/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 1000 m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	<i>Ahmed Fouad</i>			
QA/QC *		<i>monen</i>	20-10-24		
GARB**					
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only

MATERIAL APPROVAL REQUEST

المكتب العامة
للمحاور و الكباري و الجسور
(GARBLT)



ENGINEERING CONSULTING OFFICE
المكتب الاستشاري الهندسي
أ.د. خالد فتوح



Contractor Company	GOMAA BADER COMPANY		Designer Company																	
Contractor Reference	GB63-SB-21																			
Issued by Contractor	Name Eng/ AHMED FOUAD	Sign Ahmed Fouad	Date 1/8/2024	Time																
Received by ER			MIR	<table border="1"> <tr> <th>C1</th> <th>C2</th> <th>C3</th> <th>DD</th> <th>MM</th> <th>YY</th> <th>HH</th> <th>MM</th> </tr> <tr> <td></td> <td></td> <td></td> <td>1</td> <td>8</td> <td>2024</td> <td></td> <td></td> </tr> </table>	C1	C2	C3	DD	MM	YY	HH	MM				1	8	2024		
C1	C2	C3	DD	MM	YY	HH	MM													
			1	8	2024															

CODE-1	S1 to S21 Station Reference	D1 to S3 Depot Reference Work Activity	Kp XXX Note For Kilometer point only Start Km is used
CODE-2			
CODE-3	Sub Element of Activity		

Description of Materials		SUBBALLAST			
Location to be Used		562+340 TO 562+440 (0.9+) & 562+340 TO 562+440 (0.7+) 563+340 TO 562+500 (0.7+) & 563+320 TO 562+500 (0.9+)			
MAR Approval No		Date			
Supplier Name					
Test Requirement		Specification		Clause	
Reference Photos		Yes attached / No		Other	
Item	Description	Unit	Quantity	Arrival Date	Note
1	Seive Analysis	M^3	1600	30/7/2024	
2	Atterberg Limits	M^3	1600	31/7/2024	
3	Proctor	M^3	1600	1/8/2024	
6	CBR	M^3	1600	1/8/2024	
Comments by:		Comments by:			
		Test results for Estimated quantities of about 1600m3			
APPROVAL STATUS					
Organisation	Name	Sign	Date	A-AWC-R	
Contractor	ENG/ AHMED FOUAD	Ahmed Fouad			
QA/QC *	omar youssef	omar youssef			
GARB**					
Employers Representative					

* Designer

** Alignment / Bridges: Culvert Only